

INDIAN BANK , Proposed New Branch, in new Bldg on First Fl. Plot no 50/1, Bachharaj Rd; at Wardha, Nagpur.

Interior Work at first floor + ATM.						26th Feb 2019
Sr.no	Discription	Qty.	Unit	Rate	Amount	
1	Providing and constructing Full / half height / Wicket gate / partition in Banking hall using 2"x2" salwood framing with 6mm ply on both side upto 3' ft. high or full with laminate on both sides. and / or 8mm thick clear float glass / expanded alum.powder coated 3" mesh, on top till lintel lvl. Exposed edge of glass to have crystal polish. The door to have mortise lock with brass handle, inclusive of heavy-duty hinges, door closer/floor spring, door stopers, Burma teak beading on the edge, the door to be finished in 1.0 mm laminate etc. complete.(The wooden frame members above false ceiling shall not be considered for payment or for the measurement.)Wooden door shutter with its total fittings is considered in this item.(as directed by the Architect)	300	Sq.ft		-	
2	Providing and constructing half height partition / wicket gate using	0	Sq.ft		-	
3	Providing and constructing filing cabinets using 3/4th inch thick ply wood for vertical shelves and shutters, 6mm ply for back. Shelf to be at 15" c/c and verticals to be at maximum 3' c/c. Inside of cupboard to be finished with French polish / oil paint. Shutter shall have heavy-duty brass hinges, 4", long powder coated brass handles and Godrej locks, external surface of the cabinets shall be finished with laminate etc. complete.(average dept of the filing cabinet shall be 18")	160	Sq.ft		-	
4	Providing and constructing Full height partition using 2"x2" salwood framing with 6mm ply on both side upto 3' ft. high, fully using 1.0mm thk laminate of approved make and shade on both sides. balance area with 12mm thick clear float glass on top till lintel lvl with a perfect round hole 6" dia, exposed edge of glass to have crystal polish. The door to have mortise lock with brass handle, inclusive of heavy-duty hinges, floor spring, door stopers, Burma teak beading on the edge, the door to be finished in 1.0 mm laminate etc. complete.(The wooden frame members above false ceiling shall not be considered for payment or for the measurement.)Wooden door shutter with its total fittings is considered in this item. for (Cash Cabin only with doors and relevant fixtures.)	140	Sq.ft		-	
5	Providing and supplying of Roller blinds of approved make and shade including tilt, cords, pulling strings, top track etc. complete (Regular make)	75	Sq.ft		-	
6	Providing and constructing of the soft board fixed on 12mm ply with 12mm soft board with necessary adhesive and finished with blaser cloth of approved color, fixed with cobbler nail etc complete (as directed by the Architect)	42	Sq.ft		-	
7	Providing and erecting of Branch Head table with keyboard drawer on telescopic channel, writing pad, pedestal with drawers and shelves with shutter, 8mm glass top table & credenza with filming with necessary exposed edges to have crystal polishing, inclusive of exposed surface finished with laminate and inside with oil paint,with necessary locks, heavy type brass hinges,using 19mm/12mm/6mm ply with all the mouldings, polishing ,etc complete.				-	
	Branch Head Table (7'6" X2'6" X ht. 2'6")	1	Nos.		-	
8	Providing and erecting of Officer's table with keyboard drawer on telescopic channel, writing pad, pedestal with drawers and shelves with shutter, 8mm glass top table with filming with necessary exposed edges to have crystal polishing, inclusive of exposed surface finished with laminate and inside with oil paint,with necessary locks, heavy type brass hinges,using 19mm/12mm/6mm ply with all the mouldings, polishing , etc complete.(as directed by the Architect)				-	
	4'6" / 5'0" x2'6"	5	Nos		-	

INDIAN BANK , Proposed New Branch, in new Bldg on First Fl. Plot no 50/1, Bachharaj Rd; at Wardha, Nagpur.

Interior Work at first floor + ATM.						26th Feb 2019
Sr.no	Discription	Qty.	Unit	Rate	Amount	
9	Providing and fixing of running counter for cash cabin in the banking hall with regular 19mm ply wood for base with necessary ply support at intervals and finished with 1.0mm laminate on top, exposed edge full round moulded, polished,with necessary key board drawer with telescopic channels, Handles, Locks, magnetic holder, single drawer in line with the key board drawers, tw lipping to the base and oil painted to the back and internal side of the ply base; also the pedestal shall have 3 drawer's one above the other with the depth of the drawer as required by the bank, inclusive of internal partition , locks, handles, fixed on telephonic channels, oil painted from in side and laminated from outside, etc complete. (Width 0.60/0.75 in the cash cabin,as directed by the architect).	5	R.ft		-	
10	Providing and fixing of 6/12/19mm ply wood panelling to the banking hall on GF and Elsewhere finied with 1.00mm laminate with necessary leveling, filling of the joints, TW lipping / "L" moulding, polishing / oil painting. etc complete. (as directed by the Architect)	125	Sq.ft.		-	
11	Providing and constructing false ceiling using standard GI framing section and Gypsum sheet including cutouts for recessed lamps fixtures, twin and single tubes including finishing the joints with tape and making surface homogenous as per detailed drawing etc. complete. (6" /4" patti , verticals shall be counted in sq.ft only. No iten shall be considered for R.Ft.)	300	Sq.ft		-	
	9" gyp patti	125	R.ft		-	
12	Providing and constructing Modular False Ceiling of 24"X24" The tile shall be laid on Armstrong Silhouette profile grid system with 15mm white flanges incorporating a 6mm central reveal in black colour and with a web height of 38 mm and a load carrying capacity of minimum 11.25 Kgs/M2 & minimum pull out strength of 100 Kgs.. Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system of Armstrong or equivalent make.including cutouts for recessed lamps fixtures, twin & single tubes , scaffolding etc complete.	500	Sq.ft		-	
13	Providing and treating the exposed columns with necessary 19mm ply,	0	Nos		-	
14	Providing and fixing the door at main entrance door at First floor + ATM ent door and side fixed panel and the main face made out of TW section / or 19mm ply double width 6"X2" from all 4 sides and finished 1mm laminated from both sides with 8mm glass in between with necessary 3m film itching to the glass, inclusive of floor spring SS handles brush finish from top to bottom rail, locking system, including fixed 12 mm clear float glass panelling at the entrence and side ways in the front fasade with necessary boxing and lamination and bidding etc complete.	130	Sq.ft		-	
15	Providing and making of writing desk as shown in the drawing, made out of the 19mm ply with 8mm glass top, finished with 1.00 mm laminate, inclusive of the shelve below to keep the slips below, inclusive of oil painting, polishing, etc complete.(as directed by the Architect)	2	Nos		-	
16	ACP Panelling- For external front fasad----- providing and fixing of AL sheet cladding (2.00mm thick) exterior grade of approved make, inclusive of using	0	Sq.ft		-	
17	Providing and fixing of 6/12/19mm ply wood Box panelling to the AC drain pipe / copper tube with insulation in the banking hall and managers cabin finished with 1.00mm laminate with necessary leveling, filling of the joints, TW lipping / "L" moulding, polishing / oil painting. etc complete. (as directed by the Architect)(depth of 6" to 9") (ht from 1' to 3')	50	R ft.		-	

INDIAN BANK , Proposed New Branch, in new Bldg on First Fl. Plot no 50/1, Bachharaj Rd; at Wardha, Nagpur.

Interior Work at first floor + ATM.					26th Feb 2019
Sr.no	Discription	Qty.	Unit	Rate	Amount
18	Providing and fixing of doors, 32 mm flush water proof door, partly glazed, fully glazed, with ply frame on all three sides finished with laminate / polish / oil paint , all required fitting, door closure / or floor spring, finished with 1.00 mm laminate both inside and out side, handl, locking system, etc complete (in pantry / toilets/ or else where)	25	Sq.ft		-
19	Providing and applying plastic Emulsion paint of specified manufacturer and approved colours in two coats including scaffolding preparing the surfaces to receive the priming coat and the finishing coat, includes removing \ scraping of the old colour and preparing the surface for the new paint, primer, etc complete.	500	Sq.ft		-
20	Providing and applying Oil paint specified manufacturer and approved colours in two coats including scaffolding preparing the surfaces to receive the priming coat and the finishing coat, includes removing \ scraping of the old colour and preparing the surface for the new paint, primer, etc complete.(basically in toilet and window grills elsewhere.)	100	Sq.ft		-
21	Making and fixing of MS security grill made out of 12mm thk full square bar along the balcony on the west side of the building; including necessary "L" (25x25x5 mm) angle at the end fixed with full welding, plumber nails, finished with redxoide coat, finished with black oil paint, inclusive transport, loading, unloading, fixing at first floor etc complete.	325	Sq.ft		-
Total Cost of Interior Work					-
The rates mentioned above should be inclusive of GST					