

INDIAN BANK
(A Govt. of India Undertaking)
Zonal Office, Bahraich

Work: Construction of Boundary Wall at RSETI, Shrawasti

Sealed quotations are invited from **Bank's empanelled Civil contractors** in UP state for boundary work at RSETI Shrawasti under our Zonal Office, Bahraich. Tender forms will be available at Zonal Office, Bahraich or may be downloaded from Bank's own website www.indianbank.in

Tender are to be submitted at Zonal Office, Bahraich as per following program.

1	Issue of Tender Documents:	From: 12.06.2020 to 26.06.2020 (Except holidays)
2	Submission of quotation	Before 29.06.2020 at 17.00 hrs
3	Opening of tender	At 30.06.2020 at 11:00 hrs
4	Time of completions	One month
5	EMD	Rs.10000/- in form of IOI / DD Fvg Chief Manager, Indian Bank.
7	Scope of work	Civil Work
8	Who will be eligible for the job.	Bank's empanelled Civil contractors Registered in UP for Civil Contractor work
9	Payment terms	No advance money will be paid. However running bills during progress of work may be paid considering progress of work. The final payment will be made on the basis of joint measurements after completion of total work. TDS will be deducted as applicable.
10	Retention Period and Amount	10% of actual cost will be retained for 180 days and will be released after satisfaction of Bank.
11	Taxes	GST will be borne by Bank and other than that any type of Tax will be paid by contractor and the Bank will not entertain any claim whatsoever in this regard.
12	Liquidity Dmages for Delay	If the work is not completed up to satisfaction of the Bank within the stipulated time frame of three weeks, the contractor shall be bound to pay to the employer a sum equivalent to 1% of the accepted tendered amount per week subject to ceiling of 10% of the accepted contract amount by way of liquidated damages.

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reasons whatsoever.

Deputy General Manager

Construction of Boundary Wall at RSETI Shrawasti

s.no	DESCRIPTION OF ITEM	Unit	Qty	Rate	Amount
1	Earth work in excavation by mechanical means over areas after clearing of site from bushes vegetation etc. and stacking the excavated material within site area including providing required slopes to vertical sides, shoring, strutting, trimming of sides, dewatering, lead of 50 meter & lift of 1.5 meter, incidentals, etc. complete and backfilling with available excavated earth, cleaning upto the site and disposal of all surplus materials with in the site. Excavation shall be payable only for vertical cut up to the outer edge of foundation lean concrete as indicated in drawings through out the pit depths. Cost of extra excavation required for working space, supporting side shuttering of foundations and retaining walls and that required for making slopes for stability of excavation shall be deemed to be included in the rate quoted. (Note:-The line & levels in the drawings shall be strictly followed and excess excavation if any shall be made good by contractor free of cost as per the instructions of the Site Engg/ Architect)				
1.1	All kind of soil for lead of 50 meter & lift of 1.5 meter	cum	113.54		
2	Providing & laying plain cement concrete using 40mm metal for all depths below and upto plinth level in foundations, drains, fillings, non suspended floors, pavements & ramps or any other works etc.including shuttering form work & tamping, ramming, viberating, curing for a period of 14days, in any shape, position, thickness & finishing the top surface rough or smooth as specified & directed all complete. Removing of centering, shuttering, shoring scaffolding shall be done carefully without such shock or vibration that would damage the concrete in foundation and plinth etc. complete.				
2.1	1:5:10 mix.(1 cement: 5coarse sand: 10stone aggregate-40mm nominal size)	cum	10.1		
3	Reinforced cement concrete work in Beams , suspended floors , roofs having slope upto 15" landings ,balconies , shelves , chajjas, lintels, bands, plain window sills , staircases and spiral stair cases upto floor all level including the cost of shuttering & centring and finishing with 1:1.5:3(1 cement:1.5 c.sand :3 graded stone aggregate 20 mm nominal size).	cum	19.1		
4	Reinforced cement concrete work in walls (any thickness) including attached pilasters, buttresses , plinth and string course, fillets, columns pillars, piers,abutments, posts and struts etc. upto floor all level including cost of shuttering, centering and finishing : 1:1.5:3 (1 cement :1.5 coarse sand :3 graded stone aggregate 20 mm nominal size) in columns.	cum	43.9		

5	Providing Thermo- mechanically treated bars of approved make of reputed concern (CONFIRMING TO IS :1786 grade Fe 500) for RCC work including straightening, cutting, bending, binding and placing in position with contractor's own 16 SWG black soft annealed binding wires at every intersection, supplying chairs, overlaps, welding, spacers, fanhooks etc. for all heights and depths complete as directed.of 8mm and above dia.	Kg	4939		
6	Brick work with common burnt clay F.P.S. (non modular) 1st class bricks in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	6.37		
7	Half brick masonry with common burnt clay F.P.S. (non modular) 1st class bricks in superstructure above plinth up to floor V level Cement mortar 1:4 (1 cement :4 coarse sand) including 1 no of 8mm dia bar in every 3rd layer.	SqM	415.5		
8	12 mm cement plaster on rough side of single or half brick wall of mix 1:6 (1 cement :2 coarse sand :4 fine sand)	sqm	930		
9	Finishing walls with SNOWCEM PLUS Premium waterproof cement paint : New work ((Two or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.)	sqm	930		
B	Boundary wall Gate				
1	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.	Kgs	500		
C	Submersible pump				
1	Supply & installation of Submersible Pump of standard approved make of capacity 2 HP with fully equipped control panel, wires, MCBs etc. in all complete.	Each	1		
	TOTAL AMOUNT				
	TOTAL GST				
	GROSS AMOUNTS				
	AMOUNT IN WORDS				
		Signature of contractor			
		(With Seal)			