

Zonal Office Kanpur, 15/287, Civil Lines, Bada Chauraha, Kanpur U.P.

NOTICE INVITING TENDER

Sub: COMPETTITIVE QUOTATION FOR INTERIOR FURNISHING & ELECTRICAL WORK Of Branch & ATM, at ARAUL, Distt. Kanpur (U.P.)

Competitive Sealed Quotations are invited in the prescribed format from the Contractors who are already empanelled with Bank having Electrical Works License and executed Interior Furnishing & Electrical Works of Nationalized Banks in last three years.

Format of Quotation Document is enclosed for submission of Interior furnishing & Electrical works of Branch & ATM at ARAUL Branch, Distt. Kanpur. Full details and tender documents are available on Bank's website: www.indianbank.co.in or can be obtained from Zonal Office, Kanpur. Dully filled in tenders should be submitted as per following schedule:

1		La anala a	
2 Submission of Tender On or before 16.07.2020 up to 15:30 hrs 3 Opening of Tender On 16.07.2020 at 16:00 hours 4 Date of Commencement 3 Days from the date of issue of letter awarding the job. 5 Time of Completion 15 days 6 Defect Liability Period 12 Months 7 Earnest Money Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable at Kanpur. 8 Liquidated Damages for delay Contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.	1		From 30.06.2020 to 15.07.2020
Opening of Tender			On and a face 40.07.0000 are to 45.00 bear
4 Date of Commencement 3 Days from the date of issue of letter awarding the job. 5 Time of Completion 15 days 6 Defect Liability Period 12 Months 7 Earnest Money Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable at Kanpur. 8 Liquidated Damages for delay Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			'
5 Time of Completion 15 days 6 Defect Liability Period 12 Months 7 Earnest Money Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable at Kanpur. 8 Liquidated Damages for delay Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
6 Defect Liability Period 7 Earnest Money Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable at Kanpur. 8 Liquidated Damages for delay Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable at Kanpur. Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.		•	,
at Kanpur. Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.		Defect Liability Period	12 Months
B Liquidated Damages for delay Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.	7	Earnest Money	Rs.7000/- in the form of DD/IOI in favour of Indian Bank payable
delay Contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			at Kanpur.
(If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.	8	Liquidated Damages for	Rs.2000/- per day subject to Max. of 10% of total accepted
within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.		delay	contract amount.
to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			(If the work is not completed to the satisfaction of the Employer
to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			within the stipulated period, the contractor shall be bound to pay
to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			·
liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Neither any advance nor any Interim payment will be made. Payment will be reade. Payment will be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
remains un-commenced or unfinished after expiry of the completion date.) 9 Payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
payment Terms Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			· · · · · · · · · · · · · · · · · · ·
Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			• •
Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.	9	Payment Terms	Neither any advance nor any Interim payment will be made.
the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.		,	
the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			as per the rules. Retention money 10% will be deducted from
virtual completion provided no defects is observed during this period. 10 Documents to be attached with the Bill Virtual completion provided no defects is observed during this period. Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
period. 10 Documents to be attached with the Bill period. Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			
Documents to be attached with the Bill . Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.			· · · · · · · · · · · · · · · · · · ·
with the Bill Bills & 4-5 Photographs showing completion status of work.	10	Documents to be attached	
	11.		ů i ů i

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

(Deputy General Manager)

CLIENT

INDIAN BANK,

ZONAL OFFICE, KANPUR - PREMISES DEPARTMENT 15/287 CICVIL LINES, BADA CHAURAHA KANPUR-208001 (U.P.)

WORK / PROJECT

PROPOSED INTERIOR FURNISHING WORKS AT INDIA BANK, ARAUL BRANCH, DISTT. KANPUR (U.P.)

COMPETITIVE QUOTATION FOR INTERIOR FURNISHING & ELECTRICAL WORKS AT ABOVE PROJECT

Tender Issued to:
M/S
Address
Contact No:
Tender Issued on:
Last Date of Submission: 16.07.2020

Signature of the Contractor

Seal



Zonal Office Kanpur, 15/287, Civil Lines, Bada Chauraha, Kanpur U.P.

NOTICE INVITING COMPETITIVE QUOTATION

Work: COMPETTITIVE QUOTATION FOR INTERIOR FURNISHING & ELECTRICAL WORK Of ARAUL Branch & ATM, at ARAUL, Distt. Kanpur (U.P.)

General terms & Conditions:-

1) Sealed quotation should be addressed to The DGM, Indian Bank, Zonal Office, Kanpur and super scribed name of Work INTERIOR FURNISHING & ELECTRICAL WORK Of ARAUL Branch & ATM, at ARAUL, Distt. Kanpur (U.P.) and should reach before 3.30 p.m. on 16.07.2020 at Zonal Office Kanpur.

Mailing Address:

The Deputy General Manager,

INDIAN BANK

Zonal Office Kanpur,

15/287 Civil Lines, Bada Chauraha

M.G. Road, Kanpur-208001. U.P.

- 2) No quotation will be accepted after 3.30 pm on 16.07.2020 and quotations will be opened on 16.07.2020 at 4.00 pm unless otherwise informed.
- 3) The quotations will remain valid for a period of 3 months from the date of opening.
- 4) Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- 5) At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.7000/- in favour of INDIAN BANK payable at KANPUR towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected.
- 6) Contract should quote rates in figures as well as in words.
- 7) All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 8) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- 9) Joint tenders shall not be considered. Conditional tenders quoted by the contractor is liable to be rejected.
- 10) No escalation in the rates will be allowed under any circumstances.
- 11) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days. If the successful contractor/tenderer fail to undertake the work within 7 days after work allotment, the EMD will be forfeited and acceptance of his tender may be withdrawn.
- 12) The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/transportation, labour conditions and fluctuations in rates of excise duty, octroi, GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the works.
- 13) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and

- Indian Bank, Zonal Office Kanpur-Interior Furnishing & Electrical Works of Branch & ATM at ARAUL, Kanpur conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
 - 14) The agency shall submit the offer which satisfies each and every condition laid down in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be out rightly rejected in the very first instance.
 - 15) Work will be completed within the period of 15 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender document.
 - 16) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in its execution or any other ground, the contractor shall apply in writing to the Deputy General Manager, Zonal Office, Kanpur with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. All the decisions in this regard taken by the Bank shall be binding to the contractor.
 - 17) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
 - 18) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
 - 19) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
 - 20) Contractor will arrange necessary tools and plants for completing own work at their cost. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
 - 21) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the date of virtual completion provided no defects is observed during the period.
 - 22) In case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.

- 23) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 24) The work shall be got approved by by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 25) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 26) The contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 27) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.
- 28) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contactor's account and responsibility.
- 29) Civil, Interior Furnishing and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
- 30) The contractor shall inform the bank, well in time, to check measurements of any work, which is likely to be hidden before covering.
- 31) Income tax at the prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 32) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 33) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractor. However the contractor should not deviate the quantity without Banks permission.
- 34) The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- 35) The Bank has the right to terminate the contract if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

Date:	(SIGNATURE OF THE CONTRACTOR)
Place:	SEAL

INDIAN BANK, ZONAL OFFICE, KANPUR - PREMISES DEPARTMENT

15/287 Civil Lines, Bada Chauraha, M.G. Road Kanpur-208001 (U.P.) Ph.0512-2346180 E-mail ID: zo.kanpur@allahabadbank.in

Annexure-A

Quotation for Interior Furnishing Work to be done at ARAUL Branch& ATM, Distt. KANPUR

Sl.	Description of Item	Unit	Qty.	Rate	Amount
No.				(Rs.)	(Rs.)
	FALSE CEILING				
1	Providing, fabricating and erecting in position totally flushed suspended false ceiling with 12.0mm thick Gypsum board, fixed to a metal frame work comprising of ceiling channel of size 80mmx26mmx0.5mm @ every 457cm centre, inter channel 45mmx15mmx0.9mm @ every 1220 cm centres, peri-meter channel 20mmx26 mm all along the wall/partitions, strap hanger suspenders 25mmx0.5mm with nuts and bolts 6.4mmx12.7mm, connecting clips 2.6mm thick, dry walls screws 25m long, soffit cleats 27mmx37mmx25mmx1.6mm thick and dash fastenes / rawl plugs 12.5 mm diax35mm long with 6mm dia bolts etc. complete with recommended fillers, paper tapes and applying two coats of acrylic emulsion paint of approved shade and make over a coat of primer including making necessary cut outs for light fittings/ ACs etc. complete as per manufacture's specifications. (Quantity as per layout plan/site requirement)	Sft	880		
2	Providing and fixing 600 mm x 600 mm mineral fiber tiles false ceiling of Armstrong/Gypboard/equivalent approved make of micro look system including suspension system as per manufacturer's specifications and instructions of Architect/ Engineer complete in all respects including making cutouts where necessary for electrical lighting fittings etc. complete all as directed by the Bank. (Quantity as per layout plan/site requirement)	Sft	175		

3	WALL PANELING / COLUMN ENCASING		0. 2. 4	
	Supplying and erecting Wall paneling / Column encasing (up to false ceiling) as per drawing and design and conforming to the following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: 6 mm thick BWP grade plywood on face.	Sft.	553	
4	Supplying and erecting full height opaque/solid partitions (up to false ceiling/7' height) as per following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: To be finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves in both faces as per instructions. Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits, switches etc. shall be separately paid for)	Sft	210	

5	Cumplying and anating full baight mouthy	Sft.	178.5	
3	Supplying and erecting full height partly	SIL.	1/8.3	
	glazed/aluminium grill partitions for BM cabin			
	side partition/ cash back side portion			
	respectively as per following specifications:			
	Basic frame work: Framing shall consist of			
	Heavy duty Aluminium Box Sections 50mm x			
	50mm @ 600mm c/c both ways Horizontally			
	and Vertically. The vertical alternate frames			
	to be fixed to the ceiling with necessary fixtures.			
	Vertical members shall be suitably anchored			
	at ceiling level to ensure rigidity. Exposed frame			
	members in the glazed portions shall have wider			
	spacing (approx. 1200 mm) and be finished with			
	1.00 mm thick laminate of same or combination			
	shades, over 6mm BWP grade ply.			
	Chin manhana (Ozaza zati			
	Skin membrane: (Opaque portion up to 900mm			
	from floor level and from 2100mm to ceiling,			
	finished with 6mm thick BWP grade plywood			
	on each face with grooves, as per drawings/instructions.			
	Finishing: 1.0mm thick laminate of same or			
	combination shades with grooves as per instructions.			
	Glazing: 6mm thick clear float glass fixed with			
	polished teak / steam beech wood glazing beads			
	of approved shape (finished 12 x 25mm). (for			
	BM cabin side partitions) Al. grill: Readymade			
	anodized aluminium grill of approved design			
	and quality fixed with continuous teak wood /			
	steam beach beads of approved shape (finished			
	35 x25mm) duly polished by NC lacquer			
	finish. (for Cash Cabin Side Partitions)			
	Skirting- 100mm high laminate of approved			
	make & shade all as directed.			
	Top Border: 150mm high laminate of approved			
	make & shade all as directed.			
	Quoted rates shall include all necessary			
	materials, accessories and labour and also to make provisions for electrical / telephone /			
	•			
	computer wiring conduits and switch boxes,			
	etc. (Materials for wiring, conduits &			
	switches etc. shall be separately paid for)			
6	-do- as item 5 but with 12mm thick clear float	Sft	0	
	glass up to door height (instead of 6mm glass			
	in wooden partition)			
	with 6" bottom rail complete all as directed by			
	the Bank.			
	(for BM cabin front partition).			
	(101 DIVI cubin it one put tition).			
		I		

		1
7 Supply and erecting low height opaque Sft	38	
partitions (up to maximum 1200mm height)		
conforming to the following specifications:		
Basic frame work: Framing shall consist of		
Heavy duty Aluminium Box Sections 50mm x		
50mm @ 600mm c/c both ways Horizontally		
and Vertically. The vertical alternate frames		
to be fixed to the ceiling with necessary fixtures.		
Vertical members shall be suitably anchored		
at ceiling level to ensure rigidity.		
Skin membrane: 6 mm thick BWP grade ply on		
each face up to 900mm height.		
Glazing: 10mm glass in remaining portion,		
<u>Finishing:</u> 1.0-mm thick laminate of same or		
combination shades with grooves as per		
instructions.		
Edge moulds: All free top/ end surfaces shall		
have polished teak / steam beech wood moulds		
of approved shape (from 18 x 50mm sections).		
Skirting- 100mm high laminate of approved		
make & shade all as directed.		
Quoted rates shall include all necessary		
materials, accessories and labour and also allow		
provisions for electrical / telephone/computer		
wiring, conduits and switch boxes, etc.		
(Materials for wiring, conduits and switch		
boxes shall be separately paid for.)		
8 COUNTERS/WORK STATIONS:-		
Providing and erecting in position Cash Work Rft	10.25	
Station of approx. size 1370x900x750mm	10.25	
(4.5'x3.0'x2.5'), made of 19mm thick block		
T DOARD DASIED WITH LUUMIN TAMBBATE INCHISIVE OF F		
board pasted with 1.00mm laminate inclusive of a 350mm wide customer top at 1155 mm		
a 350mm wide customer top at 1155 mm		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick,		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed. Each cash workstation shall comprise of the drawer		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed. Each		
a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed. Each cash workstation shall comprise of the drawer		

	Bank, Zonai Omee Kanpai- interior i arnishing & Electric			 ·
	Cash drawers with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S. S. handles of approved quality. Inner face of cash counter to be provided with 16G, M.S. sheet, painted with two coats of synthetic enamel paint of approved shade & make, over a coat of approved steel primer. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer.			
	Skirting: 100mm high laminate of approved			
9	Providing & fixing 12mm thick clear float glass on Cash Counters at front & sides, with S S clamps/patch fittings, necessary polished beadings etc complete all as directed by the Bank. Note: Front glass to be fixed in slanting position towards inside cash area with required angle as directed. Above glass to be fixed either in two pieces. Lower piece having one semicircular/rectangle 6" dia / long opening at customer top level & other piece to be fixed at suitable height making 3" slit for conversation with customer. In this case, only glass area to be measured for payment purpose.) In case of single piece, one semi-circular/rectangle 6" dia/long opening at customer top level & one circular hole of required dia at suitable height for conversation at centre of cash counter to be provided.	Sft	30	
10	Providing and fixing in position readymade anodized aluminium grill of approved design and quality fixed with continuous teak wood / steam beach beads of approved shape (finished 35 x 25mm) duly polished by NC lacquer finish.(to be considered in cash cabin ceiling, if required, as per site requirement)	Sft	72	

11	Supplying and erecting clerical counters (running tables) 750mm deep and 750mm high including drawer-cum-cabinet unit for files, space for computer CPU, wire managers, modesty panel, tea tray etc. made with 19mm thick BWP grade block board on top and supporting sides / front with necessary well seasoned Malaysian Sal/ Kail/ Mirandi wood frame work, finished on top with mirror polished 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0 mm thick laminate of approved shade and quality, including providing and fixing 450mm long key board tray of approved shade, hardware and accessories at each of the counter. All exposed edges of block board are to be provided with half round teak wood mouldings, duly polished and 100mm high laminate of approved make & shade all as directed.Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Skirting: 100mm high laminate of approved make & shade all as directed. Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of 'Earl Behari' or equivalent approved make.	Rft	15	
12	Providing and fixing 1'-6" high, 12mm thick clear float glass railing on clerical counters with S. S. Decorative posts of 50mm dia all as directed by the Bank.	Sft.	15.37	
13	DOORS:-			
	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edges. The upper portion of the shutter is to be provided with 6 mm thick clear float glass fixed with white or steam beech wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g. mortise lock, hinges, handles, door closer etc. of approved make and quality. (Manager cabin door)	Sft	21	

- Indiani	Bank, Zonal Office Kanpur- Interior Furnishing & Electric	ai works	OI BI AI IC	II & A IIV	li at ARAUL,
14	Providing and fixing Flap Door of min. size: 3' (B) X 2'6" (H) made of block board with approved lamination on both side, of required size with hinges/tower bolts/stopper/handles etc complete.	Sft.	16		
15	Providing fabricating & fixing in position twin – style door at Main Entrance made of well seasoned teak wood of size 100 x 50 mm or anodized/powder coated Aluminium sections of required size on frame, top & bottom rail and 12mm thick glass(Modi/ Saint Gobain make) including fixing the frame to brick wall/RCC/wooden surfaces with necessary fasteners to have proper fixity including all incidentals etc complete. Glass to be fixed in the grooves of the teak wood/al. sections with necessary materials/beading etc. The job also includes cost of providing & fixing heavy duty double action hydraulic floor spring (ISI mark) in the floor, fixing the door on it, including necessary fixing materials on the lintel/bottom, bolts, locks & satin finish stainless steel decorative tubular handles(approx.300mm long) on both faces complete as per drawing and instructions. The exposed teak wood surfaces to be polished in approved shade N.C lacquer in mat satin finish. The rate should also include cost for decorative etching on the glass. a) Openable portion b) Fixed portion	Sft	28		
16	CUPBOARDS / STORAGE CABINETS / TABLE SIDE UNITS:-				
	Providing and erecting in position low/ full height Storage cabinet Made of 19 mm thick BWP grade block board including intermediate shelves as per direction, lockable shutters etc. conforming to following specifications: Shutter faces shall be finished with 1mm thick laminate of same or combination shades as per instructions with polished white or steam beech wood (6mm thick) edge lippings and 100mm high teak wood skirting duly polished/ painted as directed. Inner faces of cabinet including shutters shall be painted in approved shade. Shutters will be hung by auto-closing hinges, locks, magnetic door catcher and satin finished S. S. handles etc. of approved make. (Payment will be on the area of cabinet face). Skirting: 100mm high laminate of approved make & shade all as directed. a) Maximum 400mm deep x 900 mm high b) Maximum 400mm deep x 2100 mm high	Sft.	21		

I	Note:- Quantity to be to be restricted to bare]		
	minimum as per actual requirement being			
	costly item & to be provided in open area in			
	Banking hall & not in store room. Store room			
	may be provided with steel racks) (Actual			
	face area will be measured for payment			
	purpose.)			
17	Providing and erecting in position side cabinet	Sft	20	
17	units with shutters of approx size of 400mm deep x 700mm high made of 19mm thick BWP grade block boards including intermediate shelves as per drawing / instructions. Exposed surfaces shall be finished with 1.00mm laminate of approved shade and make. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Free edges of block board shall be finished with polished white or steam beech wood half round moulds (out of 20 x 20 mm sections). Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Skirting: 100mm high laminate of approved make & shade all as directed. Quoted rates shall include cost of necessary hardware, viz handles, locks with keys in	Sit	20	
	duplicate, etc. (Actual face area will be			
	measured for payment purpose.)(to be put on			
	table's side)			
18	TABLES:-			
	Providing and erecting in position tables as per			
	drawing and conforming to the following			
	specifications:			
	Structure of 19mm thick block board for sides,			
	top and modesty panel, finished with 1.00 mm			
	thick laminate of approved shade and make			
	including drawer–cum-cabinet unit, CPU			
	Trolley, modesty panel, tea tray ,wire			
	managers,450mm long key board trey, hardware			
	and accessories etc complete. All exposed edges			
	of block board are to be provided with half			
	round teak wood moldings, duly polished.			
	Inner faces shall be painted with two coats of			
	synthetic enamel paint of approved shade & quality over a coat of primer.			
	1			
	Rate to include charges for brass hardware			
	fittings as well as fixtures like sliding gear for drawers of 'Earl Behari' or equivalent approved			
	make.			
	mane.			

a) Approx size 1830 x 915 x 750 mm (6.0'x 3.0'x 2.5')	NOS	1		
b) Approx size 1524 x 750 x 750 mm (5.0'x 2.5'x 2.5') c) Approx size 1372 x 750 x 750 mm (4.6'x 2.5'x 2.5') d) Approx size 1220 x 750 x 750 mm (4.0'x 2.5'x 2.5')		1		
Note:-Size/quantity to be considered as per approved layout/sitting plan/staff strength & site requirement.)				
Total of Furnishing Work Discount Allowed if Any%		= =	Rs. Rs.	
Final Total of Furnishing Work		=	Rs.	
(Final Amount in Words for Interior Furnishing Work)= Rs				
only				
Note:- Quoted Rates are exclusive of taxes				
	Seal &	Signatur	e of Con	tractor
Date:				
Place:				

INDIAN BANK, ZONAL OFFICE, KANPUR - PREMISES DEPARTMENT

15/287 Civil Lines, Bada Chauraha, M.G. Road Kanpur-208001 (U.P.) Ph.0512-2346180 E-mail ID: zo.kanpur@allahabadbank.in

Annexure-B

	Quotation for Electrical /UPS Wiring Work to be done a				
Sl.	Description of Item	Unit	Qty.	Rate	Amount
No.				(Rs.)	(Rs.)
1	Supplying and fixing of 125 Amp TPN Main Switch	Set	1		
	on M.S Angel frame on wall including				
2	MAIN PANEL BOX	Set	1		
	Supply, installation, vermin-proof,, cubicle type, 20				
	gauge thick sheet enclosure main incoming (MIP) panel,				
	suitable for use on 415 V, 3-Ph, 4 wire, 50 Hz AC system,				
	incoming and outgoing cable compartment. Each unit				
	shall be accommodated in a separate compartment having				
	gasketted hinged door with locking arrangement. The				
	cubicle should be painted with 2 (two) coats of gray				
	synthetic enamel paint over a coat of zinc chromate primer. The complete fabrication, construction shall be done as per				
	the detailed specification and conforming to the relevant I				
	S code. Name plate of Panels Danger Board, incoming and				
	outgoing feeders with Ampere rating of MCCB / MCB are to				
	be fixed up on front door above or below the respective				
	switches. Approval				
	INCOMING:	Set	1		
	415V 125A 4 pole MCCB having short circuit breaking				
	capacity of 35 K A (min) with O/L, E/F & S/C protection				
	Device.				
	(a) Digital Volt Voltmeter with Selector Switch -1no. (b)				
	Digital Ammeter with Selector Switch				
	(c) Phase indicating lamps-1no.				
	(d) PVC sleeved TPN 150 Amp Tinned 4 strip Copper Bus bar-1no.				
	(e) 100/5A CT(Current transformers) -1no.				
	OUTGOING				
	a) 63 A, 4 pole TPN MCCB with 25KA				
	a, 557, 1 polo 11 14 111555 Willi 20101				
	h) 624 DD on load change over switch 1pc				
	b) 63A, DP on load change over switch-1no.c) 240V 40A SP MCB(for UPS) -1 no.				
	d) 240V 32A SP MCB(for light/fan points)-1 no. e)				
	Provision for installation of MCB-1no.				
3	Supplying and fixing concealed type factory fabricated				
J	(Double Door) with 40 Amp DP RCCB of 300		1		
	mA as				
				<u> </u>	
	Incomer complete with interconnection with				
	MCB, copper bus & neutral & earth link.				
	a)8 Way with 6 nos SP MCB (5-10 Amp)(Light)	Each	6		

	b) 12 Way with 10 nos SP MCB (5-10 Amp (UPS)	Each	10	
4	Supplying and fixing concealed type factory fabricated	Each	1	
	3 phase 400 volt TPN MCB Distribution board 4 way per phase with 63 Amp TPN RCCB of 300 mA sensivity as incomer and 12 nos (6-25) Amp MCB SP as out going complete with interconnection with copper bus & neutral & earth link. (A.C)			
5	Supplying and connection by 4 x 16 sqmm + 1x6 sqmm FRLS PVC insulated copper wire between Main	Rmt	15	
	Switch and Panel by making proper end socketing including supplying 35mm pvc pipe.			
6	Supplying and connection by 4 x 10 sqmm + 1x6 sqmm FRLS PVC insulated copper wire between TPN DB and Panel by making proper end socketing including supplying 25mm pvc pipe.	Rmt	15	
7	Supplying and drawing circuit line by 2 x 6 sqmm + 1 x 2.5 sqmm FRLS PVC insulated copper wire by 19 mm pvc pipe fully concealed and mending good the damages (For UPS Incoming & UPS to DB)	Rmt	28	
8	Supplying and drawing circuit line by 2 x 4 sqmm + 1 x 2.5 sqmm FRLS PVC insulated copper wire by 19 mm pvc pipe fully concealed and mending good all the damages)(for AC)	Rmt	20	
9	Supplying and drawing circuit line by 2 x 2.5 sqmm + 1x1.5 sqmm FRLS PVC insulated copper wire by 19 mm pvc pipe fully concealed and mending good the damages.(For circuit wiring)	Rmt	106	
10	Making point wiring for fan & light by 2 x 1.5Sqmm + 1 x 1 sqmm FRLS PVC insulated single core copper	Rmt	106	
	wire by 19 mm pvc in concealed manner including modular type switch & socket 6Amp, M.S.box, Top plate and cover plate.			
	a) Single point controlled by single switch.	Each	51	

	b) Double point controlled by single switch.	Each	4	
	c) Plug point 6Amp	Each	6	
	d) Call bell point	Each	2	
11	Supplying and fixing 2 Nos 3 pin 6 Amp Socket and 1 No 15Amp controlling switch of modular type and connection including M.S box, cover plate and top plate in one board.	Each	8	
12	Supplying and fixing 3 Nos 3 pin 6 Amp Socket and 3 Nos controlling switch of modular type including M.S	Each	6	
	box, cover plate and top plate in one board.			
13	Supplying and fixing 1 No 3 pin 6 Amp Socket with controlling switch of modular type including M.S.Box,	Each	6	
	cover plate and top plate for raw supply.			
14	Supplying and fixing 1 No 6 pin 6/16 Amp Socket with controlling switch of modular type including M.S.Box,	Each	6	
	cover plate and top plate			
15	Supplying and fixing 2 Nos 40Amp DP MCB in suitable enclosure for UPS Incoming & outgoing.	Each	1	
16	Supplying and fixing Air-conditioner Starter with 20Amp SPN MCB & Socket of North West/Havels make in suitable steel enclosures including 20Amp 3 pin plug top.	Each	2	
17 a)	Earthing:-(General) Earthling installation as per I.E. conforming to IS: 3043 or its latest amendment by making earth station with 600 mm x 600 mm x 3mm (minimum) thick copper electrode to be installed such that its top edge shall be at a minimum depth of 3.0 metre below ground level after preparation of ground with required quantity of charcoal and salt and connecting the MIP with 20mm x 3mm copper earth lead-in-strip directly in ground by bolting and then brazing to the copper plate complete with GI bolts of suitable length, double nuts and washers including supply and fixing of 50mm dia. partly perforated GI pipe with funnel for watering	Each	2	

b)	arrangement. The earthing installation should be provided with 300mm x 300mm and 300mm depth inside dimension masonry inspection pit with CI hinged cover having locking arrangement. Notes:- 1) Where ever Chemical Earthing is possible, same may be carried out as per manufacturer's specifications in lieu of above. 2) Earthing resistance must be less than 2 Ohms. 3) Guarantee for a particular period should be obtained from the contractor.	Each	30	
	1x6 sq. mm copper wire inside 19mmdia PVC pipe up to UPS.			
19	Supplying & Installation of following light fixture complete with lamps, tubes, fixing arrangement in false ceiling including making connection etc.			
	a) LED light fixture recessed type 18wt.(190x190x20mm) philips	Each	21	
	b) LED light fixture Surface type 18wt.(190x190x20mm) philips	Each	8	
	c) LED Down lighter 18wt.(190x190x20mm) philips	Each	2	
	d) Tube light fittings (phillips)	Each	14	
	e) Wall Bracket Fan 400 mm dia (Havels /	Each	4	
	Crompton Make with Plastic Body) f) Ceiling fan 48" with mounting / hanging attachment from ceiling height. (Havels /	Each	9	
	Crompton Make) g) Exhaust Fan 9" dia (Heavy Duty) complete with louver & mounting attachment. (Havels / Crompton Make)	Each	2	
20	Supply and drawing telephone cable of approved make in the PVC pipe.			
	a) 2 pair	Rmt	45	
	b) 4pair	Rmt	25	
	c) Termination of telephone cable in one end with RJ11	Each	2	

Indian Bank, Zonal Office Kanpur- Interior Furnishing & Electrical Works of Branch & ATM at ARAUL, Kanpur Telephone Socket (Jack type) -2 nos in 1 module suitable enclosures. d) Termination of telephone cable in one end with 8 Each RJ11 Telephone Socket (Jack type) – 1 no in 1 module in suitable enclosures a) Supply and drawing LAN-cable CAT-6(D-link 85 Rmt or eqv. make) in the PVC pipe. 7 b) Termination of LAN-Cable in one end by Each **RJ45** Computer Jack & mounting of modular type including supplying and fixing suitable I.O Box

in concealed manner (D-link, Roma, Crabtree, MK or eqv. make in suitable enclosures) Supply & Fixing patch chords (Cat-6) D-link or 22 eqv. make 3 i) 3' long Each 4 ii) 7' long Each 7 c) Termination of LAN-Cable in other end by Each RJ45 socket. **Total of Electrical Work** Rs. Discount Allowed if Any _____ Rs. Final Total of Electrical Work_____ Rs. (Final Amount in Words for Electrical / UPS Wiring Work)= only Note:- Ouoted Rates are exclusive of taxes Seal & Signature of Contractor Date:

Place: