

## Zonal Office Allahabad

### NOTICE INVITING TENDER

#### **Sub: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING Of MAU Branch, at Chitrakoot under ZO Allahabad**

Competitive Sealed Quotations are invited in the prescribed format in two bid system (Technical and Financial) from the Contractors who are already empanelled with Bank and executed Interior Furnishing Works of Nationalized Banks in the last three years.

Format of Quotation Document is enclosed for submission of Interior furnishing works of Mau Branch, Distt. Chitrakoot. Full details and tender documents are available on Bank's website: [www.indianbank.co.in](http://www.indianbank.co.in) or can be obtained from Zonal Office, Allahabad Dully filled in tenders should be submitted as per following schedule:

1	Issue of Tender Document	From 15.12.2020 to 29.12.2020
2	Submission of Tender	On or before 29.12.2020 up to 02:00 PM
3	Opening of Tender	On 29.12.2020 at 03:00 PM
4	Date of Commencement	7 Days from the date of issue of letter awarding the job.
5	Time of Completion	20 days
6	Defect Liability Period	12 Months
7	Earnest Money	Rs.5000/- in the form of DD/IOI in favour of Indian Bank payable at Prayagraj.
8	Liquidated Damages for delay	Rs.2000/- per day subject to Max. of 10% of total accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period, the contractor shall be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.)
9	Payment Terms	Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted from the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period.
10	Documents to be attached with the Bill	Managers Completion Certificate, Manufacture Certification, Bills & 4-5 Photographs showing completion status of work.
11.	Retention Money	10% (Including Earnest Money)

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

(Deputy General Manager)

C L I E N T

INDIAN BANK(Erstwhile Allahabad Bank)

ZONAL OFFICE, Allahabad - PREMISES DEPARTMENT  
22, P.D. Tandon Road, Prayagraj  
Uttar Pradesh - 211001

WORK / PROJECT

PROPOSED INTERIOR FURNISHING WORKS AT  
INDIAN BANK, MAU BRANCH, DISTT. CHITRAKOOT

COMPETITIVE QUOTATION  
FOR INTERIOR FURNISHING WORKS AT ABOVE PROJECT

Tender Issued to:

M/S \_\_\_\_\_

Address \_\_\_\_\_

\_\_\_\_\_

Contact No: \_\_\_\_\_


Tender Issued on: \_\_\_\_\_

Last Date of Submission: \_\_\_\_\_

Signature of the Contractor

Seal





**Zonal Office Allahabad**

**NOTICE INVITING COMPETITIVE QUOTATION**

**Work: COMPETITIVE QUOTATION FOR INTERIOR FURNISHING  
Of MAU Branch, at Chitrakoot under ZO Allahabad**

**General terms & Conditions:-**

- 1) Sealed quotation should be addressed to The DGM, Indian Bank, Zonal Office, Allahabad and super scribed name of Work INTERIOR FURNISHING WORK Of Mau Branch, at –Chitrakoot and should reach before 2:00 p.m. on 29.12.2020 at Zonal Office Allahabad.  
**Mailing Address:**  
**The Deputy General Manager,**  
**INDIAN BANK**  
**Zonal Office Allahabad**  
**22, P.D.Tandon Road, Prayagraj-211001(U.P)**
- 2) No quotation will be accepted after 2:00 pm on 29.12.2020 and quotations will be opened on 29.12.2020 at 3:00 pm unless otherwise informed.
- 3) The quotations will remain valid for a period of 3 months from the date of opening.
- 4) The agency should have valid GST registration & other supporting document related to GST. The firm should submit their GST Identification Number in the enclosed format (Annexure - III) along with the Technical Bid.
- 5) Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- 6) At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.5000/- in favour of INDIAN BANK payable at Prayagraj towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected.
- 7) Contractor should strictly quote rates in figures as well as in words.
- 8) All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 9) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- 10) Joint tenders shall not be considered. Conditional tenders quoted by the contractor is liable to be rejected.
- 11) No escalation in the rates will be allowed under any circumstances.
- 12) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days. If the successful contractor/ tenderer fail to undertake the work within 7 days after work allotment, the EMD will be forfeited and acceptance of his tender may be withdrawn.
- 13) The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/ transportation, labour conditions and fluctuations in rates of excise duty, octroi, GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the works.
- 14) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and



- conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.
- 15) The agency shall submit the offer which satisfies each and every condition laid down in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be outrightly rejected in the very first instance.
  - 16) Work will be completed within the period of 20 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender document.
  - 17) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in its execution or any other ground, the contractor shall apply in writing to the Deputy General Manager, ZO Allahabad with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. All the decisions in this regard taken by the Bank shall be binding to the contractor.
  - 18) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
  - 19) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
  - 20) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
  - 21) Contractor will arrange necessary tools and plants for completing own work at their cost. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
  - 22) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the date of virtual completion provided no defects is observed during the period.
  - 23) In case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.



- 24) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 25) The work shall be got approved by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 26) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 27) The contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 28) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.
- 29) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contractor's account and responsibility.
- 30) Civil, Interior Furnishing and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
- 31) The contractor shall inform the bank, well in time, to check measurements of any work, which is likely to be hidden before covering.
- 32) Income tax at the prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 33) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 34) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractor. However the contractor should not deviate the quantity without Banks permission.
- 35) The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- 36) The Bank has the right to terminate the contract if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

(SIGNATURE OF THE CONTRACTOR)

Date:

Place:

SEAL

Seal & Signature of Contractor

## ANNEXURE III

Collection of Vendor Master Data				
SL.NO.	GSTIN DETAILS		DETAILS TO BE FILLED UP BY VENDOR / SUPPLIER	
1.	Name of the Vendor/supplier			
2.	PAN			
3.	GST Identification Number (GSTIN)			
4.	TAN			
5.	Composition Scheme (Please indicate)		(Yes / No)	
6.	Nature of Service Rendered/supply made – as given the Registration Certificate issued by the authorities			
7.	Address of principal place of business in the state as per GST registration Certificate	Address		
City				
PIN				
State				
8.	Location	SEZ/STP/DTA		
9.	Contact details	Name		
E-mail ID				
Phone No.				
	Date :		(Signature of Customer )	
			(of Authorized Signatory only with stamp)	

\*\*\*\*\*

PROJECT - FURNISHING WORKS for MAU Branch, Indian bank					
Under ZONAL OFFICE-Allahabad					
S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
A.	FURNISHING WORKS				
1	Main Entrance Door (Double Door for Branch )	105	SQFT		
	Providing and Filing in Position toughened glass door with 12 mm thick toughened glass with 3M security film complete in all respects with Ozone patch fittings including top patch(OPF-02),BOTTOM PATCH (OPF-03)angle lock(OPL-01)TOP PIVOT (OFS-ACC-GDP)Floor Spring (FS8400) and handle (OGH-55) 32mm x 457 mm all item included & One door for branch & One for E-lobby )				
2	LOW HEIGHT OPAQUE/SOLID PARTITION				
	Supply and erecting low height opaque partitions (up to maximum 1200mm height) conforming to the following specifications : <b>BASIC FRAME WORK:</b> Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. <b>SKIN MEMBRANE:</b> 6 mm thick BWP grade ply on each face up to 900mm height. <b>GLAZING:</b> 10mm glass in remaining portion. <b>FINISHING:</b> 1.0-mm thick laminate of same or combination shades with grooves as per instructions. <b>EDGE MOULDS:</b> All free top/ end surfaces shall have polished teak / steam beech wood moulds of approved shape (from 18 x 50mm sections). <b>SKIRTING-</b> 100mm high laminate of approved make & shade all as directed. (Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical / telephone/computer wiring, conduits and switch boxes etc.)	50	SQFT		
3	FULL HEIGHT OPAQUE/SOLID PARTITION				
	Supplying and erecting full height opaque/solid partitions (up to false ceiling/7' height) as per following specifications: <b>BASIC FRAME WORK:</b> Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. <b>SKIN MEMBRANE:</b> To be finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. <b>FINISHING:</b> 1.0mm thick laminate of same or combination shades with grooves in both faces as per instructions. <b>SKIRTING-</b> 100mm high laminate of approved make & shade all as directed. <b>TOP BOARDER:</b> 150mm high laminate of approved make & shade all as directed. ( Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. )	200	SQFT		



S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
4	<b>FULL HEIGHT PARTLY GLAZED/CASH CABIN SIDE PARTITION</b> Supplying and erecting full height partly glazed/aluminium grill partitions for BM, cabin side partition/ cash back side portion respectively as per following specifications: <b>BASIC FRAME WORK:</b> Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (MIN 1200 mm/as per site) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply. <b>SKIN MEMBRANE:</b> (Opaque portion up to 900mm from floor level and from 2100mm to ceiling, finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. <b>FINISHING:</b> 1.0mm thick laminate of same or combination shades with grooves as per instructions. <b>GLAZING:</b> 6mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm). (for BM cabin side partitions) <b>AL.GRILL:</b> Readymade anodized aluminium grill of approved design and quality fixed with continuous teak wood / steam beech beads of approved shape (finished 35 x25mm) duly polished by NC lacquer finish. (for Cash Cabin Side Partitions). <b>SKIRTING-</b> 100mm high laminate of approved make & shade all as directed. <b>TOP BOARDER:</b> 150mm high laminate of approved make & shade all as directed. (Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc.) Al. grill: Readymade anodized aluminium grill of approved design and quality fixed with continuous teak wood / steam beech beads of approved shape (finished 35 x25mm) duly polished by NC lacquer finish. (for Cash Cabin Side Partitions)	292	SQFT		
5	<b>Glass Barrier on cash cabin and front glass for counter(12 MM NECESSARY)</b> Providing and fixing glass barrier (as per profile and design) in front of cash and ledger counter made out of 12mm thick polished edged float glass (Make – Modi guard or equivalent). It shall have 25mm x 20mm teakwood beading (as/shape approved by the Architect) to hold the glass from sides and top (optional). All teak wood surfaces shall be melamine polished. The rates shall include for cutting (in geometrical shape) and polishing the edges, all complete to the satisfaction of the Architect.	60.00	Sq.Ft		
6	<b>Computerised Ledger &amp; Cash Counter</b> Providing and placing in position ledger counter with top, vertical sides/dividers, skirting and fascia made out of 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces. It shall also have 75mm x 40mm teak wood runners below the top and for footrest below. Every unit shall be provided with a side unit (size - W-500mm, H-750mm, D-500mm approx.), consisting of 150 mm deep drawer at top and a cabinet with open able/hinged shutter below.				



S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
	. The fascia of drawer and shutter of cabinet below shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The side unit shall have CAM locks, handles, guides, sliding units, hinges, magnetic catcher's etc. of approved make. Every unit shall be provided with a keyboard drawer unit (size - W-550mm, H-100mm, D-300mm approx.) below. The counter shall have 100mm deep fascia, below the top, in which keyboard drawer unit shall be adjusted.				
	It shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The unit shall have CAM locks, handles, guides, sliding units etc. of approved make. The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.				
7	High Level	10.00	Rg.Ft		
	High level (two levels) Computerised cash counter.				
	Lower level top shall be 900mm wide and at 750mm level from floor & upper level top shall be 250mm wide (and at 1150 mm level from floor				
8	Low Level	25.00	Rg.Ft		
	Low level (two levels) Computerised ledger counter.				
	Lower level top shall be 900mm wide and at 750mm level from floor & upper level top shall be 150mm wide and at 900mm level from floor				
9	Writing Table & Brochure Holder	2.00	No.		
	Providing and fixing in position (with rear wall) slip and customer writing desk (as per design) of over all size - 1200mm x 450mm x 300mm. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect.				
	.The writing top and facia/sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect), on all sides and . It shall be laid over the base of 19mm thick water proof board (already considered in various items.) and fixed with araldite. It shall include for beveling and polishing at all the exposed edges. The rate shall include cost of all materials, labour, scaffolding, wastages, polishing and T& P etc. It shall be made out of 12mm thick water proof plywood (two surfaces of 6mm thickness, fixed together, where required) on rear and both sides.				
	The front shall be made out of 12mm thick glass (as per profile). It shall be fixed in the grooves, made in side members, in an inclined manner (as per profile in drawing enclosed) with a gap of 75mm (max.) in between. The space shall be further divided in four equal parts with help of 12mm thick water proof plywood. All edges of the glass shall be polished. All the exposed edges of water proof board and plywood shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect				

S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
<b>10</b>	<b>Complaint &amp; Suggestion Box &amp; CHEQUE DROP BOX</b>	2.00	No.		
	Providing and fixing in position complaints/suggestion box (as per design) with hinged shutter of size - 450mm x 600mm x 150mm made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect) on all exposed surfaces. It shall have 6mm thick water proof plywood on the back.				
	.The hinged shutter shall be made out of teakwood (section - 25mm x 50mm) framework, with 4mm thick float glass, fixed with teakwood (size - 12mm x 12mm) beading. The unit shall have cam locks, handles, spring hinges, magnetic catchers etc. of approved make. All the exposed edges of water proof board or ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.				
<b>11</b>	<b>Notice Board</b>	1.00	No.		
	Providing and fixing in position notice board (as per design) of size - 900mm x 600mm x 150mm. The sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect) on all exposed surfaces. It shall have 12mm thick tack The front shall have 6mm thick float glass sliding shutter in two parts.				
	It shall also have 19mm wide two track aluminium channel for sliding arrangement, all around, along with locking arrangement. board (Make – Cellotex or equivalent) wrapped with stretched blazer cloth (Make- Raymonds), of Rs. 200.00 per Mt. (approx.) in colour and pattern approved by the Architect. It shall be fixed with help of nail/partial wood (sect. 19mm x 25mm) frame work. It shall be covered with 6mm thick water proof plywood, on the back. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.				
<b>12</b>	<b>False Ceiling(Armstrong)</b>	600.00	Sq.Ft.		
	Providing and fixing in position false ceiling in armstrong 600 x 600 x 15 /16 mm dune supreme RH 99 prima tile with regular edge frame work as specified by armstrngcompany with suspenders making necessary frame work for A.C. Ducting for diffusers and light fitting.				
<b>13</b>	<b>False Ceiling Works (Gypsum)</b>	500.00	Sqft		
	Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop upto 1'6" etc				



S.NO.	DESCRIPTION OF ITEM	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
14	<b>Low /full height Storage Racks</b>				
	S1-Storage (Low Height)				
	Size- 6' Length X 2'-6" highX 1'-4"deep				
	with shutters, shelf 19.0mm ply				
	Shelf-19.0mm thick MR Grade IS303 ply				
	Handle-Brush finish stainless steel				
	Lock-Vijayan/Godrej				
	All internal & rear surfaces to be painted with two coats of enamel paint over a coat of primer / putty as directed to get a smooth finish.All instructed by Bank's Engineer/Architect.	98.00	sqft		
15	<b>Etching Work &amp; Bank logo for Branch</b>	75.00	sqft		
	Etching for Toughened glass((Branch and ATM) , Etching for Cash Cabin Glass , Etching for Front counters				
	Etching work on glass with chemicals (as per design and profile) as and where required. The rates shall include cost of all materials, labour, T& P, wastage, transportation etc. required for proper completion of work. It shall be made out of following profile.-Bank's logo (300mm dia. / 300mm x 300mm).All complete to the satisfaction of the Architect.				
16	<b>Column &amp; wall Panelling (As per Direction BY Architect )</b>	45.00	Sq.Ft.		
	Providing & fixing in position 2"x2" kailwood frame and finished with 6 mm thk. Premium Board (Green /Century) on both sides with1.0 mm thk. Laminate on top as per instruction of the Architect.				
<b>Total =Rs</b>					
<b>Total GST Amount(Rs.)</b>					
<b>Grand total Amount</b>					
<b>Amount in Words</b>					
<b>MATERIAL SPECIFICATION</b>					
1	BLOCK BOARD	ARCHID/Century /Kitply/ Green (BWP Grade)			
2	PLY BOARD	ARCHID/Century /Kitply/ Green (BWP Grade)			
3	LAMINATES				
	FOR PARTITIONS/TABLES/COUNTER SURFACES	Century ply, Sunmica, Formica ,Green lam or Equivalent(Colour Shade--Fusion Maple (wood Finish))			
	FOR BOARDER AND SKIRTING	Century ply, Sunmica, Formica ,Green lam or Equivalent (As decided by Bank)			
4	GLASS	Modi/Saint Gobin/ Indo Asahi/Triveni			
5	GYP BOARD	India Gypsum or equivalent approved.			
6	LOCKS/HANDLES	Godrej/Harrison/Vijayan			
7	DRAWER SLIDING FITTING	Earl Bihari (EBCO)/Godrej/Blum or equivalent			
8	FLOOR SPRING/DOOR CLOSER	Sandhu / Hemco / Hardwin or equivalent approved.			
9	OTHER MATERIALS	ISI mark & approved by the Bank.			