

PREMISES, ESTATE & EXPENDITURE DEPARTMENT, CORPORATE OFFICE, NO: 254-260, AVVAI SHANMUGAM SALAI, CHENNAI – 600014.

BID DOCUMENT - PROVIDING & FIXING OF MODULAR WORK STATIONS FOR SETTING OF CAPC & MCB IN INDIAN BANK PREMISES AT FIRST FLOOR, GEE GEE COMPLEX, NO.:42,ANNA SALAI, CHENNAI - 600002

PART-II FINANCIAL BID

Ref.No: CO:EST:CAPC -04 Date : 02.01.2021

Name of	the contractor:

Last date of submission of	20.01.2021 upto 15.00Hrs. at Indian Bank, Corporate Office, Premises,
tenders	Estate & Expenditure dept, First Floor, No. 254-260, Avvai Shanmugam
	Salai, Royapettah, Chennai – 600 014.
Date of opening Tender	20.01.2021 upto 15.30Hrs . at Indian Bank, Corporate Office, Premises, Estate & Expenditure dept, First Floor, No. 254-260, Avvai Shanmugam
	Salai, Royapettah, Chennai – 600 014.
Cost Of Tender	Free Of Cost.

This part of the tender should be submitted in a separate envelope and financial bid shall be quoted only in this form and no other form will be accepted.

This Tender document contains 05 pages





Schedule of Quantities

Quote for Providing Modular Works Station for CAPC & MCB at F.Floor No.:42,Gee Gee Complex, Anna Salai, Chennai - 600 002

SI No	Description	Unit	Qty	Rate	Amount
Α	MODULAR FURNITURE				
1	Branch Manager Table & Side Unit	Nos	2		
	Supplying and installation of Table and Side unit as per specification:- Table size: 1800*750*750 mm and side table: 1050mm*450*750 mm				
	Main Table (1800*750*750 mm): <u>Understruture</u> made of straight leg which should be fabricated with cross connector by welding MS CRCA ERW Squre Tube of size 50.8mm X50.8mm x 1.6 mm thk with the base of MS tube fitted with Glide Plate Over M8 X50mm metal leveller. The leg shall be supported by the cross connector, which shall be MS ERW RHS 50 mm X25mm (RHS) ,1.6 mm thick members at two levels in 3 side along with 500mm ht X1.2 mm thick CRCA sheet as a perforated stiffener (Lazer cutting as per design) by suitable welding.				
	The under structure shall be finished within 60 -80 micron thickness of epoxy polyester powder coating. The table top shall be 12 mm thick toughened glass with lacquered finish as per design fixed by SS studs through the legs along with PU rubber gasket with all accessories for firmly fixation.				
	Side Table (1050mm*450mm): The same as above but top shall be finished with 25 mm thick twin prelaminiated (0.8mm thick) Board with 2 mm pvc edging, to be fitted on the MS straight leg by suitable accessories the rate inclusive of providing wire management by Soft closing access flap as per approval.				
	The rate including accessories: Metal CPU trolley (safe load 20 Kgs). & Key board tray should have 1.2 mm thick CRCA sheet with slides Tray size should be 540mm* 197mm fixed on the side table top (bottomside).				





2	ABMs Table	Nos	2	
	Supplying and installation table size: 1500*750*750 mm but without Side Unit and the Table top shall be Prelaminated board as detailed below Construction details: the same as item No.:1 but the size of the table shall be 1500*750*750mm and top shall be 25mm thick Pre Laminated board confirming to IS:3087 laminated with laminate of thickness 0.8mm confirming to IS: 2046 and glued with PVC. 2mm PVC lipping to be done which is glued with Hot melt EVA glue and to be fitted under structure.			
	The rate inclusive of providing wire management by Soft closing access flap as per approval and the rate inclusive of CPU trolley			
3	SWASTIK WORKING MODULAR TABLE Size 1350X750X750mm X 4 Nos = 1 Unit(1Nos)	Nos	20	
	Table Top: Supplying and installation of Swastik type Working Table,25 mm thick of Grade II Type II conforming to IS 3087-2005 with laminated IS 12823:1990 pre laminated finished with approved shade. The particle shall be of uniform thickness and uniform density through the length and width of the boards, with 2mm PVC edge banding finishes. All particle boards shall be flat. Both surfaces of the particle boards shall be sanded to a smooth finish and same shall be fixed 25mm metal clip support (or approved clip) with under structure ,Race way,Softclosing access flap etc, Privacy Divider (by White board & Magnetic Fabric Board), C.P.U trolley as per below specification. Under Structure: Swastik type Under structure for 4 Nos Works Station made of straight leg which should be fabricated with cross connector by welding/bolding. All the outer vertical legs shall be MS CRCA ERW Square Tube of size 50 mm X50mm Dia x 1.6 mm thk with the base of MS tube fitteded with Glide Plate Over M8 X50mm PU leveller. The legs shall be supported by the cross connector, which shall be MS ERW RHS 50			
	mm X25mm (RHS) ,1.6 mm thick members at upper level for table top stability. The Middle Vertical raiser 4 Way connecting pole made-up with 1 CRCA sheet 300X300X1.2 mm thick. The rate inclusive of 400mm X 1.2 mm thick CRCA sheet as a Modesty Panel (Lazer cutting as per design) by suitable welding for two sides of the each table (front & side)			





	Wire Management/Horizontal Race Way: MS 1.2 mm thick race way shall be provided for vertical & horizontal wire management in the centre of the under structure along with provision for 20 moduler switch plate in build metal power box. The under structure including race ways. All the under structures, race ways shall be finished within 60-80 micron thickness of epoxy polyster powder coating. Table Top: The table top shall be 25mm thick twin side Pre Laminated board confirming to IS:3087 laminated with laminate of thickness 0.8mm confirming to IS: 2046 and glued with PVAC. 2mm PVC lipping to be done which is glued with Hot melt EVA glue and to be fitted under structure by MS supporter. the rate including provising softclosing access flap having 450/500X120mm in the table. The rate including accessories: Metal CPU trolley (safe load 20 Kgs). Key board tray should have 1.2 mm thick CRCA sheet with slides Tray size should be 540mm* 197mm fixed on the table top (bottom side). Privacy Divider (partition) in centre of the table: Front side Partition for a length of 1200 mm X450mm, the panel partition shall be 25/30 mm thick powder coated suitable aluminium extrusion vertical trim and horizontal trim. Privacy panel shall be white board & Magnetic Fabric Board back to back each table (4 Nos). The fabrics should be upholstered with adhesives back to back, The suitable fixing arrangement to be made for firmly fixation on the under structure. The rate inclusive of necessary fittings & hardware as per approved design above tabletop. The Cost to include the supporting system to privacy divider & under structure such as brackets /fasteners /joining posts / race ways / wire management cleats / runners etc.(Basic cost of fabric Rs. 300/- per running meter.The shop drawing shall be approved			
4.	MOBILE PEDESTAL	Nos	85	
	:Providing and installing drawer boxes (Box Box File) of size 650 mm ht., 390mm width and 450 mm deep made out of18mm thk pre laminated particle board Grade II & Type-II (IS12823: 1990; Reaffirmed 2005) finished with 0.8mm thk laminate twin side, front and sides made of 18 mm thk pre laminated particle board Grade II & Type-II (IS 12823: 1990;Reaffirmed 2005)finished in 0.8mm thk laminate and back, drawer bottom to shall be metal box ,2 nos. minimum 120mm high drawer & 1minimum 275mm high filing drawer. Handles to be provided. Central locking to be given for each pedestal Soft closing and Anti slam mechanism for pedestal. M8 Leveling stud for free standing pedestal. The anti-tipping mechanism should have fitted in the roller arrangement mounted below file drawer to avoid toppling of unit when file drawer is pulled out.	.100		





SUMMARY OF MODULAR WORKS STATION					
SL:No	Description	Unit	Qty	Rate	Amount
1	Branch Manager Table & Side Unit	Nos	2		
2	ABMs Table	Nos	2		
3	SWASTIK WORKING MODULAR TABLE Size 1350X750X750mm X 4 Nos = 1 Unit(1Nos)	Nos	20		
4	MOBILE PEDESTAL	Nos	85		
	Total				

Total Amount in words: Rupeesonly				
GST (taxes) will be extra				
Place:	Signature & Seal of the Tenderer			
Date:				

