

Tender Document for furnishing work of Panaji Branch, Indian Bank

Sr. No.	MATERIALS	APPROVED MANUFACTURER / BRAND	Code No. / Basic rates with GST
A	<u>FURNITURE ITEM</u>		
1	Plywood	Regency suffier, Century Sainik / Blue berry / Anchor - Sevak	18mm -Rs.75 12mm -Rs.40 6mm -Rs.25 per sqft
2	MDF Board	Green ply (uttranchal), Archid (uttranchal), Merino	4 mm -Rs.12 6mm - Rs.16 per sqft
3	Teak wood based Particle Board		
4	Gypsum Board – Partition / Paneling	India Gypsum Co. Ltd.	Rs.18 per sqft
B	<u>FINISHES</u>		
1	Laminates	Royale touch / Formica / Green lam / Sunmica	Rs.45 per sqft
2	Veneer (decorative plywood)	Green ply industries / Archid	
C	<u>HARDWARE</u>		
1	Door Closer	Godrej / Enox / Ozone	
2	Floor Springs	Enox / Ozone	
3	Locks	Ebco / Godrej /	
4	Point fittings, Fixing screws		
5	Patch fittings	Enox / Ozone	
5	Drawer Channels	Telescopic – Ebco / Godrej / Appex	
6	Handles	S.S 304 GRADE BRUSH FINISH	
7	Auto closing Hinges for shutters	Ebco	
8	“W” & “Z” Hinges for shutter	Heavy- Brass hinges & S.S hinges of Rockline/Floora	

Tender Document for furnishing work of Panaji Branch, Indian Bank

9	Butt Hinges for Door	Heavy – Brass hinges/ S.S hinges, of Rockline/Floora	
10	CPU Trolley	Made by 18 mm plywood	
11	Keyboard tray with Mouse pad	Made by 18 mm plywood	
12	Screws	G.K.W., Nettle fold.	
13	Adhesives	Fevicol SH, Araldite of FalcoFix	
D	<u>OTHER</u>		
1	Acoustical Tile		
2	Aluminium Composite Panels		
3	Float Glass	Modi, Asahi, Saint Gobain	
4	VERTICAL / roller Blinds	Parrytex / Vista	
5	Tapestry	Vimal- Harmony / Raymond / Classic fabrics.	
E	<u>CIVIL ITEMS</u>		
1	Ceramic Floor tiles	Nitco / Asian / Kajaria/ RAK / Jhonson /	Rs. 70 per sft.
2	Vitrified Floor tiles	Jhonson / Asian / Kajaria / RAK (1 st quality) / Jhonson	Rs. 110/70 per sft.
3	Ceramic Dado tiles	Nitco / Asian / Kajaria / Jhonson /	Rs. 60 per sft.
4	Waterproofing compound	Aceproof of Dr Fixit	
5	G.I. Pipes		
6	PVC pipes	Kisan / Prince / Finolex make.	
7	Epoxy based waterproofing		
8	Cement	Rajashree, Ambuja, Ultratech- Birla.	
9	Sand for plastering etc.	.	
10	Sanitary fitting		
A	Wall mounted closet	Parryware / Cera / Hindware	Rs. 15,0000
B	Wash basin		
C	Urinal's		
D	Orissa pan		

Tender Document for furnishing work of Panaji Branch, Indian Bank

E	Anglo Indian w.c with cover		
11	Taps	Jaquar – continental, Jaquar Escco	
12	Stainless Steel Sinks		
13	Aluminium Windows / Doors	Jindal make sections of approved guage.	
14	Mosaic Tiles		
15	Granite		
F	<u>FALSE CEILING</u>		
1	Gypsum Board –Ceiling / Partition/ Panelling	India Gypsum Co. Ltd.	
2	Modular Ceiling	Armstrong	
G	<u>PAINT</u>		
1	Fire Retardant Paint.		
2	Paint	Asian Paints.	
3	Textured Paint		

CONTRACTOR

INDIAN BANK

Tender Document for furnishing work of Panaji Branch, Indian Bank

	SUMMARY	AMOUNT
	INTERIORS	
	TOTAL OF SUSPENDED FALSE CEILING	
	TOTAL OF PARTITIONS WORK	
	TOTAL OF DOOR & ACCESSORIES	
	TOTAL OF WORKING COUNTER	
	TOTAL OF TABLE & FURTINURE	
	TOTAL OF STORAGE & SIDE UNIT	
	TOTAL OF OTHER MISCELLANEOUS ITEMS	
A	TOTAL	
	GST AS APPLICABLE	

Tender Document for furnishing work of Panaji Branch, Indian Bank

A	SCHEDULE - 'A' (FURNISHING WORK				
S. NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
1	SUSPENDED FALSE CEILING				
1.1	FALSE CEILING (GYPSUM BAORD)	sq.m	25		
	<p>Providing and fixing Gypsum false ceiling as per drawing including of providing And fixing G.I. Frame work shall comprise of G.I. perimeter channel (MF - 6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling ,screw fixed to the beam to the required curvature with nylon sleeves and screw at not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc.</p>				

	<p>The joints to be properly mended with paper tapes and gypsum compound all complete. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for gypsum board .A layer up to of 3.00mm thickness of veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be competed as per specification, approval of the bank. No Drop or design (if any) will be considered as extra measurement it will be considered flat ceiling. (only plan area to be measured for payment). No extra payment will be made for the cutting of light points, stain glass, stain glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, no extra amount will paid for the drops.</p>				
--	---	--	--	--	--

		UNIT	QTY	Rate	Amt.
1.2	FALSE CEILING (ARMASTRONG CEILING –FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL)	Sq. m	52.00		
	Providing and fixing ceiling system manufactured by M/s. Armstrong world Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. Wall angle of size 19 x 19 mm, having 0.33 mm gauge fixed to the periphery of the wall. the above grid is suspended at every 600 mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL) Ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mm x 600mm x 15mm having NRC 0.55, Light reflection of >84 (WT), Thermal conductivity k = 0.052-0.057 W/mOK, Humidity Resistance of 99, having Fire Performance CLASS O/ CLASS 1 (BS 476), surface having 3 coats of white paint with fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete. (BRANCH & ATM) .				

1.3	Wooden Ceiling – Fabricating & fixing in position wooden false ceiling consisting of kailwood battens 2” x 2” section in framings grids as per drawings (framework to have coating of fire retardant and anti-termite paint) with 12mm thick ply and 1.0mm thick laminate topping fixed to the framework as per drawings , i / c necessary M.S. hangers, screw , clips etc. complete I / c melamine polishing and polyurethane coating complete as per detailed drawing.	Sq . Ft.	0.00	-	-
	TOTAL OF SUSPENDEED FALSE CELING				
2	PARTITIOUS WORK				
	FULL HEIGHT SOLID PARTITON	Sq. m	65		
	Ful ht. Solid Partition including flush door :- Providing and fixing solid partition , the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL as internal frame structure placed horizontally & vertically at max distance of 2’ -0” center to center.				

Tender Document for furnishing work of Panaji Branch, Indian Bank

<p>Fixing 8 mm thick commercial ply on both sides with 1.0mm thick laminate on top of approved shades with groove pattern as per instructions pf Architect. The rate shall include the cost of providing skirting of 100mm wide lined with 1mm thick laminate complete. Laminate should be considered up to two or three colour combination. The edge beading with steam beach wood should be finished with melamine polish if required , frame work above false ceiling done shall not be measured but contractor may factor quoting there rates as measurement up to false ceiling lvl...</p>				
<p>The rate inclusive of providing & fixing required flush door of 37mm thick approx. with 1.0mm th. Laminate both sides with steem beech wood chowkhat of size 75mm x 65mm approx and Item includes Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 nos. per shutter) with screw etc. the shades of laminate finish to be got approved from Bank . All as per the design and instruction Bank</p>				

	UNIT	QTY.	Rate	Amt.
<p>Note : - for the purpose of payment partition shall be measured including the area of door / door frames up to false ceiling height.</p>				
<p>Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2" -0" c/c with dash fasteners.</p>				
<p>2.2 Single skin partition</p> <p>As of the above but Providing and fixing single skin partition above false ceiling (where false ceiling is provided only on one side) for a height of up to 600mm or neat about soffit of roof using aluminium frame as specified above along with 6mm thick commercial plywood lined on only one side and lining with 1mm thick laminate of approved shades and make along with grooves.</p>	Sq.m	25.00		
<p>2.3 Full height glazed partition</p> <p>Same as of Solid ht. partition , providing 8mm thick Modi /saint Gobin float glass above 1' -0" / 3'- 0" & up to 7'- 0"fixed with steam beech wood beading of finished size 1 ½" x 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. Joint shall be located strictly as shown in the drawing. All exposed woodwork to be mealamine polished. Item included frosted/striped/designer glass film of 3m, Avery Dennison or equipment (basic rate of film Rs. 50/ sq.ft) on existing glass as per manufacturer's specifications. All as per the design and instruction Bank.</p>	Sq.m	55.00		
<p>2.4 Low. Height Semi Glazed Partition</p> <p>Same as above but of low height as per design</p>	Sq.m	12.00		

	including 10mm Toughened glass with edges polished to be used. All other specs are same as of above, Edges of the partition to be covered with 3" x 1.5" steam beech wood duly melmine polished moulding. 38mm thick flush door: wicket gate also shall be included for a measurement. All as per the design and instruction bank.				
2.5	Front Glazeing In head cash cabin & SWO	Sq.m	5.00		
	Providing & fixing 10mm thick toughened clear float glass to shape for front side of the cash counters including cutting the holes and providing & fixing TW beading polished and tinted to approved shades. (including SWO/ Chief Cashier front Glass).				

2.6	ACP WALL PANELLING (AT ENTRANCE DOOR FOR BOXING PURPOSE –ATM QTY IS DELETED QTY IS REDUCE):- Providing & fixing in position ACP (Aluminium Composite Panel) with ways. ACP to be in 2' wide panels or distributed equally. Panels to be fixed to the frame with 3M or equivalent adhesive. Joints to be finished with silicon based sealant. Minimum ACP thickness -3mm. Aluminium foil thickness to be min 0.25mm on both sides .Alubond, Eurobond, fujibond, Alcobond or equipment ISO certificate or approved brands to be used. White (IVORY) & Blue to be as per bank's approval. Additional sections to be provided to fix the Indoor AC units.Both AC units to be installed near the machine area at the highest position. The rate shall be included for providing proper access panel for ATM power point and shall have proper locking arrangement for plug point by providing additional framing (The measurement shall be made up to false ceiling).including work near entrance.	Sq.m	15.00		
2.7	BACK ROOM (ATM) – Providing and fixing partition made up on aluminium box section with 2" x 2" and 20 gauge with 2' 0" c/c both ways , and to be fixed on inside 3mm thick Aluminium Composite panel and rear side (only where backroom/storage is available) with 8mm thick plywood finished with 2 –coat colour enamel paint. The rate inclusive of providing and fixing of suitable shelve for fixatation CCTVs instrument & UPS extra (1Nos.) & Access Door with teak wood louvers, and necessary accessories including handle & locking design and instruction Bank. The item shall include suitable cutting & provision for installation of ATM facility.	Sq.m	7.20		
	Note:- for the purpose of payment partition shall be measured including the area of door / door frames				

	up of false ceiling height. Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2' -0" c/c with dash fasteners.				
2.8	Grouting:- ATM to be firmly embedded into the ground with para bolts/ anchor bolts through the SAFE of the ATM. Scope of work includes moving /titling of machine, drilling 8" -10" holes in the existing flooring using concrete drill bits, Hammering metal in these holes, Repositioning the machine over the existing markings, Anchor fasteners to be put in place, Min. 6" Long anchor finished bolt positions for improved bonding and Repairing the broken tiles, if any	job	0.00		
	TOTAL OF PARTITIONS WORK				
3	DOOR & ACCESSORIES				
3.1	Main Entrance Door PT Door	s.qm	5.20		
	Providing and fixing toughend glass door shutters of 12mm thickness in opening of glazed partitions with stainless steel patch fittings of approved make (DORMA/DLINE / GEZE or approved equivalent) including heavy duty double action floor-spring with steel cover plate of approved make , pull handle SS brushed finished 24" long thick 25mm on both sides of door shutters, locking arrangement of Dorma / D Line or equivalent or better quality as approved by Engineer -in - charge . Exposed edge of glass shall be machine cut & polished . Cost includes cutting and making good the floor, walls, ceiling etc. for fixing spring and patch fittings . All complete as per approval of the Architect.				
3.2	Main Entrance Fixed PT Glazing	Sq.m	12.00		
	Providing and Fixing toughend glass partition of 12cm thickness with stainless steel patch fittings of approved make (DORMA /DLINE / GEZE or approved equivalent as approved by Engineer - in charge. Exposed edges of glass shall be machine cut & polished. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing patch fittings. All complete as per approval of the architect.				
3.5	Supplying and fixing of dorma / GEZE DLINE / HARDWYAN / GODREJ or approved equivalent door closer for wooden door for Branch Manager, Banking hall, chief Cashier, Dinning, UPS, Toilet	-	-	-	-

3.6	Supplying and fixing of mortice door lock of hardwyn make HML-480 Lock Body 304 Stainless Stell . (in BM Cabin , State room 0.Cash cabin shall be Godrej Night latch . (atm 1 No.)	Nos	-	-	-
3.7	Supplying and fixing of door stopper SS Grade 304 , HESSF-2C hardwyn make .	Nos	-	-	-
TOTAL OF DOOR & ACCESSORIES					
4	WORKING COUNTER				
4.1	CASH/STAFF COUNTERS	rm	1.50		
	Providing and fixing Chief Cash Counter in split-level 2' -6" (height 750mm) & 18" (1140mm) with 2' -6" & 15" wide each respectively . Upper levels having 20mm thick, black granite glued with approved adhesive to 19mm thick commercial ply top (Basic rate of granite Rs.180/- sq.ft i/c taxes and transportation).Edges of 18" wide counter shall be double with matching granite and shall be rounded and machine polished. Lower tier shall be made of 19mm thick ply wood finished in 1.5mm thick laminate. Exposed edges having steam beech wood edging of size 1 ½ x 1". Vertical face shall have 19mm thick ply wood over pine wood framework as per requirement of design. All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade and colour.				

	1 No. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L - brackets for securing to the table top. Chest of drawing (size 1' - 4" x 2' - 5") made of 19mm thick commercial ply wood having three drawers finished with 1.0mm thick Laminate on all slides . Each drawer shall have locking system and 6" long S.S. brushes finished handle, drawer slides etc. of approved make. All exposed edges of ply wood sealed with steam beech wood beading of size ½ x ¾ . All beading and exposed wood shall be melamine polished and non-laminate surface to be enamel painted. Item included readymade metal powder coated CPU trolley, grommet, footrest for each seat. All complete as per approval and instruction of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1 st class seasoned country frame.				
	Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined lined with				

	1.0mm thick laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thick laminate complete .				
4.2	RUNNING COUNTER	r.m	2.40		
	Providing and fixing staff counter/SWO in splits-levels 2' -6" (750mm) & 3' 1" with 2'-6" (750mm) & 9" wide each respectively. Upper levels having 19mm thick black granite with full round edges glued with approved adhesive to 19mm thick commercial ply top (Basic rate of granite Rs. 180/- Sq.ft. i/c taxes and transportation). Lower tier shall be made of 19mm thick ply wood and finished in 1.5mm thick laminate. Working top having steam beach wood edging of size 1 ½ x 1" .Vertical face shall have 19mm thick commercial ply over pine wood framework as per requirement of design . All exposed edges of ply wood sealed with seam beech wood beading of size ¼" x ¾ . All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade.				

	The item includes chest drawers (size 1' - 4" x 2' - 5") made of 19mm thick commercial ply wood having one drawers at top and a storage Cabinet below having shutters of 19mm thick ply wood finished with 1.0mm thick Laminate on all sides. 1no.prefabricated metal computer key board tray including drawer slides 12.5"mm x 22" tray with 14" telescopic slides including L - brackets for securing to the table top for each seat. All beading and exposed wood shall be melamine polished and non-laminate surface to be enamel painted. Item includes 1'-3" high 12mm thick toughned glass above upper tier and readymade metal powder coated CPU trolley ,grommet, foot each seat. All complete as per approval and insructions of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1 st class seasoned country frame. Payment will be made only on the centreline measurement.				
	The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thick laminate and providing & fixing a boarder at top of 100mm wide lined with 1.0mm thick laminate complete.				
	TOTAL OF WORKING CAPITAL				

5	TABLE & FURNITURE				
5.1	MANAGER TABLE (SIZE :- 5" X 2' -6") ht . 2'-6"	nos	1.00		

	Providing and fixing tables made out of 19mm thick commercial ply over hard wood frame work finished with 1.5mm thick laminate of approved shade .Top having steam beech wood edging of size 2" x 1 ½ . 10mm thick clear float glass with beveled edges shall be provided on the finished to 19mm thick comm. Ply wood of approved make cladded with 1mm thick. Laminate (colour with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly melamine polish. The drawer to be made out of 19mm thick ply wood with 1.0mm laminate finish in the front, and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint & Table back side will be 1mm laminate. A leg rest to be provided duly polished made out of 3" x 2" wooden section. The rate inclusive of providing & fixing wooden cabinet to suit the DVR for size 2' k6" x 1'9" or as per the requirement.				
	A shutter to be made by 19m plywood cladded with 1.0mm laminate. The necessary locks handles to be provided in each drawers and shutters. 3" x ½" wooden skirting to be provided in all visible areas duly polished. The necessary wire managers (SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be duly malamine polished The work to be complete as per design and approval of the bank. The table should have key board tray and CPU trolley to be Modular. All as per design and instruction Bank.				
5.2	Officer table same as above without glass top(5' 0 x 2' 6") height 2'6"	Nos	4.00		
5.3	SERVER TABLES (2' - 0" WIDE)	r.m	1.85		

	Providing and fixing of Utility // Server Counter 2'-0" wide top made up of 19mm thick commercial pasted on 1.0mm thick. Laminate. The top of table will be finish with 1.00 thick laminate. All hardware fittings fixtures etc. The drawers to be made out 19mm thick board eith 1.0mm laminate finish in the front , sides to be made out of 12mm plywood and bottom to be made out of 6mm				
--	--	--	--	--	--

	plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and details of the table shall be as per design. (As per site, Designing of table and specification may be Changed) .The woks to include a keyboard try and CPU trolley to be modular . All as per the design and instruction Bank . (s. s. Finish Lock & Handle to be included)				
	TOTAL OF TABLE & FURNITURE				
6	STORAGE & SIDE UNIT				
6.1	Side and Back Unit	Sq.m	8.66		
	Providing and fixing side Unit/ Back unit 400mm depth made up of 19mm ply wood finished with 1.0mm laminate in all exposed areas and top shall be 1.5mm thick . The drawers to be made up of 19mm commercial plywood and cladded with 1.0mm laminate and bottom made out of 6mm comm ply duly painted in matching tone and it should play on drawer sliding channel . The shutters to be made out of 19mm commercial ply on drawer sliding castors on powder coated channels .The necessary locks, handle, etc to be provided. 3" x ½ wooden skirting to be provided duly polished as per matching tone all along the visible area. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards / ply woods to be covered with wooden lipping / /moulding duly polished all complete. The work to be completed as per approval and specification of the Architect .				
6.2	Full HT Cabinet UNIT	Sq.m	15.20		
	Providing and fixing Full / Low height Cabiner 400mm deep made out of 19mm thick plywood finished with 1.0mm laminate in all exposed areas . The Shutter to be made out of 19mm ply wood in the front cladded with 1.0mm laminate (colour, vertical grain). And bottom made out of 6mm plywood duly painted In matching tone and shelves 19mm ply wood. The necessary locks , handles, etc to be provided . 3" x ½ wooden skirting to be provided duly polished as per matching tone all along the visible areas . Inside of the unit to be enamel paint finish. All the exposed edges of the boards/ plywood to be covered with wooden lippings/ mouldings duly polished all complete. All as per the design and instruction Bank.				

Tender Document for furnishing work of Panaji Branch, Indian Bank

6.3	Main Electrical Panel Cabinet	Sq.m	2.40		
	Providing and fixing of DB Shuttering formed of 12mm thick plywood on 12mm thick Gypsum board (fire proof) with finish as per Item no 1 for inside and outside shutters finished with laminate on outer surface with SS (4Nos) louvre perforation and necessary hardware, hinges etc complete as per details. All as per the design and instructions Bank				
	TOTAL OF STORAGE & SIDE UNIT				
7	OTHER MISCELLANEOUS ITEMS				
7.1	PIN UP / NOTICE BOARD				
	Providing and fixing soft board with necessary framework with 12mm BWR plywood on top 12 jolly board to be fixed finished with fabric Rs.80 ,necessary instruction Bank .	Sq.m	2.40		
7.2	PAINTING PLASTIC PAINT (landlord scope of work)	Sq.m	0.00		
	Applying 2 coat putty with primer and Providing and applying Plasterwork including Plastic emulsion paint (Asian)of approved make and shades on walls including scrapping off, preparing the base & applying 3 or more coats of approved make, colour and shades to give an even and smooth surfaces on new scaffolding, coat of cement primer etc. all complete as per direction of Bank. (only banking hall).				
7.3	Applying 2 coat of Plastic emulsion paint (Asian) of approved make and shades on walls including scrapping off, preparing the base ect colour and shades to give an even and smooth surfaces on new work including necessary scaffolding, coat of cement primer etc. all complete as per direction of Bank. (Other than banking hall).	Sq.m	-	-	-
7.4	WRITING LEDGER & Cheque & suggestion box	NO	1.00		
	Providing and fixing writing ledge as per design minimum 5ft length made out 19mm comm. Board with necessary grooves patterns with 1.0mm laminate. 10mm thick machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 12mm comm. Ply to be made on top of the writing ledge finished with 1.0 mm laminate , inside enamel painted and rate should be included providing fixing of suggestion box & Cheque deposit box as per approval of bank . The work to be completed as per design and approval of the architect.				
7.5	Other Shutter Boxing (This item is there for covering up of open shutter box of rolling shutter				

	of branch , hence reconnended to be retained)				
	Overhead outside shutter box : p/f sal wood frame fixing of 12mm plywood with 1mm thick. Laminate finish and openable shutter for out side area inside shall be 2 coat enamel paint with primer	Sq.m	30.00		
7.6	PILLAR PANELLING	Sq.m	0.00		

	Fabricating and fixing wall / column panelling, the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL at spacing not exceeding 600m both ways (horizontal and vertical) . Paneling framework to be secured to wall surfaces / column surfaces . Paneling framework to be clad on one side with 9mm thick ply finished with 1.0mm thick laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. All as per the design and instructions Bank.				
	Decorative Front Face PILLAR PANELLING				
	Providing , fitting and fixing in position, Glo board of approved design, shape, shades, pattern at all levels, for ceiling, walls, partitons, window sills, jambs, soffits and trims etc. finished neat in line, length and plumb, cutting and finished with matching wooden beading at edges and painted with two coats of Duco paint over one coat of primer including all labour, material, equipment, handling, transportation, scaffolding, workmanship, cleaning after fitting and fixing etc all complete including wastage ,with all clips, ss studs/ gutkas (wooden / acrylic), beading, neoprene / rubber / nylon clear gaskets etc as required as per specification, drawing and instructions of EIC.				
a	15 mm Glo grill board of panel size (8' -6' x 4')	Sq.m	0.00		
	Providing , fitting and fixing in position , minimum 3mm thick approved Acrylic sheet of approved colour , shade and pattern at all levels (fixed with 25 x 25 acrylic gutkas) over MDF grill board board etc. For ceiling, walls partitons, window sills, jambs soffits and trims etc . finished neat in line lengths and plumb, cutting and finshing including all labour, material, equipment , handling, transportation, scaffolding, staging, workmanship, cleaning, after fitting and fixing etc all complete including wastage with all clips, beading,	Sq.m			

Tender Document for furnishing work of Panaji Branch, Indian Bank

	neoprene/rubber/clear gaskets etc as required as per specifications, drawing and instruction .				
7.9	ROLLING BLINDS	Sq.m	7.00		

	Providing and fixing Roller blinds of approved design and shades by the Architect, include all std fittings as per manufacturer's specification . The work to be completed and approval of the architect. (approved brand vista, Hunter Dogulus)				
7.1	Modification to staircase	NO	1		
7.2	CLEANING OF PREMISES	NO	1	-	-
	Since painting is in landlord scope of work the contractor will have to clean the entire premises and furniture after the painting is done and handover spic and span premises to the Bank				
	TOTAL OF OTHER MISCELLANEOUS ITEMS				
	GRAND TOTAL FOR FURNISHING (A)				