

INDIAN BANK
OFFICE BUILDING, INDIAN BANK, MEERUT

Sealed quotation are invited from the eligible empaneled contractors for Interior Furnishing works Category in INDIAN BANK and ALLAHABAD BANK for Renovation works of Reception Lobby of Office Building Indian Bank, 55 The Mall Road, Meerut Cantt, Meerut.

Last Date for submission in sealed cover envelope in the office of the Field General Manager, Indian Bank, FGM Office, 55 The Mall Road, Meerut Cantt, Meerut is 07.08.2021. The bids will be opened on the same day at 5:00 P.M.

Format for tender document can be collected from Indian Bank, FGM Office, 55 The Mall Road, Meerut Cantt, Meerut.

List of Approved Makes for above mentioned Works:

1. BOARD, PLY & MDF	Century/ Green Ply/ Archidply- Gold
2. LAMINATES	Century/ Green lam/ Merino
3. PAINTS	Asian Paints/ Nerolac/ Dulux
4. GRID CEILING	Armstong/ Hunter Douglas/ Boral
5. GYPSUM	Saint Gobain/ Gypsum India
6. MOLDINGS	Teak/ Sal wood/ White cedar wood
7. GLASS	Saint -Gobain/ Asahi/ AIS
8. ALUMINIUM SECTION	Hindalco/ NALCO/ BACL
9. DOOR & LOCKS FITTINGS	Ozone/ Dorma/ Hettich

The Bank reserves the right to accept/reject any tender/quotation without assigning any reason whatsoever.

Date: 31/07/2021

Field General Manager
Indian Bank, Meerut

Renovation works of Reception Lobby of Field General Manager's Office, Meerut

Sl. No.	PARTICULARS	UNIT	QTY	RATE	AMOUNT
1	FALSE CEILING (24"x48" GRID FALSE CEILING)				
i	24"x48" Grid False Ceiling Providing and fixing in the true horizontal level false ceiling system of Armstrong world industries. The suspension system shall be the Armstrong Trulock Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color black or white revealed Silhouette main runners and cross tees to have mitered ends with birds mouth notches to provide mitered cruciform junctions. Main runners to be spaced at 12mm c/c fixed by using 2mm pre straightened GI Wire.Main tee,rotary stitched of size 15mm x44mmx3600mm at every 1200mm c/c maximum and 1200mm cross tee of size 15mmx44mm x1200mm at every 600 mm c/c maximum and 600 mm c/c cross tee of size 15 mm x 44 mm x 600 mm at every 1200mm c/c maximum and 19mmx19mmx3000 wall angle All as per the design and instructions Architects (make- Armstrong)All as per the design and instructions Architects.	SFT	260.00		
ii	Providing and fixing GYPSUM BOARD FALSE CEILING in levels as per the detailed drawing - made up of G.I frames as specified by Gypsum India/Saint -Gobain Gyproc and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel of size 20X27X30 mm and 0.55 mm thick for light fittings, AC Grills, diffusers, suspenders etc. shall be standard sections supplied by Gypsum India/ Saint Gobain. Spacing of intermediate channels shall be at 1200 mm c/c and ceiling section at 457 mm c/c. The work includes taping and jointing, applying primer, two or more coats of plastic emulsion paint of approved shade ICI/ ASHIAN PAINTS make, making cut-out for light fixtures /fittings, etc. The Final coat shall be done with FOAM ROLLER and no brush marks should be visible. Providing of perimeter channels / beading etc. as per drawing complete in all respects.(All measurement in sqft only and finished surface area shall be measured)	SFT	300.00		
2	GLASS DOOR WITH GLAZING				
	Providing and fixing of 12mm toughened glass door with 18" long SS handles, floor spring (Havey Duty only (Ozone,) etc. locking arrangement of brass make at top of standard make(patch fitting), including fixing of Frosted strip vision film & bank logo as directed by the Bank/ Architectinclusives of all materials, labour and all complete with Indian Bank monogram.				
i	Toughned Glass Door (4'-0" x 7'-0")	SFT.	28.00		
ii	Toughned Glass Door (3'-0" x 7'-0")	SFT.	21.00		
3	TABLE & COUNTERS				
	Providing and fixing MANAGER'S TABLE with 10mm beveled toughened glass of approved make to be fitted on top obtain the total height of 2'-6" as per detailed drawing, made up of 19mm board of approved Make and finished with 1 mm thick laminate of approved make, and shade. Table(with one side drawer unit and another side drawer unit) shall be provided with drawers sliding on telescopic channels and one cabinet with proper locking arrangements and keyboard with telescopic channels . The work includes providing and fixing of foot rests, shelf for CPU, furniture locks, wire managers, spirit polishing of steam beach/ white cedar beading etc. and The inner exposed surfaces to be finished with 0.8mm thik laminate of approved shade. complete in all respects to the entire satisfaction of the Architect/Bank.				
I	Table size: 6'-6" x 3' 0" / 2'-9" x 2'-6" (Must be fixing to the wall)	No	1.00		
4	STORAGE/ WALL DISPLAY/ TV PANEL				
	Providing & fixing STORAGE CABINETS/ DISPLAY 2'-6" ht and 1'-6" deep as per layout plan made up of 19mm board/ply of approved make and finished with 1mm thick laminate of approved make, shade and as per detailed drawing. one shelves made up of 19mm thick board, each drawer(with lock) & cabinet(with lock) 19mm/ 12 mm Toughned Glass portion every place must be finished with proper liping/ margin teak wood finish. In side and back shall be finished with 0.8 mm thick laminate of approved Make and color The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc as specified. complete in all respects.				
i		SFT	175.00		
	COLUMN / WALL PANNELING				
ii	Providing and fixing of COLUMN PANNELING as per design, consisting of 9mm thick MDF BOARD of approved Make fixed on wall with made of 2"x2" alluminium tublar section framework (14 gauge) 2'0" c/c both ways. The above shall be laminated with 1mm thick mica of approved Make, The work includes sprit polishing of wood beading, complete in all respects as per detailed drawings to the complete satisfaction of the Architect.	SFT	720.00		
5	Providing & fixing of BANK MONOGRAM in BRASS 100% only (3'-0" x 3'-0")	No	1.00		
6	FALSE CEILING/DOORS /PARTITION (all types) etc, boarding at all the levels including all necessary carting away of all the waste materials from the site, complete with cleaning & disposal etc. as directed by the Architect.	LS	1.00		
	TOTAL				

		"B"Electrical Works						
1	Wiring for light points with 2x1.50sqmm PVC insulated copper conductor wire of 650/1100 volts grade with concealed PVC pipe/ conduit, including Providing & fixing G.I. box ,modular plate, 6amp SP switch etc. as required, including making all the connections, including cutting chases and making good the surfaces wherever required.							
i	One point controlled by one switch.	Nos	3.00					
ii	Two point controlled by one switch	Nos	6.00					
2	Supply Fixing & connection of modular type 5 amps Plug switch complete with Ms box Socket to fixed above table. 03 nos plug can be connected from 01 circuite	No.	10					
3	Same as above but 16 Amps 6pin socket with 16amps switch for raw power point. (01 Nos plug connected from one circuite.) including 2x4 sqmm +1x 2.5 sqmm earth wire)	No.	1					
4	PHILIPS CorePro LED Downlight downlighter 11 watt	Nos.	10.00					
5	Fixing , testing & commissioning of 2'x4' Recess mounted LED lights of PHILIPS /Wipro company. Size 24" x 48" for modular ceiling	No.	6.00					
6	LAN CABLE							
i	Supply and laying of 4pair CAT-5E LAN Cable with points, wiring & conduiting etc.	No	2					
ii	Supply, drawing, connecting, testing and commissioning of T.V Coaxial cable RG 6 in with wiring & conduiting etc.	No	2					
7	Demolition, Dismantling & Removal of existing electrical work along with PVC/ MS Conduit, wire/ Cable, Switch & socket, ceiling / wall Fan, Back box/ fan box, cable tray, smoke detector, speaker, CCTV system and other electrical work with accessorieswhich are not in use & shifting it to the required location.	LS	1					
	TOTAL							
	TOTAL (A+B)							
	GST EXTRA							
NOTES:								
1- Submission of bid along with Empanelment letter of Indian Bank & Allahabad Bank will be accepted only.								
2- Every Tender shall be accompanied by Earnest Money Deposit of Rs. 8000.00 to be submitted in the form of a DD in favour of Indian Bank, payable at Meerut. The Tender not accompanied by such Earnest Money are liable to be rejected straight away. (E.M.D in any other form is not accepted).								
3- Above mentioned approved makes / manufacturers shall be taken into consideration while quoting the price.								
4- Liquidated damage at the rate of 1% per week subject to maximum of 10% on Contract value applicable for the work completed after Contractual delivery date.								
5- Total completion Period of the project is 15 Days after issuing work order.								
6- Evaluation of the bids shall be done based on total price against this BOQ.								
7- All the materials shall be apply on the site after approval of Indian Bank/Architect.								
8- GST Extra.								
Place:								
Date:								
Signature of contractor with seal								