

**KULASEGARAPATTINAM BRANCH - INTERIOR FURNISHING, FIXTURES,
DATACABLING AND AIRCONDITIONING WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

A	MAIN WORKS	(Amount(Rs.)
1	INTERIOR WORK	
2	FIXTURES WORK	
2	BRANCH ELECTRICAL WORK	
3	BRANCH DATA CABLING WORK	
4	BRANCH A/C WORK	
	TOTAL	
(RUPEES ONLY)		
ALL RATES ARE INCLUSIVE OF 18% GST		

**KULASEGARAPATTINAM BRANCH - INTERIOR FURNISHING WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

BILL OF QUANTITIES

S NO	PARTICULARS	QTY	UNIT	RATE(Rs)	AMOUNT (Rs)
1	<u>PARTITIONS</u>				
a	<u>Full & Half Blocked Partition</u>				
	Providing full height double skin fully blocked partitions upto RCC ceiling ht using aluminium plain rectangular sections of 2 1/2"x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (Bank approved colors) with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base and a 100mm wide border (Brown) at the top including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.(Record, dining, strong room, ups room)	212.50	Sft		
b	<u>Partly Glazed Partition Manager & Server Cabin:</u>				
	Providing full height double skin partly glazed partitions using aluminium sections of 2 1/2"x11/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base and a 100mm wide border (Brown) at the top and shall include the cost of providing 8mm tk. plain float glass with etching Designe to suitable sizes, including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.	393.00	Sft		

c	Low Height Partition				
	<p>Providing low height double skin partitions along with Counter Divider partition wicket gate of the same type using aluminium sections of 2 1/2" x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (bank approved laminates only) with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base& including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.</p>	67.50	Sft		
d	CASH PARTITIONS (BULK CASH)				
	<p>Providing full height upto 7' 3" from floor level, semi grilled plywood partition for cash cabin, using aluminium sections of 2 1/2" x 1 1/2" size spaced at 2'0" c/c maximum for the frame work , fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (bank approved laminates only) with necessary grooves of 1mm thick, The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base and a 100mm wide border (Brown) shade at the top and shall include the cost of providing ornamental aluminium grille to suitable sizes, including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.</p>	65.88	Sft		
e	CASH CABIN TOP ALUMINIUM GRIL				
	<p>Providing and fixing in position readymade anodized alumium grill of approved design and quality fixed with continuous steam beech / teak wood beads of approved shape (finished 35 x 25 mm) all round polished (in cash cabin)</p>	51.19	Sft		

2	FRONT COUNTER 12MM GLASS				
	Providing front glazing for cash cabin above counter from 3'9" to 7'0" height, and inbetween banking counters using 12mm thick plain glass including edge polishing & etching.	60.00	Sft		
3	DOORS				
a)	ENTRANCE DOOR				
	To be made out of 12mm thk glass with etching as per design. The glass with etching has to be fixed with top & sides rails of 2½"x4" and bottom rails of size 2½" x 6". The rails to be made out of beech wood The door shall have 18" long s/s handle (as shown in the drawing) and also double action floor spring of specified make. The door frame to be mde out of 5"x 2½" best quality beech wood. The etching in glass pattern to be done strictly following instructions of the Architect or following the drawing attached. The exposed wood of frames, rails to be polished as per instructions of the architect. NB: The size of the door may slightly vary as per site conditions for matching the elevation on the fixed glazing. All exposed edges of the glass to be machine polished. The rails are to be made as per the design of the architect. Bank Entrance door (4'0" X 7'0")	35.00	Sft		
b)	FLUSH DOORS				
i)	Door (3'0" x 7'0")	1.00	No		
ii)	ups - (2'6" x 5'0")	1.00	No		
iii)	Record Entry - (2'6" x 5'0")	2.00	No		
c)	SEMIGLAZED DOORS				
i)	Manager & Banking Hall Door (3'0" x 7'0")	1.00	No		
ii)	Manager, Server & B.cash (2'6"x 7'0")	3.00	No		

d)	WICKET DOOR				
i)	Wicket Door (3'0"x3'0")	1.00	No		
4	SERVER ROOM WORKING COUNTER				
	Working top will be 2' - 6" ht to be provided as per instructions given by the architect. Rest of the working counter as per specifications in fabricated out of 18mm ply for top, sides and 6mm ply for back. The work station will have drawer units, keyboard tray, cpu platforms, leg rest etc., and drawings attached in tender and specifications. All clarifications to be taken before quoting the prices and no extra cost shall be entertained at the time of execution. The entire work as per the instruction of the Architect at the time of execution.	10.00	Rft		
5	Cheque drop box/ Complaint				
	Providing cheque drop box/ Complaint/Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tk. Laminate (Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over a coat of primer & two coats of putty.	1.00	No		
6	Vertical Blinds:				
	Providing and fixing 100mm wide Vista Make or equivalent vertical blinds of approved make quality and colour shade and pattern. Rate shall include necessary scotch guard treatment on both side. The overlaps should be uniform and adequate	264.00	Sft		

7	FALSE CEILING (GYPBOARD)				
	<p>Providing & fixing suspended gypboard false ceiling, which includes Providing & fixing G.I perimeter channels of size 27mm, 0.5mm thk having one flange of 20mm & another flange of 20mm along with perimeter of the ceiling, screws fixed to brick wall/partitions with the help of rawl plugs & Screws. Then suspending G.I intermediate channels of size 45mm, 0.9mm thk with two flanges of 15mm each from the soffit at 1200mm centres with stell G.I hanger of width 25mm,0.5mm thk fixed to soffit with G.I. cleat & steel expansion fasteners. Ceiling section of 0.5mm thickness having knurled wedge of 51.5mm and two flanges of 26mm each with leafs of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 450mm centres. 12.5mm tapered edge gypboard is then screwed fixed to ceiling section with 25mm dry wall screws at 230mm centres Screw fixing will be done mechanically either with screw driver or drilling machine with suitable attach</p>	1286.00	Sft		
	<p>with requisite jointing compound, paper tapes, finisher and premier suitable for Gypsum plaster boards. The entire work shall be finished as per instructions of the Architect. And also finished with two or more coats of acrylic emulsion paint of approved shade and make. No extra cost shall be entertained in completing the entire work in all respect.</p>				
	Total Interior Works				

**KULASEGARAPATTINAM BRANCH - FIXTURES WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

BILL OF QUANTITIES

S NO	PARTICULARS	QTY	UNIT	RATE(Rs)	AMOUNT (Rs)
1	TABLE				
	Manager table as per drawing done with structure made of 18mm plywood with drawer unit comprising of 1 drawer, 1 filing shelf fixed with pull out door (box type hinges), locks, D type handles and all accessories to be provided.All drawers, corners, doors to be finished with beach wood lipping/beading, melamine polished., push in type keyboard, all drawers and key board on telescopic channels. All exposed edges Teak/beach wood beadings is finished with melamine polished and inside laminated with 0.8mm laminate. The table to be topped with 12mm float glass with beveling on all four sides. The side unit is provided with two drawers and filing shelf with two pull out doors, finished in same manner.CPU platform with foot rest to be provided. wall to table gap to closed with plywood.				
a)	Branch Manager 6'0"x2'6"	1.00	No		
2	FRONT COUNTER AND BULK CASH COUNTER				
	Providing and assembling banking counter and Cash, single window counter unit as shown in drawing of size not less than 5'0" x 2'6" x 2'6" or as per site requirements, with regular drawer - 1 No. and shelves on one side, a keyboard drawer at centre and a platform for CPU onto other side for each counter as shown in drawing using 19mm thick commercial plywood lined with 1.0mm thick laminate(Bank approved colors) Cash and single window with 12mm thick glass (to be strictly followed) in front side for all the exposed surfaces, including providing skirting 4" wide with 1.0mm thk laminate (Black) on both sides to match with the adjoining partition and 4" wide border at top with 1.0mm thk laminate (Brown).The customer top at 3'9"ht of 1'3" width & working counter top of 2'6" width to be fixed with 19mm Granite top (Jet Black/approved) with double nosing @ front side as shown in the drawing				
	All the plywood edges shall have teak wood lipping and all inner surfaces shall be painted with two coats of enamel paint over a coat of primer & two coats of putty. The rate shall include providing, fixing & painting a foot rest using first class seasoned country frame of size 3" x 1 1/2".Necessary hardware fittings like draw sliders, hinges, multipurpose locks with set keys, handles shall be provided.				
i)	Bulk cash	5.00	Rft		
ii)	Working counters	30.00	Rft		

2	STORAGE				
	Providing and fixing filing cabinet in manager cabin for a height of 2'6" & 7' ht. made of 18mm plywood structure comprising of suitable intermediate horizontal racks with open type doors, finished with 1mm laminate and teak wood beadings neatly melamine polished and inside finished with 0.8mm laminate with locks, handles and all accessories				
i)	Manager	7.50	Sft		
ii)	Cash&Swc	20.00	Sft		
3	WRITING LEDGE WITH 12mm GLASS TOP				
	Made out 18 mm ply as per design and exposed external surfaces to be laminated and internal surface to be painted with top provided 12 mm thk etched glass with machine polished edges . The entire work has to be done to the satisfaction of the architect. The design given has to be strictly followed	1.00	No		
4	NOTICE BOARD				
	Providing and fixing of the soft board on the customer lobby made of jolly board with a fabric of B / R @ 200 / - per meter .The design and the entire work has to be done as per the instructions of the architect a the time of execution	12.00	Sft		
5	ROLLING SHUTTER COVER BOX				
	Supplying & fixing of rolling shutter box using	55.00	sft		
	Total Interior Works				

**KULASEGARAPATTINAM BRANCH - ELECTRICAL WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

BILL OF QUANTITIES

Sl.No	Description Of Work	Unit	Qty	Rate	Amount
A	Supply&Installation&Commisioing of the following				
1	MAIN DB (8WAY VTPN DB)				
	Three Phase, Vertical Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer :				
	100A TPN MCCB -1Nos				
	Outgoings:				
	63A TP MCB -4Nos				
	32/25/20A SP MCBs- 12 Nos	Set	1		
B	Supply&Installation&Commisioing of the following				
1	LIGHTING DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 40A TPN MCB				
	Outgoings:				
	10/6A SP MCBs- 12Nos	Set	1		
2	POWER DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB&ELCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 63A TPN MCB				
	Outgoings:				
	32/25/20A SP MCBs- 12Nos	Set	1		

3	COMPUTER DB(8WAY SPN DB)				
	12 Way SPN Distribution board				
	with neutral bar, earth bar, cables ties, top and				
	bottom removable gland plate and with necessary				
	adaptor boxes if any. The DB should be IP 42 metallic				
	double door with provision of MCB&ELCB etc as				
	required including cutting of wall and plastering the				
	same with neat finish. It comprising as follows:-				
	Incomer : 40ADP MCB				
	Outgoings:				
	10A SP MCBs- 6Nos	Set	2		
4	Supply&Installation of the following with the necessary				
	enclosure and adaptor boxes if necessary,				
	a)63A TPN MCB	Set	2		
	b)63A DP MCB	Set	4		
5	Supply&Installation of 32A Metal Clad Socket with				
	top in a specified company manufactured box with				
	suitable rating MCB for AIR CONDITIONS	set	8		
6	Supply&Installation of 63A 4Pole Change over switch	set	1		
7	Supply and Fixing for 63A Phase Selector switch with				
	enclosure and adaptor boxes if necessary,	set	2		
C	LT CABLES				
1	Supply&Laying of the following cables in built up				
	trenches, on wall, or in the ground as per the case may be,				
	with proper clamping with necessary fixing materials etc.				
	Installing testing&commissioning of 1100V grade UG				
	cable as per IS 7098/1554 (Finolex/ Universal)				
	3.5Corex50Sqmm Aluminium Armored cable	Mtr	45		
	3.5Corex35Sqmm Aluminium Armored cable	Mtr	20		
	4 Corex16Sqmm Aluminium Armored cable	Mtr	35		
2	End Termination of the above cables with proper Glands				
	and Lugs				
	3.5Corex50Sqmm Aluminium Armored cable	Set	2		
	3.5Corex35Sqmm Aluminium Armored cable	Set	2		
	4 Corex16Sqmm Aluminium Armored cable	Set	4		
D	WIRING				
1	Light/Fan point wiring with 3 of 1.5 sqmm PVC				
	insulated copper conductor to be laid in 2mm suitable				
	PVC conduit with Bend, Couplings, etc.. And fixing with				
	clamps screws etc. All conduits to be laid above the				
	false ceiling/partition/concealed in the wall				
	etc. Wiring to be connected with supply&Fixing of				
	6A Modular type switch(MK/ROMA) with suitable				
	Modular plate and metal Box				
	a) One light Controlled by One Switch	Pts	40		
	b) Two light Controlled by One Switch	pts	4		
	c) 6A Switch box Sockets in the switch board itself	Pts	10		
	d) Ceiling fan with regulator	Pts	8		
	e) wall bracket fan point (6A socket with 6A switch)	pts	12		
	f) Calling bell point with Calling bell instrument	Pts	1		
	g) Exhaust fan point	pts	3		

2	Supply&Wiring with Flame Retardant				
	insulated PVC wire as per grade IS 994				
	for Circuits,Computer point,Power points within 2mm thk				
	PVC conduits with necessary accessories and with				
	proper clamps and to be concealed below the false				
	ceiling It comprises as follows:-				
	a) 3Runs of 2.5Sqmmcopper wire in PVC conduit for				
	lighting circuit mains	Mtr	300		
	b) 3Runs of 2.5Sqmmcopper wire in PVC conduit for				
	Power points	Mtr	300		
	C) 3Runs of 2.5Sqmm copper wire in PVC conduit for				
	computer points	Mtr	325		
	d) 2Runs of 4Sqmm copper wire+1.5Sqmm copper				
	wire in PVC conduit A/C Wiring	Mtr	230		
	e) 2Runs of 6Sqmm copper wire+2.5Sqmm copper				
	wire in PVC conduit	Mtr	20		
	f) 4Runs of 6Sqmm copper wire+2.5Sqmm copper				
	wire in PVC conduit	Mtr	40		
E	POWER POINT OUTLETS				
1	Supply&Installation of 3 Nos of 6A Sockets controlled by				
	2of 5A Switches with front plate with enclosure and				
	other accessories etc..(MK /ROMA)	Set	10		
2	Supply&Installation of 1Nos of 6A Socket controlled by				
	1No 6A Switch with front plate with enclosure and other				
	accessories etc..(MK /ROMA)	Set	8		
3	Supply&Installation of 1Nos of 16A Socket controlled by				
	1No 16A Switch with front plate with enclosure and other				
	accessories etc..(MK /ROMA)	set	7		
F	LIGHTING FIXTURES				
1	Supply, Fixing & Commisioning of Recess mounting type compact vert	set	21		
2	Supply, Fixing & Commisioning of Recess mounting type compact verti	set	6		
3	Supply&Fixing of Patti Type LED 20Watts Fiitings (Crompton, Wipro,P	Set	15		

4	Supply&Fixing exhaust fan(Crompton, Almonard)	set	3		
5	Supply&Fixing & Commisioning of wall mounting fan with necessary Down Rods and with all fixing accessories.,(Crompton / Havells)	Set	12		
6	Supply&Fixing & Commisioning of 48" ceiling fan with necessary Down Rods and with all fixing accessories.,(Crompton / Havells)	Set	8		
G	EARTHING				
1	Providing dedicated earthing with 600x600x3.15 mm copper plate along with 50mm dia.10feet long G.I pipe with other accessories in the earth filled with necessary salt,charcoal,etc. It should be covered with G.I Manhole cover with necessary civil works.etc..	Set	1		
2	Supply & Laying of 10 Sqmm PVC Insulated Multi strand copper conductor laid in 25mm dia PVC pipe for Dedicated earth leads from the earth electrodes to the UPSsystem	Mtr	35		
3	Providing general earthing with 50mm dia.10feet long G.I pipe with other accessories in the earth filled with necessary salt,charcoal,etc. It should be covered with G.I Manhole cover with necessary civil works.etc..	Set	1		
4	Supply&Laying of 8SWG copper wire	Mtr	60		
F	TELECOMMUNICATION				
1	Supply&Laying of 2 Pair Telephone Cable within PVC Conduit and its necessary accessories etc..	Mtr	250		
2	Supply&Laying of 20Pair Telephone Cable within PVC Conduit and its necessary accessories etc..	Mtr	25		
3	Supply&Installation of RJ II Jack with necessary Face plate and Box for connecting telephone points	Set	8		
4	Supply & fixing of 10 pair KRONE Box with lock and key	Set	1		
	TOTAL				

**KULASEGARAPATTINAM BRANCH - DATA CABLING WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

BILL OF QUANTITIES

S.No	Description Of Work	Unit	Qty	Rate	Amount
	DATA CABLING				
1	Supply&Laying of CAT 6 Data Communication cable in 2mm thk heavy duty 20mm dia PVC conduit and makinng holes in the aluminium partitions/wall all accessories as required (DLink)	Mtr	330		
	Supply&Installation,Testing&Commisioing of Modular type 1Nos of RJ45 Female Jack housed in GI anodised metal box with suitable Faceplate fixing the same in the wall/partitions with all accessories etc. as required.	Set	10		
3	Supply and fixing of 1M Mounting Cord	Set	10		
4	Supply and fixing of 2M Mounting Cord	Set	10		
5	Supply&Installation of 24por cat6 SWITCH	Set	1		
6	Supply and installation of 24port cat 6 jack panel	Set	1		
7	Supply and installation of 9u wall mounting rack	Set	1		
	TOTAL				

**KULASEGARAPATTINAM BRANCH - AIR CONDITIONING WORKS FOR INDIAN BANK
(TIRUNELVELI ZONE)**

BILL OF QUANTITIES

Sl.No	Description Of Work	Unit	Qty	Rate	Amount
1	Supply, Testing and commissioning of indoor and outdoor split air conditioner with remote control, with 3 star rating units and necessary civil works etc., The rate of units is including the supply and laying of 3 mtr of copper pipes with insulations, rubbers, white cements etc., (Brand: Voltas)				
b	1 TR - Manager & Server&Hall	3	No		
b	2 TR - Banking hall and manager	5	No		
2	Supply and laying of copper pipes with rubber insulations, rubbers, white cements etc.,	30	Mtr		
3	Supply and installation of Stabilizer for following units				
a	2 TR - 4 KVA	8	No		
b	Installation Charges for 1 Tr,2 Tr Split Air Conditioner	8	No		
4	Supply and Installation of Outdoor Stand with necessary civil works	8	No		
5	Supply and laying of PVC Blue pipes for water drain from the indoor units.	50	Mtr		
6	Civil works like cutting AC hole,packing,drain pipe cutting and p	1	Ls		
	Airconditioning works Total:				