

Zonal Office:Gonda

**NOTICE INVITING TENDER**

**Sub: COMPETITIVE QUOTATION FOR ELECTRICAL AND DATA NETWORK CABLING  
WORK OF BALRAMPUR MAIN BRANCH AND LEAD BANK CELL BALRAMPUR  
UNDER GONDA ZONE**

Competitive sealed quotations are invited in the prescribed format from the contractors who are already empanelled with bank executed interior electrical and Data network cabling work of nationalized Banks in last three years.

Formats of Quotations document is enclosed for submission of Electrical and Data network cabling work of Balrampur branch and Lead Bank Cell Balrampur, Distt-Balrampur. Full details and tender document are available in Bank's website [www.indianbank.in](http://www.indianbank.in) or can be obtained from Zonal Office Gonda. Duly filled tenders should be submitted as per following schedule:

1	Issue of Tender Document	From 21.02.2022 to 02.03.2022
2	Submission of Tender	On or before 02.03.2022 up to 5:00PM
3	Opening of Tender	On 03.03.2022 at 01:00 PM
4	Estimated cost of work	<b>Balrampur Main- Rs.-2.10 Lacs</b> <b>Lead Bank Cell Balrampur- Rs.-1.14</b>
5	Date of Commencement	7 Days from the date of issue of letter awarding the job
6	Time of Completion	10 days
7	Defect Liability Period	12 Months
8	Earnest Money	Rs.5000/- in form of DD/IOI in favour of Indian Bank payable at Gonda. <b>*Firms registered with MSME/NSIC with valid certificate issued by GOI are exempted from submitting EMD along with Tender.</b>
9	Liquidated Damages for delay	Rs.2000/- per day subject to Max. of 10 % of accepted contract amount. (If the work is not completed to the satisfaction of the Employer within the stipulated period the contractor shall be bound to pay to the employer a sum equivalent to Rs. 2000/- per day subject to ceiling of 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains un-commenced or unfinished after expiry of the completion date.
10	Payment Terms	Neither any advance nor any Interim payment will be made. Payment will be made on satisfactory completion of the job on the basis of actual measurements. Income tax will be deducted as per the rules. Retention money 10% will be deducted the bill and to be released after 12 months from the date of virtual completion provided no defects is observed during this period.
11	Document to be attached with the Bill	Manager completion Certificate, Manufacture Certification Bills & 4-5 photographs showing completion atatus of work.
12	Retention Money	10% ( Including Earnest money)

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tender without assigning any reason whatsoever. Late/delayed tender shall not be accepted after due date and time of submission of tender.

Zonal Manager

**CLIENT**

**INDIAN BANK**

ZONAL OFFICE Gonda- Premises Department  
Bahraich Road, Near Roadways Bus stop Gonda  
Uttar Pradesh-227001

**WORK /PROJECT**

PROPOSED ELECTRICAL AND DATA NETWORK CABLING WORKS AT  
INDIAN BANK ,BALRAMPUR MAIN BRANCH  
AND LEAD BANK CELL BALRAMPUR, DISTT- BALRAMPUR

**COMPETITIVE QUOTATION FOR ELECTRICAL AND DATA**  
**NETWORK CABLING WORKS AT ABOVE PROJECT**

Tender Issued to

M/S .....

Address.....

.....

Contact No ... ..

Tender Issued on :.....

Last Date of Submission : .....

Signature of the Contractor

seal

## Zonal Office:Gonda

### **NOTICE INVITING TENDER**

#### **Sub: COMPETITIVE QUOTATION FOR ELECTRICAL AND DATA NETWORK CABLING WORK OF BALRAMPUR MAIN BRANCH AND LEAD BANK CELL BALRAMPUR UNDER GONDA ZONE**

##### **General terms & Conditions:-**

- 1) Sealed quotation should be addressed to The Zonal Manager, Indian Bank, and Zonal Office Gonda and super scribed name of Work electrical and Data network cabling work of Balrampur Main Branch and Lead Bank Cell Balrampur, at Balrampur, Distt- Balrampur and should reach before 5:00 p.m. on 02.03.2022 at Zonal Office Gonda.

##### **Mailing Address:**

The Zonal Manager,  
INDIAN BANK  
Zonal Office Gonda  
Bahraich Road, Near Roadways Bus Stop, Gonda-271001(U.P)

- 2) No quotation will be accepted after 5:00 pm on 02.03.2022 and quotations will be opened on 03.03.2022 at 1:00 pm unless otherwise informed.
- 3) The quotations will remain valid for a period of 3 months from the date of opening.
- 4) Bank reserves the right to accept or reject any or all the quotations accept part of any tender, entrust the entire work to any contractor or divide the work to more than one contractor (item wise) without assigning any reason to do so or giving any explanation. The rates quoted by the contractors will help well for bifurcation and no compensation will be paid on this account.
- 5) At the time of submission every quotation must be accompanied by IOI/ Demand Draft for an amount of Rs.5000/- in favour of INDIAN BANK payable at Gonda towards EMD. Any quotation which is not accompanied by EMD will be summarily rejected.
- 6) Contract should quote rates in figures as well as in words.
- 7) All erasures and alterations made must be attested with the initials of tenderers. No overwriting is permitted.
- 8) The EMD of the unsuccessful bidders will be returned within 45 days from the date of opening the tender.
- 9) Joint tenders shall not be considered. Conditional tenders quoted by the contractor are liable to be rejected.
- 10) No escalation in the rates will be allowed under any circumstances.
- 11) On receipt of the intimation from the bank of the acceptance of his quotation, the contractor should submit his acceptance within 3 days If the successful contractor/ tenderer fail to undertake the work within 7 days after work allotment, the MMD will be forfeited and acceptance of his tender may be withdrawn.
- 12) The rate quoted in the tenders shall be inclusive of all materials as required and shall be inclusive of all charges of scaffoldings, lifting, tools and plants, freights/ transportation, labour conditions and fluctuations in rates of excise duty, octroi, GST, VAT, Excise Duty, service tax and any other taxes or expenditure of carrying out the works.
- 13) The Agency is advised to inspect and examine the sites and satisfy himself as to the condition prevailing at sites and its surrounding extent of work, scope and conditions under which the work is to be executed. The contractor shall also satisfy himself about the accessibility to the premises.

- 14) The agency shall submit the offer which satisfies each and every condition laid down in this notice, failing which the tender will be liable to be rejected. Conditional bids shall not be considered and will be out rightly rejected in the very first instance.
- 15) Work will be completed within the period of 10 days from the date of issue of tender or work order whichever is earlier. If the work be not completed to the satisfaction of employer within the stipulated period, the contractor will be bound to pay to the Employer a sum equivalent to Rs.2000/- per day subject to ceiling of Max 10% of the accepted contract amount by way of liquidated damages and not as penalty during which the work remains uncommenced or unfinished after expiry of the completion date. The contract may be rescind by giving one week notice incase work is not executed as per specification and as per time schedule given in tender document.
- 16) The liquidated damages as mentioned in the Notice inviting tender may not be enforced if the contractor applies for extension of time mentioning the genuine reasons for extension. If an extension of time of completion of the work is sought on the grounds of having unavoidable hindrances in his execution or any other ground, the contractor shall apply in writing to the Zonal Manager, Zonal Office Gonda with full details of the circumstances which is causing such an extension. Extension of time in days will be granted by the bank if it is proved that the contractor is not at fault for extending the work beyond stipulated date of completion. At the decision in this regard taken by the Bank shall be binding to the contractor.
- 17) The successful contractor is bound to carry item of work necessary for completion of job even though the same are not included in the schedule of quantity. Rates of extra item will be derived from quotation. In case the rates do not exist in quotation and extra item is not similar to the quoted item, then the rates will be worked out on actual cost of material and labour, any other expenditure for completing that work plus 15% towards contractors profit and overheads.
- 18) The work shall be carried out in such a way that, there is least disturbance to the staff of Bank. Contractors are required to organize the work in such a way that workings of staff and officers/executives of Office are not affected. Contractor is required to take adequate Care during progress of work to protect belongings. In case any damage, contractors at their own cost shall make the same good.
- 19) The contractor must co-operate with other contractors appointed by the bank so that entire work shall proceed smoothly and to the complete satisfaction of the Bank.
- 20) Contractor will arrange necessary tools and plants for completing own work at their cast. In case of any accident the total responsibility will be on the contractor. Contractors are required to submit time schedule of work. After completion of work, cleaning of floors, walls etc are to be done on daily basis to the satisfaction of Branch Head / engineer-in-charge. After completion of jobs, the site shall be cleared of all rubbish malba /debris etc in all respect and handover the site in proper manner on completion of the work.
- 21) No advance will be paid. Payment will be released on satisfactory completion of job and submission of bills. Retention Money @10% will be deducted from the bill and to be released after twelve months from the data of virtual completion provided no defects is observed during the period.
- 22) in case of non-completion or delay in completion of work or removal of defects in time, the bank shall be free to appoint another agency to get the job done at contractors risk and cost.
- 23) The contractor will attend to all the defects noticed during defect liability period. If the contractor fails to attend the defects these defects will be got rectified by the bank and the expenditure incurred on this account will be recovered from security deposit / retention money.
- 24) The work shall be got approved by the Architect / engineer and the contractor shall rectify any bad workmanship pointed out at any stage and remove from the site all the rejected materials immediately at his own cost.
- 25) The contractor shall acquaint himself with the site conditions making his own arrangements for storing of materials at site, lift, cartage etc. at his own risk and safety.
- 26) The Contractor shall make adequate arrangement for watch and ward of material and shall ensure the safety, breakage and any theft of material fixed or unfixed by him or the other sub contractors. The bank shall not be liable for any sort of loss incurred.
- 27) The contractor shall be responsible for application of labour laws, compensation for injury and accident to person, whether employed by him or his sub-contractor.
- 28) The contractor shall ensure that the workmen employed by him for the execution of work are suitably covered against Workmen Compensation Act and that all liabilities arising out of Workmen's .

- 29) compensation Act, ESIS and other legislative enactment applicable to such works and workmen shall be to the contractor's account and responsibility.
- 30) Civil, Interior Furnishing and Electrical Works will be carried out as per Bank's standard drawing / specifications and to the entire satisfaction of the bank.
- 31) The contractor shall inform the bank, well in time, to check measurements of anywork, which is likely to be hidden before covering.
- 32) Income tax at me prevailing rates will be deducted at source from contractor's bill and will be deposited with I.T.O. as per rules.
- 33) Any extra work or item can only be started by contractor after obtaining written approval from the Zonal Office. Item executed without prior approval from the Zonal Office will not be considered for payment.
- 34) The quantities mentioned in the schedule of quantities are approximate. Payment will be made on the actual work done by the contractors. However the contractor should not deviate the quantity without Banks permission.
- 35) The Bank has the right to alter the nature of work and to add or omit any items of work or to have the option of the same carried out departmentally or otherwise and such alterations or variations shall be carried out without prejudices to the contract.
- 36) The Bank has the right to terminate the contact if the contractor abandons the work or fails to commence the work in time, or fails to abide by the terms & conditions of the contract.

I have read and understood all the instructions/conditions given above and I have taken into account the above instructions/conditions while quoting the rates.

Date:

(Signature of the Contractor)

Place:

Seal

DETAILED SPECIFICATION FOR BILL OF QUANTITY					
OF ELECTRICAL WORK FOR INDIAN BANK BALRAMPUR MAIN BRANCH					
A ELECTRICAL FURNISHING					
Sl.no	Description of items	Unit	Qty.	Rate	Amount
1.0	Supplying fabrication and installation of new panel board made by 2mm CRC sheet 415 volt 3 phase comprising of following including termination of all the incoming and outgoing line by proper socket inter connection neutral link and painting.	no.	1.00		
	Incoming 250 Amp TPN MCCBCN/ CH Frame.				
	Copper Bus Bar- 250 Amp				
	Outgoing MCB of breaking capacity 10ka				
	- 25 Amp MCB - 4 Nos.				
	- 40 Amp MCB – SPN – 3Nos				
	- 63 Amp MCB – TPN – 3Nos				
	- 125 Amp TPN ON LOAD change over EURO - 1No.				
	Amp.Meter voltmeter, fuse C.T.				
2.0	S/F A.C. Box(Hevell,s(MDS with earth metal clad(20Amps, MCB concealed in walls.)in cluding 2x4sqm+1x1.5sqm Multi standard copper wire in suitable size PVC conduit A.C. Box to main panel	no.	5.00		
3.0	P/F of point wiring 5Amp controlling switch modular type, including 1.5sqmx2 +1x1sqm multi stand red PVC nsulated copper wire in suitable size PVC conduit & M.S box plateetc.				
	A- Single point controlled by single switch.	no.	10.00		
	B- Plug point on switch board.	no.	5.00		
4.0	S/F 15Amp switch & 15 amp Socket including 2x2.5sqm +1x1sqm Multi standard copper wire in suitable size PVC conduit & M.S box front plate etc.	no.	6.00		
	S/F 4 No. 5 Amp socket & 4 No controlling switch including M.S box cover plate & top plate, 2x1.5sqm+1x1sqm multy stand Wire in suitable size PVC conduit. & separately provide 1.0 No 5 Amp switch & socket.	no.	10.00		
5.0	A-Supply & drawing two pair Telephone cable in suitable size PVC conduit with RJ -11 telephone jack in suitable encloser	no.	2.00		
6.0	Providing & installation of 8way SPN D.B. of Havell's MDS make with provision for incoming & outgoing connection and 5/20 Amp. Single pole MCB (8Nos)	no.	2.00		
7.0	Providing & installation of 12way SPN D.B.of Havell's MDS make with provision for incoming & outgoing connection and 5/20 Amp. Single pole MCB (12Nos)	no.	3.00		
8.0	Providing & fixing of 32Amp.SPN including Board etc. as required at site (for U.P.S.)	no.	2.00		
9.0	S/Laying 2x2.5sqm +1x1sqm multi standard copper wire Circuit wire in suitable size PVC conduit for light point circuit MCB D.B to switch board 2.5sqm wire	no.	5.00		

10.0	A – Supplying and drawing lan cable cat - 5 d-link or eqv make by 19mm pvc pipe fully concealed.	rmt	220.00		
11.0	B- termination of lan cable in one end with RJ 45 computer jack of MK, Roma or Crab- tree make in suitable enclosures.	no.	12.00		
12.0	C- termination of land cable in other end with RJ 45 socket.	no.	11.00		
13.0	S/F of cash cabin light with LED	no.	2.00		
14.0	P/F Cutout 100Amp.	no.	3.00		
15.0	32 Amp Change Over Double Pole for UPS	no.	1.00		
16.0	S/F of generator power supply with 25sqmxx 2 Core Al.cable from Gen.to C/OVER.	mtr	25.00		
17.0	S/F of 40Amp RCCB with Encloser complete Make Havells,ABB	no.	2.00		
<b>TOTAL (A)</b>					
<b>B</b>	<b>ELECTRICAL FIXTURES</b>				
<b>Sl.no</b>	<b>Description of items</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount</b>
1.0	S/F Exhaust Fan 300mm Heavy Duty Make Crompton.	no.	2.00		
2.0	S/F of 400 mm sweep wall mounted fan CG/ KHAITAN.	no.	7.00		
3.0	S/F of 1x36watts Fluorescent Tube light fitting c/w cost of 1x36w fluroscent tube light - Tarang Electronic 4' TMC090 1xTLD36W HF - Phillips	no.	8.00		
4.0	Supplying and fixing Philips make 36W LED FLAT PANEL after disconnection of existing fitting 2'x2' size in grid type false ceiling, 600x600 suitable for recess mounting,CRCA sheet, asthetic looking, or eqv Philips/havells	no.	14.00		
5.0	Supplying and fixing Philips make or eqv <b>10 W LED round type downlighter</b> (Philips/ wipro /Jaguar)	no.	20.00		
6.0	Supply and fixing LED Bulb 7Watt, 9 watt & 12 watt				
6.1	a) 7W	no.	2.00		
6.2	b) 9W	no.	2.00		
6.3	c) 12W	no.	2.00		
<b>TOTAL (B)</b>					
<b>Grand Total (A+B) Rs.</b>					

DETAILED SPECIFICATION FOR BILL OF QUANTITY					
OF ELECTRICAL WORK FOR INDIAN BANK LEAD BANK CELL BALRAMPUR					
A	ELECTRICAL FURNISHING				
Sl.no	Description of items	Unit	Qty.	Rate	Amount
1.0	Supplying fabrication and installation of new panel board made by 2mm CRC sheet 415 volt 3 phase comprising of following including termination of all the incoming and outgoing line by proper socket inter connection neutral link and painting.	no.	1.00		
	Incoming 250 Amp TPN MCCBCN/				
	CH Frame.				
	Copper Bus Bar- 250 Amp				
	Out going MCB of breaking capacity 10ka				
	- 25 Amp MCB - 4 Nos.				
	- 40 Amp MCB – SPN – 3Nos				
	- 63 Amp MCB – TPN – 3Nos				
	- 125 Amp TPN ON LOAD change				
	over EURO - 1No.				
	Amp.Meter voltmeter, fuse C.T.				
3.0	S/F A.C. Box(Hevell,s(MDS with earth metal clad(20Amps, MCB concealed in walls.)in cluding 2x4sqm+1x1.5sqm Multi standard copper wire in suitable size PVC conduit A.C. Box to main panel	no.	2.00		
4.0	P/F of point wiring 5Amp controlling switch modular type, including 1.5sqmx2 +1x1sqm multi stand red PVC insulated copper wire in suitable size PVC conduit & M.S box plate etc.				
	A- Single point controlled by single switch.	no.	0.00		
	B- Plug point on switch board.	no.	0.00		
5.0	S/F 15Amp switch & 15 amp Socket including 2x2.5sqm +1x1sqm Multi standard copper wire in suitable size PVC conduit & M.S box front plate etc.	no.	2.00		
6.0	S/F 4 No. 5 Amp socket & 4 No controlling switch including M.S box cover plate & top plate, 2x1.5sqm+1x1sqm multy stand Wire in suitable size PVC conduit. & separately provide 1.0 No 5 Amp switch & socket.	no.	4.00		
7.0	Providing & installation of 8way SPN D.B. of Havell's MDS make with provision for incoming & outgoing connection and 5/20 Amp. Single pole MCB (8Nos)	no.	2.00		
8.0	Providing & installation of 12way SPN D.B.of Havell's MDS make with provision for incoming & outgoing connection and 5/20 Amp. Single pole MCB (12Nos)	no.	3.00		
9.0	Providing & fixing of 32Amp.SP.N including Board etc. as required at site (for U.P.S.)	no.	2.00		
10.0	S/Laying 2x2.5sqm +1x1sqm multi standard copper wire Circuit wire in suitable size PVC conduit for light point circuit MCB D.B to switch board 2.5sqm wire	no.	5.00		



11.0	A – Supplying and drawing lan cable cat - 5 d-link or eqv make by 19mm pvc pipe fully concealed.	rmt	110.00		
	B- termination of lan cable in one end with RJ 45Computer jack of MK, Roma or Crab- tree make in suitable enclosures.	no.	5.00		
	C- termination of land cable in other end with RJ 45 socket.	no.	4.00		
12.0	P/F Cutout 100Amp.	no.	3.00		
13.0	32 Amp Change Over Double Pole for UPS	no.	1.00		
14.0	S/F of generator power supply with 25sqmmx 2 Core Al.cable from Gen.to C/OVER.	mtr	25.00		
15.0	S/F of 40Amp RCCB with Encloser complete Make Havells,ABB	no.	2.00		
<b>TOTAL (A)</b>					
<b>B</b>	<b>ELECTRICAL FIXTURES</b>				
<b>Sl.no</b>	<b>Description of items</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount</b>
1.0	S/F of 1x36watts Fluorescent Tube light fitting c/w cost of 1x36w flourscent tube light - Tarang Electronic 4' TMC090 1xTLD36W HF - Phillips	no.	2.00		
2.0	Supplying and fixing Philips make 36W LED FLAT PANEL after disconnection of existing fitting 2'x2' size in grid type false ceiling, 600x600 suitable for recess mounting,CRCA sheet, asthetic looking, or eqv Philips/havells	no.	3.00		
3.0	Supplying and fixing Philips make or eqv <b>10 W LED round type downlighter</b> (Philips/wipro /Jaguar)	no.	6.00		
4.0	S/F of 400 mm sweep wall mounted fan CG/ KHAITAN.	no.	3.00		
<b>TOTAL (B)</b>					
<b>Grand Total (A+B) Rs.</b>					

**Specifications of ELECTRICAL Materials**

<i>S.No.</i>	<i>Item</i>	<i>Make/ Specifications</i>
1	FITTING	Philips
2	WIRE	Havells, Finolex, Polycab
3	SWITCHES	Roma, M.K., Crabe Tee-Havells
4	MCCB	Havells , L&T
5	MCB DB	Havells, L&T
6	Main Switch	HPL, L&T,
7	Changeover	Havells , L&T, HPL
8	PVC Pipe	AKG, Plaza. 2mm thick
9	Wall Fan	Crompton, Havells
10	Ceiling Fan	Crompton, Havells
11	Exhaust fan	Usha; Khaitan, Crompton.
12	Cable	Gloster, Havells, National, Railisons.
13	Telephone Wire	Delton, Anchor.
14	Cat- 6 Cable	D - Link
15	IO - Box	D - Link
16	MCB	Havells, L&T
17	LED	Philips (Only)
18	MS Pipe	AKG, MK,