

Sl. No.	Particulars	Units	Qty.	Remarks
1.0	Full Ht partition			
	Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section (conforming IS 710) and/or as per frame work shown in the drawings with 6 mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass with chemical eachingas per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects. (Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	Sft	1,358.00	Fibre Cement Board partition Instead of plywood partition with aluminium frames
2.0	Low ht. partition			
	Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 1/2" hevy gazed almunium section (conforming IS 710)and/or as per frame work shown in the drawings with 6 mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass with chemical eaching as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.	Sft	576.00	
3.0	Full glazed Partition			
	Providing , fitting & fixing 12mm thick flot glass partition with chemically eaching as per design.the partiton will be supported with S.S patch panel fittings as per drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as per direction of architect including cost of all labour & material .	Sft.	80.00	
4.0	Storage			
	Providing and fixing in position full height storage / low height storage / back storage (Credenza) as shown in Drg. using Plywood of required thickness finished with 1 mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint as detailed therein.The storage units shall be provided with handles. (Stainless Steel finish) as per approval of the Project Consultant/Bank.All exposed plywood surfaces to be finished with 1 mm thick laminate of approved make & shade and all exposed edges of plywood to have 1" x 1/4" T.W. Lipping. All exposed T.W. sections to be melamined in matching colour laminate and internal surfaces to have white enamel paint as directed. Item to include all necessary hardware and fittings in Stainless Steel finish, Godrej multi purpose locks including magnetic ball catcher etc. complete in all respects.	Sft	610.00	
5.0	Executive/ officer,s table			
	Providing and erecting in position, Tables as per drawing and conforming to the following specifications.basic structure of 19 mm thick BWR grade block board for sides. top and modesty panel, finished with 1.00 mm thick laminate sheet of approved shade and make including inner faces.drawer-cum-cabinet urit of approximate overall size of 400 x 500 x..600 inm (w x d x h) of 19 mm thick BWR grade block board and 12/6 mmthick BWR grade plywood. The drawer unit shall comprise of 3 sliding drawers: The drawer unit shall be finished with 1.00 mm thick laminate sheet of approved shade. Inner faces of cabinet shutters/drawers' shall be finished with 0.7 mm th inner mica.Readymade keyboard drawer of engineering plastic(KD 575 . PMT/INNOFIT SYSTEMS OR Equivalent approved make); and all necessary accessories, suitably suspended below table top. Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood-lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc.			

5.1	Size:- 9'-6"x2'-6"x2'-6"	Nos	1.00	
5.2	Size:-6'-6"x2'-6"x2'-6"	Nos	1.00	
5.3	Size:- 4'-6"x2'-6"x2'-6"	Nos	5.00	
5.5	Linear Work Station 2'-3" wide top	Rft.	162.00	
6.0	Conference Table Providing modular type Conference table top 25mm th.BWP ply other portion are made up of 19mm th. BWP ply . The exposed , inner and edge surfaces are to be finished with 1.0mm th. Laminates as per design of approved shade . The work should be completed including all labour and material.The item also include the crushed toffen glass pics and decorative stone as per design including all labour and materials.			
6.1	The table Size (24'-0"x4'-0"x2'-6") as per detail drawing of conference table.	Nos	1.00	
7.0	Entrance Door.			
7.1	Openable			
	Providing and fixing frameless fully glazed 12mm thk toughened float glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO. approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cilinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length)	Sft	49.00	
	a) Open able portion (it include SS finished H type 1'-6" long door handle)	Sft	49.00	
7.2	Fixed partion	Sft	60.00	
8.0	Doors – semi glazed Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mmx 60mm, 28mm x80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition . The shutter will have part glazed 8mm thk float glass side beveled , high polished & part solid one covered with 6mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partiion elevations designs, the rates are inclusive of cost of necessary hinges, handles (1'-0"long), aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	Sft.	298.00	
9.0	Door closer Providing and fixing Godrej/ Doorset make over head door closers in door with necessary fixtures and fittings etc.	Nos	10.00	
10.0	Floor spring Providing and fixing Godrej/ Door set make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	Nos	2.00	
11.0	Panelling Providing and fixing panelling on wall /column/partition . Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 25 mm @ 600mm c/c Both ways horizontally and vertically on the wall.This framing would be covered by 9mm thk. BWP Ply finished in approved 1.0 mm. Thk. Laminate . It also include Wooden moulding, lipping with melamine polished as per design. as directed by Bank / architect shall be provided wherever required, as per Architect's drawing/ direction. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	Sft	600.00	Fibre Cement Board panelling instead of plywood panelling
12.0	Panelling (Mica finished) in celing P/f paneling without wooden framework but 12mm thick plywood fixed on leveled celing and finished with 1.00mm thk. laminate of approved make and shade , on all exposed surfaces on all exposed surfaces as per details and design	Sft.	80.00	
13.0	Corian Top Providing fitting and fixing 6mm th. corian top as per design on table and storage top including all labour and materials.	Sft	80.00	
14.0	Roller blinds			

	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable roller blinds inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, transportation taxes etc., complete for the work.	Sft	420.00	
15.0	Wall Paper			
	Providing and applying printed wallpaper of approved make, color and brand on paneled walls with basic framework and finishes as per design and direction including necessary surface preparation. The printing must be digital one of best quality available in market. The surface is to be made free of dust. Rate should be inclusive of taxes as applicable supporting cash memo/bill are to be produced for payment of this item including certificate from the dealer certifying use of the product. The work should include certificate from dealer certifying use of the product. The work should include all necessary materials accessories and labour. All materials should be approved by the bank. (Basic cost of wall paper Rs. 4000/roll.)	Sft	250.00	
16.0	CNC Cutting Jalli			
	Providing and fixing CNC cutting jalli with HDHR board as per design finished with Duco paint including all labour and materials.	Sft	60.00	
17.0	Wall plastic paint.			
	Providing & applying 2 coats of plastic emulsion paint of royale ICI dulux & approved shade on wall, columns, beams, ceiling, etc. of back office hall including locker room, including preparation of surface, sand papering the intermediate coats, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	6,000.00	
18.0	Wall Putty work.			
	Providing and applying wall putty work punning in order to make the total plastered wall surface perfectly leveled, including cost of all materials, labour, conveyance, taxes, royalties, scaffolding, watering, curing, sundries, T&P, etc., as per direction of Engineer-in-charge.	Sft.	4,000.00	
19.0	Enamel Paint			
	Providing & supplying all materials and application of one coat of primer paint two coats synthetic enamel paint of approved colour and manufacture including preparation of surface, scaffolding etc., complete including all materials as per specifications and directions of Architects.	Sft	400.00	
20.0	Textured Finished			
	Providing & applying a coat of textured finish on walls and columns. The rate shall include scrapping, levelling & preparing the surface. Primer coat + (minimum) 3 coats of approved make, quality & shade shall be provided.	Sft	300.00	
21.0	Glazed display board.			
	Providing and fixing glazed display board as per design and instruction of architect of size 1'6"x2'-6" of 12mm th. Glass of edge polished and 1" edge beveled and fixed on wall with 1" SS stude as per direction. The work include all labour and materials.	Nos.	4.00	
22.0	Pigeon hole storage			
	Providing and fixing in place pigeon hole storages made of 12 mm thick plywood and finished with 1.0mm thick laminate externally. The shelves and internal verticals for the pigeon hole to be made of 12mm thick plywood and finished in hand polish. All complete as per the requirements of the Bank.	Sft	30.00	
23.0	False ceiling (Gypsum board.)			
	Providing & fixing at site plain gypsum board stepped/ flush false ceiling as per pattern & design made from 12.5mm thk paper reinforced gypboard sheets fixed with mainframe channels 80mm x 26mm x 0.5mm, every 450mm c/c or as mentioned in drawing intermediate channels 15mm x 45mm x 0.9mm at every 1220mm c/c with perimeter channel 20mm x 26mm x 0.5mm all along the wall shall be provided. The whole system to be suspended with strap bolts as recommended using rawl plugs 12.5mm dia. x 35mm long, with 6mm dia bolt & soffit cleat 27mm x 37mm x 25mm x 1.6mm thk. Gypboards to be screw fixed to the above framework using 25 mm dry wall screws. Provisions of melamine polished white beach wood moulding at wall / partition joints.	Sft	2,008.00	

	<p>Arrangements are to be made to accommodate light fixtures by forming recessed channels etc., wherever directed. Depressions, nails & screws, jointing & finishing etc., shall be done with jointing compound & paper tape. Ceiling shall be finished with painting 2 coats of plastic emulsion paint (velvet touch) of approved shade . Ceiling to be leveled & free from cracks including fixing GI perimeter to hold light fittings. Item to be completed in all respect to the Architect's approval. Provision of Opening (openable) min 4 nos(for maintenance purpose) in ceiling as per site conditions are to be done with necessary timber frame work tied with perimeter channel properly such as to match the remaining area of ceiling by leveling perfectly complete in all respect. This rate includes cost of all materials, labours, royalty,taxes, lead & lift to the place of work& also the cost of all fittings, (Measurements shall be taken for flat surface).</p>			
24.0	<p>False ceiling (Armstrong) Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile with sheihard gride Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)</p>	Sft	1,176.00	
25.0	<p>Dining table Providing and fabricating of dining table top made up of 19mm th.BWP ply . The exposed edge surfaces are to be finished with 1.0mm th. glossy Laminates as per design of approved shade and the inner surface is painted with two coat of enamel paint of approved color over one coat of primer with frame stand made up stainless steel hello square bar. the work should be completed including all labor and material.</p>			
25.1	<p>Approx. size of 6'-0"x3'-0"x2'-6"</p>	Nos	1.00	
26.0	<p>Providing and laying lunch platform of 1'3" width (Clear width) and at 3 '6" height (finished top level) from floor of approved 20mm thick Granite with bull nosed edges. It shall be laid on BWP ply wood 19mm thick supported on Steel L angle bracket. The plat form should be cantilevered from the wall as shown in the drawing. 9" wide 19mm thick BWP ply wood to be provided below the entire lunch counter for tiffin and kitchen items. The ply surface to be painted with enamel paint after applying putty. OR alternatively the lunch platform to be made of RCC slab cantileved from the wall as per required shape and size and the Granite slab to be fitted over the slab properly with necessary plastering for exposed faces of the slab.</p>	Rft	12.00	
27.0	<p>Pantry Storage Cabinete. Providing and fixing of low height storage cabinete having 600 mm. depth of made out of 19mm th. BWP grade ply having one horizontal intermidiate shalves as per requirement. The storage unit should have sliding arrangement with front shutter with kitchen basket slider having load capacity of 30 KG .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shadea and the inner surface to be finished with 0.7mm th. inner mica .The work should be completed according to drawing and design including all labour and materials.Quoted rates shall also include cost of polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges : other necessary hardware and accessories including satin finish S.S handles, knobs etc. of approved quality.</p>	Sft	16.00	