Project: proposed Renovation of SAM office for Indian Bank at 7th Floor, Mittal Chamber, Nariman Point, Mumbai-.

Budgetary Cost Estimate (Air Conditioning work) R

SR.No	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
Α	Spit Air conditioners :				
	Desige & supply of Air cooled split type A.C. system of 3star				
	Branded make (Voltas or Blue Star or Carrier) comprising				
	wall mounted/ ceiling suspended indoor air handling unit,				
	outdoor condensing unit (with scroll/ Rotary compressors),				
	isolating valvs, thermostatic control, safety cutouts,and				
	vibration isolation pads etc complete as per drg, details and				
	instruction incl. Maintenance/ service till defect liability				
	period and warranty (one year) pl note that the necessary civil				
	work including making good also included.Machine shall be 3				
1	Supply of Hi Wall 2.0TR	3.0	No		
2	Supply of Hi Wall 1.5TR	0.0	No		
3	Supply of Hi Wall 1.0TR	2.0	No		
	Total of A		Rs.		-
	Add: 28% GST as applicable				
В	Low Side Work:				
1	Refrigeration Piping:				
	Installation & commissioning of hard/ soft copper				
	refrigeration piping of approved thickness, complete with				
	tubular sleeve insulation of nitryle rubber, fitting, elbows,				
	bends, supporting arrangement on walls, ceiling, cable trays/				
	trenches. * pl note that 3 mt along with Machine not be				
	considered in piping measurement.(Standard length of 4 m				
	supplied with unit not to be considered) Rate to include				
	insulation cost CIVIL WORK required for cheasling/				
	cutting/ making holes in walls/RCC slab and redoing to				
1.1	Original with cement & sand HI wall Split (12.5mm dia)	110.0	Rmt		
2	Drain Piping:	110.0	Killt		
	Insulated condensate water drain piping constructed out of				
	PVC/ HDPE hard pipes, Fitting, Accessories, bends, tees,				
	Flanges, tappings, wall sleevss, hangers, supports, anchors,				
	fastners, complete. Make- Finolex, Prince				
	Rate to include insulation cost CIVIL WORK required for				
	cheasling/ cutting/ making holes in walls/RCC slab and				
2.1	redoing to original with cement & sand	00.0	D.c.+		
2.1	32 mm nom. Dia	80.0	Rmt		
3	Electrical cabling;				
	providing and laying electrical cabling makes: polycab, finolex or eqv. * pl note that 5 mt along with Machine not be				
	considered in cabling measurement.				
	Supply, Installation, Testing & Commissioning of Power				
3.1	Cabling between outdoor Unit & Supply Point near the indoor	128.0	Rmt		
] ,,1	unit (3core 4 sqmm single phase)for HI Wall	120.0	Milt		
4	Frame work: (MS Cage with Locking Arrangement)				
т	i rame work (mo cage with bucking Arrangement)				

				1	I
	Supply,Fabrication and installation of MS base frame for				
	indoor & outdoor units complete with epoxy				
	painting,vibration isolation pads, supports, hanger,				
	railing, brackets etc. complete as per site condition and Unit				
	requirmnt. Note: apply 2 coats of epoxy primer & 2 coats of				
	Black paint. MS Cage made out of 12 x12 sq Bar with 6" c/c				
	grid both ways with locking arrangement, complete. M/s				
	Godrej make padlock 5 levers locks are to be supplied				
	provided by the contractor for each cage. The top surface of				
	the MS grill box to be fixed/ covered with Aluminium sheet as				
4.2	outdoor unit (2TR/ 1TR HI Wall split)	5.0	No		
	Realighning Existing MS Cage as per site requirement using	4.0	No		
	old/ new material, finished with red oxide and oil paint,				
	ensuring Locking arrangement is must., completeas per				
4.3	instruction.				
5	Timers:				
	supply, installation, testing & commissioning of 12 hourly				
	sequencial timers along with the necessary wiring/ cabling for	1.0	No		
	timed operation of the stand - By Ac units Make: L/T				
6	Testing and commissioning:				
	supply, installation, commissioning & Pressure Testing of the				
	entire system upto 350 PSI, and holding the same for				
	minimum 48 Hours. Flushing the system, Refrigerant Gas				
1					
	Charging in the system and final commissioning of the system				
	Charging in the system and final commissioning of the system				
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up				
6.3	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit	5.0	No		
6.3	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install,	5.0 4.0	No No		
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per				
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per instruction & site condition.		No		
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per				-
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per instruction & site condition. Total of B		No Rs.		-
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per instruction & site condition. Total of B Sub total (A+B)		No		-
	Charging in the system and final commissioning of the system comprising indoor and outdoor condensing unit with nitrogen pressure testing,vaccumizing and gas Topping up HI Wall split Unit Remove carefully existing hi wall split ac unit, install, commissioning and testing as per Layout. complete as per instruction & site condition. Total of B		No Rs.		-