

PROJECT: INDIAN BANK AT HINGANGHAT BRANCH				
CLIENT: CIRCLE OFFICE, NAGPUR				
SITE ADDRESS: HINGANGHAT CITY				
PLY WOOD: KITPLY/DURO/GREEN WITH A VALID IS 303 CERTIFICATE				
laminare: Sunmica				
Adhesive: Fevicol SH				
All hardware to be of EBCO make only.				
Glass :- Asahi Float glass toughened 12mm thk				
1. All wires ISI mark Polycab make				
2. All switches / sockets ISI mark ANCHOR ROMA make.				
3. PVC Pipes ISI mark MMS Diamond / Press fit make				
4. All MCBs 1Pole, 2 Pole, 4 Pole ISI mark Legrand make.				
5. TPN DB / MCB DB ISI mark (Legrand make)				
6. CAT 6 for LAN / Camera ISI mark (D-Link make)				
7. LED Panel make Philips make				
8. LED Floodlight waterproof Philips make				
9. LED Tube set Philips make				
10. Fans Crompton make High Speed				
11. AC BOX Havells make				
RECAPITULATION				RS
A	FALSE CEILING			
B	FURNITURE WORK			
C	ELECTRICAL WORK			
D	DATA CABLING AND COMPUTER POINTS WORK			
E	AC WORKS			
1	TOTAL			
GST				
CGST- 9%				
SGST-9%				
TOTAL AMOUNT				

INTERIORS & CIVIL WORK				
A	FALSE CEILING			
A1	GYPSUM CEILING (IN FRONT PORTION ONLY)	sq.m	40	
	Providing and fixing falseceiling of India Gypsum Company 12.5MM THK USG BORAL MAKE make which includes fixing of GI perimeter channel of 0.55mm thk having one flange of 20mm and the other flange of 30mm and web of 27mm along the perimiter of ceiling screws fixed to wall/partition with the help of necessary screws and sleeves of 610mm c/c and suspended GI intermediate channel of size 45mmx0.9mm thk with flange of 15mm each from soffit at 1220mm centre with ceiling angle width25x10x0.55mm thick fixed to soffit of GI cleat with steel expansion fastener. Ceiling section of 0.55mm thick having knurled web of 51.5mm and 2 flanges of 26mm each with lip of 10.5mm and then fixed to intermedate channel with the help of connecting at 457mm centre using 12.5mm tapered edge Gyp board is then screw to the ceiling sections either screw 230mm center, all joints to be finished with necessary paper tapes and jointing compounds the finished as directed with 3 coats of luster paint. the rate is inclusive of making openings for light fittings and AC grilles Complete			
A2	TILED CEILING	sq.m	0	
	Providing 600x600 tiles15mm thk USG BORAL RH 90 make on SILHOUTTE grid fixed as per manufacturer specifiction. Complete.			
TOTAL: PART A: FALSE CEILING				
B	FURNITURE WORK			
B1	Partitions (with laminate finish)	sq.m	40	

	Providing and fixing on site in required position Full/half height partition of height as shown on drawing made out Hard wood sections of full size 50mmx50mm treated with anti termite treatment space at maximum 600 mm horizontally and vertically.c/c with proper half notch joint between the horizontal and vertical members and lap joint between two straight members with proper fixing, to be covered with 6mm ply of approved make on either side so as to make a composite partition thickness of 62mm. All exposed periphery of the parttion to have 12x75mm agrowood moulding with half round on both sides fixed to the partition finished in natural polish. Partition shall be finished on both sides with 1.0mm laminate of approved shade make and design fixed with Fevicol (SH) and mild steel nails and supports as required for adequate strength. Including all reccomended Hardware,Doors,12/6mm thk glass etc.as shown in drawing. including 32mm Flush door as per design Complete.				
	Same as aove but will 12.0mm thick gypsum with paint finished. Skirting 100mm thk at bottom and 100mm (ht) panelling in 12mm ply and 1.0mm thk laminate. Complete	sq.m	25		
B2	Counter	R.M	8.5		
	Providing & fixing at site Counter made out of 18mm thick of size & design as shown in drawing and as per Architect's instructions. The counter shall include one no cash drawer wher CTO is going to sit while other drawers and EBCO Make ready made computer drawer on slides per clerk space. All external finishing to be done in 1.0mm laminate all internal surfaces to be french polished only. All edges shall have 25x 8mm TW/agrowood lipping. The top & front surface of vistors side to in 1.0mm thk laminate . As shown on drawing and directed. . Refer drawing complete				
B3	Counter front partition	sq.m	5		
	Providing and fixing counter front partition in 10mm thk glass with white film at botton, with opening for cash transcation Complete as shown in drawing.				

B4	TABLES including side Unit Providing & fixing onsite tables made in 18mm ply for top vertical & front finished in 1mm thick laminate vertical and 1.5mm laminate on horizontal surface externally, all internal surface in, french polish, item to include all hardware, lipping etc. as shown in drawing and as instructions issued by the Architect. The table shall have computer keyboard drawer with lock and cable ring on top surface. The drawer unit shall consist of drawers as shown in drawing with 12mm ply for front and ebco make drawer sides on slides and back. One footrest in salwood section of 70mmx35mm, Providing multipurpose lock and recessed handles of approved make for each of drawer and shelf. Rubber wood beading for all expose surface finished in natural polish. Complete.				
	MANAGER TABLE 1.65X.65 SIDE UNIT 0.9X.75 (H)	NO	1		
	OFFICE TABLE 1.5X.6 SIDE UNIT 0.9X.75(H)	NO	2		
	SERVER TABLE	NO	1		
B5	Panelling Providing & fixing on site wall panelling in 6mm ply finished with 1mm laminate. As per design shown and directed by Architect with edge8mm thk agrowoob. lipping finished in polish etc. The panelling shall have gap of 35mm from wall to be provided by 35mmx35mm thk hardwood laminate treated with anti termite for levelling surface and fixed at 600mmx600mm horizotal and vertical (for concealing conduits pipe) complete	sq.m	0		
B6	Writing Desk (1.2 x0.45) Providing and fixing on site writing desk made in 18mm ply finished with 1.0mm laminate and 12mm clear glass with edge crystal polish supported on s.s studs and caps for holding slips/challans. including dust box shown below. As shown on drawing and directed by Architect. Complete.	no	1		

B7	Storages Providing & fixing Storage units made in 18mm ply front sides horizontal and vertical and back in 6mm ply with front shutter finished in 1.0mm lamiate of approved shade and colour agrowod lipping finished in french polish all internal surface shall be finished in french polish only including all necessary hardware such as Handles (s.s finish) hinges (brass anondised) Locks (Ebco make) Magnetic catch etc with 18mm plywood shelves at 400mm approx c/c etc . The depth of storage units shall be 450mm complete	sq.m	9		
B8	Notice board Providing & fixing on site soft board covered with blazer cloth on 12mm ply as base and 50x25 mm T.W. frame finished in polish.	no	1		
B9	Vertical Blinds Providing & fixing on site Vertical Blinds of 100mm of vista/mac make of approved shade as driected and channels fixed as per site conditionsfor measurement window opening shall be considered only.	sq.m	0		
B10	CHEQUE DROP BOX, SUGESSTION BOX	NO	2		
B11	ACP cladding on exterior Providing 3.0mm thk ACP cladding on aluminum frame work for exterior portion only. Complete	sq.m	0		
B12	PAINTING (ONLY ON FRONT BRANCH) providing plastic emulsion paint in one coat of primer and two coats of paint, item to include wall putty appliaction. Complete	sq.m	0		
A	T O T A L : FURNITURE WORK				
B	ELECTRICAL WORKS				
NO	ITEM SECTION - A	UNIT	qty	rate	amount
2	<u>MAIN INCOMING PANEL (MIP)</u>	nos	1		

	Supply, installation, testing and commissioning of wall /floor mounted indoor type, air insulated, totally enclosed vermin-proof, dead front, cubicle type, 2 mm thick sheet steel enclosure main incoming panel (MIP) suitable for use on 415 V, 3 Ph., 4 wire, 50 Hz. A.C. system, instrumental panel, CTs, incoming and outgoing cable compartment. Each unit shall be accommodated in a totally separate compartment having gasketed hinged door with locking arrangement. The Panel shall be complete with switches of following ratings, interconnection, G.I. earth busbar of adequate size covering the total length of switch board with drilled holes, G.I. bolts, nuts, washers, etc. The cubicle should be painted with 2 (two) coats of light grey synthetic enamel paint over two coats of zinc chromate primer. Danger sign board in English, and Marathi.				
	The complete fabrication, construction shall be done as per the detailed specification and conforming to the relevant IS. Name plate of Panel, Danger Board, incoming and outgoing feeders with Ampere rating of switches / change over switch are to be fixed up on front door above or below the respective switches. Short circuit I.C. of all MCBs should be of 10 KA (min.) The contractor shall submit the fabrication drawing for approval before fabrication.				
	The MIP consists of the following				
	<u>INCOMING :</u>				
	1 No. : 415V 100A 4P MCCB (25KA min.) having O/L & S/C protection device.				
	1 No. : 415V 25A TPN MCB				
	6 Nos. : Phase indicating lamps.				
	3 Nos. : 150/5A CTS				
	<u>2 sections of PVC sleeved TPN Tinned Copper Busbar</u>				
	a) 25mm x 6mm for phases & neutral for one section &				
	b) 20mm x 5mm for phases & neutral for other section.				
	<u>G.I. EARTH BUSBAR</u>				
	25mm x 6mm covering the total length of panel.				
	<u>Outgoing</u>				
	2 nos. 415V 63A TPN MCB				
	3nos. 415V 32A /40A TP MCB				
	4 nos. 240V 32A/40A SP MCB				
	6 nos. 240V 16A/20 A SP MCB				
3.5	ATM BOARD: - 40/32 Amps DP MCB in MS enclosure box	nos	1		
3.6	UPS POWER DISTRIBUTION BOARD 4 Way TPN DB consist of	nos	1		

	Incomer: -63 Amps DP MCB - 1 No.				
	Outgoing: -63 Amps DP MCB - 1 No.				
	TOTAL SECTION A				
	SECTION - B				
	POWER CABLE & TERMINATION: -				
1	Supplying, Installation, Testing & Commissioning of LT Cable rated for 600 / 1100 Volts AC as per IS Standard with necessary accessories and termination as required.				
2	3 .5 Core X 50 Sq.mm. Aluminum armoured cable from Meter Room to Main Power Panel with 2 Nos. of 12 SWG Copper Earth Wire. including crimping	per m	5		
3	4 Core x 6 sq.mm Copper armoured cable with 1 no. of 12 SWG earth wire from MPP to AC DB.	per m	0		
4	10 Sq.mm x 2 nos Copper PVC insulated wire from UPS output to UPS DB with 1 no of 6 sq.mm Copper earth wire.	per m	12		
5	25 sq.mm x 4 nos of lead wire from meter to Main switch in Meter room.	per m	5		
6	2x4 sq.mm +1x1.5 sq.mm thru M.S conduit from main panel to glow sign Board	per m	5		
7	3.5 Core 50 sq.mm PVC insulated Alu armoured cable with 2 nos 8 SWG G.I. wire as running earth.	per m	8		
	TOTAL SECTION B				
	SECTION - C				
	LIGHT POINT with WIRING				
	Note: The point mention below is inclusive of circuit wiring. Aa Switch boards should be connected with separate circuit from main panel				
	Point wiring with 1100 V grade 3 nos. single core 1.5 sq.mm. (1 for phase, 1 (black colour) for common neutral by looping method and 1 (green colour) for common earth by looping method) PVC insulated flexible FRLS copper conductor cable (IS:694) through PVC Conduits of 25mm/20mm of 16 guage thickness (ISI marked embossed on conduit surface) complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall from light & fan switch board to light, fan & 6A socket outlet on the same switch board or separately mounted switch board. The work includes supply and fixing of all materials as specified make modular type 6A switch for each light and fan point, 6A 2/3 pin shuttered socket outlet with switch, 3 plate ceiling rose / angle or batten holder etc. as required.				

	The point wiring also includes circuit wiring with 1100 V grade 2 nos. single core 2.5 sq.mm. (1 for phase and 1 (Black colour) for neutral) + 1 no. single core 1.5 sq.mm. (Green colour for earth) PVC insulated flexible (FRLS) copper conductor cable (IS:694) through suitable size PVC. conduit as described above from DB to switch board, interconnection, mending good all damages to original finish, painting etc. as required to be completed in all respect. All connections of wires to be done by means of "Wago" type connectors. (All wiring in strong room, locker room, records & stationery room will be of surface conduit type).				
1	Primary Light Point	nos	35		
2	Wall Bracket Fan Point with 2/3 Pin socket (to be installed at Fan height and switch)	nos	6		
3	Ceiling Fan Point with supply and fixing of 2 Module step regulator/dimmer (280 W min)	nos	5		
4	Exhaust Fan Point	nos	3		
5	Call Bell Point with Push Bell (Indicator Type or Ding Dong)	nos	1		
6	1x6A 2/3 pin shuttered socket with switch on separate switch board other than fan/light switch board.	nos	8		
7	1x6A 2/3 pin shuttered socket with switch on separate switch board on than fan/light switch board.	nos	8		
8	1x16A 5 pin shuttered socket with switch on separate switch board on than fan/light switch board.	nos	8		
9	AC POWER POINT with WIRING: -	Each	5		
	A.C. power point wiring from DB with 1100 volt grade 2 Nos. single core 4 sq.mm. + 1 No. 2.5sq.mm. (Green colour for earthing) PVC insulated flexible FRLS copper conductor cable through suitable size M.S. conduit (ISI marked embossed on conduit surface) complete with junction box, circular box, elbows, bends, couplers and other accessories on surface above false ceiling or concealed by chase cutting on wall. The work includes supply & fixing by chase cutting on wall, 'North-West' make A.C. power unit having 25A 3 pin socket with matching plug, 20A Starter in sheet steel enclosure with 4 module plate, mounting box complete with interconnection, mending good all damages to original finish, painting etc. as required. All connections of wires to be done by means of 'Wago' type connectors.				
10	Supply and fixing of 16/6A 6 pin shuttered socket outlet with switch & indicator, mounting box and suitable size front plate on wall just opposite to Switch Board of Strong Room / Locker Room and supply of 1.1 KV grade 3 core 2.5 sq.mm. round PVC insulated and PVC sheathed flexible copper conductor cable of 1.5 meter length having one (1) no. 16A 3 pin plug at one end and the other end will be permanently connected to the Switch Board inside the room including interconnection, chase cutting, mending good all damages to original finish, painting, etc. as required.	NO	1		

TOTAL SECTION C			
SECTION - E			
LIGHT FIXTURE: -			
Supplying, Installation, Testing & Commissioning of following light fixtures complete of approved make as per specification with all fitting, accessories such as Junction Box, Hardware, Starter, Connector, Lamps, Tube etc. fittings and make as mentioned below consist of electronic ballast & color 84 PL tube with direct & indirect lighting, all fitting, accessories such as Chain Link Support on Ceiling/ wooden framework approved by Architect. (Before Installation Sample must be shown to Architect.)			
a	PHILIPS MAKE RC 3808 LED 25 6500 PS OD WH	Nos	0
b	PHILIPS MAKE DN 191B LED 6S -6500 PSU WH	Nos	11
c	PHILIPS MAKE TUBE LGHT	Nos	20
6	CROMPTON CEILING FAN 1200MM dia, white colour with all accessories.	no	7
7	300mm Exhaust fan with all accessories with mounting ring and louver Complete(white colour only) GEC make.	no	2
8	400mmdia wll bracket fan with all accessories (White Colour Only)	no	2
9	Supplying and fixing on wall call bell buzzer (approved by Consultant) suitable for 240 volt single phase A.C. supply including interconnection. etc. as required.	no	1
TOTAL OF SECTION -E			
SECTION - F			
TELEPHONE CABLING: -			
1	S/I/T/Commissioning of 20 pair telephone unarmoured cable from service point to Krone Box INCLUDING CONDUIT/CASING CAPPING (Make - Finolex / Delton / Polycab)	per m	15
2	<u>TELEPHONE JUNCTION BOX</u> Supply and fixing of 25 pair telephone junction box "Krone" make on wall /furniture/partiion with hinged cover and screwed type tag strips complete with chase cutting, mending good, painting etc. as required. Inc (Make - Krone type Delton / ITL)	per nos	1
3	<u>TELEPHONE WIRING</u> Supplying and laying of 2 paid 0.50 mm dia Telephone cable through pre - laid rigid PVC conduit as shown in the drawing or otherwise as directed by the consultant from Telephone Junction box to Telephone socket outlet including interconnection, mending good, etc, as required to be completed in all respect including conduit	per m	100

4	<u>TELEPHONE SOCKET</u>	per nos	10		
	Supply and fixing on wall / furniture / partition recessed type Legrand/North - West/Novar make Telephone socket outlet (RJ 11) with mounting box & front plate as shown in the drawing complete with chase cutting, mending good etc. as required.				
	TOTAL OF SECTION - F				
	SECTION - G				
	MISCELLANEOUS WORK: -				
3.5.1	Earthing the installation as per I.E. rules conforming to IS:3043-1987 or its latest amendment by making earth station with 600mm x 600mm x 6mm (minimum) thick copper plate electrode to be installed such that its top edge shall be at a minimum depth of 3.0 metre below ground level after preparation of ground with charcoal and salt and connecting the 25mm x 6mm copper earth lead-in-strip (upto 10 metre length) by bolting and then brazing to the copper plate complete with copper bolts of suitable length double nuts and washers including supply and fixing of 50mm dia. partly perforated G.I. pipe with funnel for watering arrangement. The copper earth lead-in-strip shall be PVC sleeved / insulated throughout the total length and the underground portion to be laid through suitable size heavy duty rigid PVC conduit (ISI mark embossed on conduit surface) at an average depth of 500mm below ground level.				
	The earthing installation should be provided with 300mm x 300mm and 300mm depth inside dimension masonry inspection pit with C.I. hinged cover having locking arrangement and restoring the surfaces duly rammed	Each	2		
3.5.2	Earth lead-in-strip exceeding 10 metre length as mentioned in item no. 3.5.1. with supply and fixing of 25mm x 6mm copper strip having PVC sleeved / insulated to be fixed on wall surface with tinned copper bar saddles / clamps at an interval of 300mm etc. as required to be completed in all respect. Minimum clearance between wall surface and copper earth lead-in-strip should be 6mm	Mtr.	15		
	TOTAL OF SECTION - G				
	SUMMARY				
	TOTAL SECTION A				
	TOTAL SECTION B				
	TOTAL SECTION C				
	TOTAL SECTION E				
	TOTAL SECTION F				

TOTAL SECTION G					
B	ELECTRICAL GRAND TOTAL				
DATA CABLING AND COMPUTER POINTS					
	COMPUTER SOCKET POINT: - (thru UPS supply only)	Set	12		
	Computer socket outlet cluster point wiring with 1100 V grade 3 nos. single core (1 for earth, green colour) 1.5 sq.mm. PVC insulated flexible FRLS copper conductor cable conforming to IS : 694 through suitable size rigid PVC.conduit (ISI mark embossed on conduit surface) and conduit accessories partly through concealed in wall, embedded in floor, partly on surface above false ceiling and partly through partition or through flexible conduit from CDB to computer socket outlet cluster as detailed below and upto connection of 2 nos. socket clusters in 1 (one) circuit connecting by looping method. The work includes supply and fixing of socket outlet clusters components (Legrand/North - west/Novar make)				
	Each computer socket outlet cluster comprising the following :				
	3 nos. 6A 2/3 pin modular type shuttered socket				
	3 nos. 6A modular type controlling switch				
	1 no. 16 /6A 6 pin modular type shuttered socket				
	1 no. 16A modular type controlling switch				
	1 no. Front cover of suitable size				
	1 no. Mounting box of suitable size				
	Note:- All power supply is thru UPS DB. The Control switch is to be located in another board above table. The supply socket is located on another board below table.				
3.3	UPS Power Distribution Board	nos	1		
	4 Way TPN DB consist of				
	Incomer: -63 Amps DP MCB - 1 No.				
	Outgoing: - 10/16 Amps SP MCB - 14 Nos.				
3.4	UPS INPUT/ OUTPUT consist of	nos	4		
	63 Amps/40 Amps DP MCB in MS enclosure box				
	SECTION - G				
	MISCELLANEOUS WORK: -				
	COMPUTER POINTS				
1	DATA CABLING (including conduit casing capping)				

2	SUPPLY & INSTALLATION OF CAT 6 UTP CABLE	per m	450		
3	CAT 6 INFORMATION OUTLET WITH FACE PLATE	per no	12		
4	24 PORT CAT 6 JACK PANNEL (EXISTING)	per no	1		
5	3 FT. PATCH CORD CAT 6	per no	12		
6	7 FT. PATCH CORD CAT 6	per no	12		
7	24 PORT 10/100 FAST ETHERNET SWITCH	per no	1		
8	12 U WALL MOUNTING 19" STANDARD NETWORKING RACK	per no	1		
B	DATA CABLING COST				
TOTAL DATA +COMPUTER POINTS					

INDIAN BANK

HINGANGHATBRANCH

ESTIMATE

SATYAJIT RANE
ARCHITECT