

INDIAN BANK					
ESTIMATE FOR <u>AIR-CONDITION</u> WORK OF VASHI BRANCH. REV. DT. 15.01.2023					
AIR CONDITION TOTAL AREA TO BE A.C. = 939SQ.FT.					
Sr.No.	Description	Qty	Per	Rate	Amount
	Installation of High-Wall Split Machines :				
A)	Providing & Fixing High-Wall Split/ Ceiling Cassette Air conditioners including piping. Installation, timer etc. High wall split (3-Star Rating only with Copper Condensing Coil)/ Cassette air-conditioner units with cordless remote control of Blue Star Co., Carrier Co., Voltas Co. Copper and Drain pipe of adequate length should be provided. Lockable M.S. Grill Cage for condensing units with Stand The basic rate of the A/C with all necessary components should be coated. Unit rate per Split-units given below :				
1	High Wall Split AC.Machines. Of 1.0Ton Capacity (3 Star Rating Only)	3	Nos.		
3	High Wall Split AC.Machines. Of 2.0Ton Capacity (3 Star Rating Only)	4	Nos.		
	Total Cost of High AC.Machines :				
	B) Installation Cost :				
1	Charges for Installation of Split Air-condition units. Inclusive drilling of holes etc.	7	Nos.		
2	Lockable Grill Cage for Condensing units.	7	Nos.		
3	SITC. Of 5'-8" & 3'-8" extra copper Piping with installation.	81	Rmt.		
4	SITC. Of Drain PVC. Drain Pipe including with proper Clamping etc. complete.	72	Rmt.		
5	Additional Inter-connecting 3 Core-2.5Sq.mm. Cu flexible cable of Polycab make Only.	81	Rmt.		
6	Prov. & fix. Timer Switch at given Position.	1	No.s		
	Total Cost for Installation Work :				-
	NET TOTAL (A+B) :				-

NOTE: RATES TAKEN IN THE ESTIMATES ARE EXCLUDING GST. GST WILL BE ON ACTUALS.