

SECTION- I NOTICE INVITING TENDER FROM CONTRACTORS

Sealed **Tenders** are invited on behalf of Indian Bank, Dibrugarh Zonal Office, T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001 from registered contractors having adequate experience in Interior & Carpentry Works, for carrying out the Interior Furnishing & Electrical works of its Dubia Branch with ATM, at Dubia, Assam in accordance with the Bank's General Conditions of Contract, Special Terms & Conditions of Contract & Particular Terms & Conditions of Contract, Standard specifications, Extent of Work, Special Instructions to Bidders as appended on the subsequent page & Annexures.

a)	Name of work	:	Interior Furnishing & Electrical works of its Dubia Branch with ATM
b)	Time of Completion	:	30 days
	Earnest Money	:	Rs 10,000.00 by crossed Demand Draft/ Pay Order payable at Dibrugarh and drawn in favor of Indian Bank to be submitted with the Bid (Tender without earnest money in proper form will)
d	Potentian men		
u)	Retention money	:	10% of total certified bill amount
e)	Release of Retention	:	Retention money will be released after 1 (One) year from the date of payment of the final bill after adjusting all dues if any from the contractor
f)	Availability of Tender Document	:	Dy. Zonal Manager Indian Bank Dibrugarh Zonal Office, T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001
g)	Issue of Tender Document	:	From 23.02.2023 to 08.03.2023 Between 10.00 hrs to 15.00hrs , except Sunday and holidays.
h)	Date of Commencement	:	Either one week from the date of acceptance of work order or the day on which contractor is instructed to take possession of the site, whichever is later.
i)	Time and date of Submission of tender	:	Upto 03.00 P.M. on 08.03. 2023
j)	Time and date of Opening of tender	:	At 4.00 P.M. on 08.03.2023
k)	Venue of Opening Tenders	:	Dibrugarh Zonal Office

इंडियन बैंक 🔬	Indian Bank
📤 इलाहाबाद	ALLAHABAD
 Tender to be addressed and submitted to 	T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001 : Dy. Zonal Manager Dibrugarh Zonal Office, T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001
m) Clarification, if any to be obtained from :	M/s. <u>ARCHIVENTIONS</u> - Architects & Engineers Above Kalita Enterprises, 1 st Floor Jonali, R.G Baruah Road, Dibrugarh -786001 PH- +91-9854062928/ +91-361-2970463
n) Validity of Tenders of	: 6 (Six) calendar months from the last date submission of Tender
 Defects liability period payment of 	: 12 (twelve) months from the date of the final bill
p) Taxes	: GST at applicable rate shall be paid as extra.

q) Delay in submission: Delay in submission of any part arising due to postal or any other irregularities at any stage will not be considered. The Bank will not be responsible for any damage in transit in case of postal delivery / delivery through courier service.

r) All tenders in whom any of the prescribed conditions are not fulfilled or are incomplete in any respect are liable to be rejected.

s) The acceptance of tender will rest with Indian Bank which does not bind itself to accept the lowest or any tender and reserves to itself the right to reject any or all the tenders received without assigning any reason/s thereof.

t) In case the date of opening of tenders is declared as a holiday, the tenders will be opened on the next working day.

u) Conditional Tenders will be summarily rejected.

<u>Retention money</u>: The Retention percentage (i. e. deduction for interim bill) shall be 10% of the gross value of each interim bills. The Retention Money will be released after 1(one) year (Defect Liability Period) from the date of payment of the final bill provided the contractor has satisfactorily carried out all the works and attended to all defects in accordance with the conditions of the contract, including site clearance.

Defects liability period shall be as per memorandum. It must be realized that this period is for exposure of "Latent Defects". The DLP commences from the date of payment of the final bill for a period of 12 months.

After opening the envelope containing the offer on the standardized conditions and opening of the priced tender, no correspondence will be entertained.

Prior to opening of Financial Bid, Indian Bank/ Deputed Architect, at their discretion may inspect the on - going/completed works of the Contractors as well as obtain confidential report from the concerned employers. The bids of tenders who do not fulfill the above criteria will



Page 2

इंडियन बैंक 🔬 Indian Bank

summarily be rejected. The Bank also reserves to itself the right of accepting the whole or any Part of the tender and the tenderers shall be bound to perform the same at the rates quoted.

Pre-Qualification Criteria : The firms having experience of successfully completed Carpentry Works during the last 7 years ending on 30th September, 2022

1.	3 (three) "similar completed works" costing not less than the amount equal
	to 40% of the estimated cost (Rs. 3.46 lac)
2.	2 (two) "similar completed works" costing not less than the
	amount equal to 50% of the estimated cost (Rs 4.32 lac)

OR

3. 1 (one) "similar completed work" costing not less than the amount equal to 80% of the estimated cost. (Rs. 6.92 lac)

Minimum average turnover of Rs. 8.65 lac (i.e 100% of project cost) during the last 3 (three) years, testimonials to be submitted along with tender in Cover -1.

 The Tenderer should have at least min. 07 years experience of working with nature of works as briefly mentioned below:

i. Civil Interior Works : [1] New partition walls made of wooden, aluminum, gypsum board, bison board [2] False ceiling, acoustic paneling and flooring work [3] Center table, loose furniture [4] Door closer, louver window work, floor spring works [5] All types of anti-termite and pest control treatment works [6] All types of plumbing, sanitary works in the residential / office complex including supply of plumbing and sanitary materials as per the requirement for office premises, board rooms, auditoriums, hotels, resorts etc.

ii. Internal Electrical works : [1] Installation, testing, commissioning of all electrical low tension [LT] works [2] Electrical control panel, wiring, conducting, trunking. [3] Installation of fitting and fixture, chandelier, switches, MCB's [4] Maintenance and repair of earthing system and lightning arrestors. Works for office premises, board rooms, auditoriums, hotels, resorts etc.

The Bidder / Tenderer who are registered as an Interior Contractor with any Institutional, Public Sector and Corporate Sector and having experience of executing above types of works under a single contract may apply with detailed certificates / credentials to the The Dy Zonal Manager, Indian Bank, Dibrugarh Zonal Office, T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001

"similar completed works" means Composite nature of work comprising of Civil work, Carpentry work, Flooring work, Painting work, Sanitary & Plumbing work, Furniture work, Electrical work, and other associated works.

Following documents (with its supporting valid papers) are also to be submitted along with tender in Cover-I.

- 1. Name, address & Type of firm with organization details, Trade License, Registration Certificate Copy, telephone numbers, fax numbers etc.
- 2. List of Govt./ Quasi-Govt. Deptt. and other organizations of repute with whom the company is empanelled/ working.





- 3. List of similar work completed in last 7 years with details enclosing completion certificate from the clients the clients along with the names of two responsible clients/ persons with address & telephone number who will be in position to certify about quality as well as past performance of your organization.
- 4. List of similar works in hand with details enclosing the copies of work orders from the clients.
- 5. Copies of the Audited Balance Sheet for the last three (3) Years along with the Profit & Loss Account.
- 6. Banker's Certificate for credit worthiness.
- 7. Valid Income Tax/ Pan Card, GST Registration Certificate. etc.
- 8. Registered Office in Assam, with supportive trade License and other documents to authenticate the
- 9. List of disputes/ litigations entered into, if any, with its details
- 10. In support of above, the bidder must submit the documentary evidences in the form of Work Order copies & completion certificate etc. without which the offer is liable to be rejected.

NOTE:-(i) The above mentioned documents should be enclosed in sequenced order as mentioned above.

(ii) The agency will be fully responsible for correctness of all documents submitted along with the tender. The false documents may lead to termination of the offer.



Dy. Zonal Manager Indian Bank

Dibrugarh Zonal Office. T.R. Phukan Road, Chirang Chapari, Dibrugarh, Assam-786001



Indian Bank

📥 इलाहाबाद

ALLAHABAD

INDIAN BANK

DIBRUGARH ZONAL OFFICE T.R. Phukan Road, Chirang Chapari Dibrugarh, Assam- 786001

SECTION - II

TENDER DOCUMENTS FOR INTERIOR & CARPENTRY WORKS OF DUBIA BRANCH FROM EXPERIENCED & REGISTERED CONTRACTORS

ARCHIVENTIONS- Architects & Engineers Above Kalita Enterprises, First Floor



Zoonali, R.G Baruah Road, Dibrugarh -786001, Assam PH- +91-9854062928/ +91-3612970463

A. Terms & Conditions

- 1. As far as possible corrections in the tender documents to be avoided. However in case of any corrections, the same should be authenticated by the person who is signing the Tender. Over writing on the tender document is not permitted.
- 2. The Tender should be forwarded in the official letter head of the tenderer.
- The complete Tender documents (duly signed tender conditions, specification, priced bill of quantities etc.) should be addressed to "The Dy. Zonal Manager, Indian Bank, Dibrugarh Zonal Office, Dibrugarh -786001, Assam" and reach the office on or before date fixed and notified in the tender document as mentioned in the cover page.
- 4. The Tenders will not be received after the due date and the time fixed. However, if the **Dibrugarh Zonal Office** desires to extend the time limit, it can do so by informing all the tenderers either before the due date and time fixed for submission or after the due date and time.
- 5. In case the due date for submission / opening of the tender is declared as a public holiday in the State, (where the tender document is to be submitted), the time limit will be automatically changed to the next working day at the same time.
- 6. In case, the tenderer does not wish to quote for the work, the same should be informed to "The Dy. Zonal Manager, Indian Bank, Dibrugarh Zonal Office, Dibrugarh -786001, Assam over letter / fax addressed to The Dy. Zonal Manager on or before the due date of submission of the Tender. The blank Tender also must be returned to the The Dy. Zonal Manager, Indian Bank, Dibrugarh Zonal Office, Dibrugarh -786001, Assam. The technical specification, design and all other contents of the tender documents are patented and the same should not be reproduced without the prior permission of the Dibrugarh Zonal Office.
- 7. The **Dibrugarh Zonal Office** will take no responsibility for delay or loss or non-receipt of tenders after dispatch, by the tenderer.
- The tenderers are advised to hand over the duly filled tender directly to the office of "The Dy. Zonal Manager, Indian Bank, Dibrugarh Zonal Office, Dibrugarh -786001, Assam or ensure that the tender reaches the office before the due date fixed for submission of the tender.
- The tenderers are requested to inspect the site of work and acquaint about the site conditions and rules and regulations before quoting the rates. For this, the officials of Bank may be contacted to make the arrangements.
- 10. The rate quoted should be inclusive of the cost of materials, labour, transportation, loading, unloading, installation, however GST on works contract shall be paid additionally as per the applicable rates.





- 11. The tender should be submitted strictly as per the terms & conditions spelt out in the tender notice. The tenderer should not make any alteration in the terms & conditions, drawings, specifications etc. In case of any alteration the tender may be considered as invalid/void.
- 12. Incomplete tenders are liable to be rejected.
- B. Pre-Qualification Criteria: The firms having experience of successfully completed Carpentry Works during the last 7 years ending on 30th September, 2021
 - 1. 3 (three) "similar completed works" costing not less than the amount equal to 40% of the estimated cost (Rs. 3.46 lac)

OR

 2 (two) "similar completed works" costing not less than the amount equal to 50% of the estimated cost (Rs 4.32 lac)

OR

- 3. 1 (one) "similar completed work" costing not less than the amount equal to 80% of the estimated cost. (Rs. 6.92 lac)
- Minimum average turnover of Rs. 8.65 lac (i.e 100% of project cost) during the last 3 (three) years, testimonials to be submitted along with tender in Cover I.
- 5. The Tenderer should have at least min. 07 years' experience of working with nature of works as briefly mentioned below:

i. Civil Interior Works : [1] New partition walls made of wooden, aluminum, gypsum board, bison board **[2]** False ceiling, acoustic paneling and flooring work **[3]** Center table, loose furniture **[4]** Door closer, louver window work, floor spring works **[5]** All types of anti-termite and pest control treatment works **[6]** All types of plumbing, sanitary works in the residential / office complex including supply of plumbing and sanitary materials as per the requirement for office premises, board rooms, auditoriums, hotels, resorts etc.

ii. Internal Electrical works : [1] Installation, testing, commissioning of all electrical low tension [LT] works [2] Electrical control panel, wiring, conducting, trunking. [3] Installation of fitting and fixture, chandelier, switches, MCB's [4] Maintenance and repair of earthing system and lightning arrestors. Works for office premises, board rooms, auditoriums, hotels, resorts etc.

"similar completed works" means Composite nature of work comprising of Civil work, Carpentry work, Flooring work, Painting work, Sanitary & Plumbing work, Furniture work, Electrical work, and other associated works.

Following documents (with its supporting valid papers) are also to be submitted along with tender in Cover-I.

- 6. Name, address & Type of firm with organization details, Trade License, Registration Certificate Copy, telephone numbers, fax numbers etc.
- 7. List of Govt./ Quasi-Govt. Deptt. and other organizations of repute with whom the company is empanelled/ working.
- 8. List of similar work completed in last 7 years with details enclosing completion certificate from the clients the clients along with the names of two responsible clients/





persons with address & telephone number who will be in position to certify about quality as well as past performance of your organization.

- List of similar works in hand with details enclosing the copies of work orders from the clients.
- Copies of the Audited Balance Sheet for the last three (3) Years along with the Profit & Loss Account.
- 11. Banker's Certificate for credit worthiness.
- 12. Valid Income Tax/ Pan Card, GST Registration Certificate. etc.
- 13. Registered Office in Assam, with supportive trade License and other documents to authenticate the same
- 14. List of disputes/ litigations entered into, if any, with its details
- 15. In support of above, the bidder must submit the documentary evidences in the form of Work Order copies & completion certificate etc. without which the offer is liable to be rejected.

NOTE:-(i) The above mentioned documents should be enclosed in sequenced order as mentioned above. (ii) The agency will be fully responsible for correctness of all documents submitted along with the tender. The false documents may lead to termination of the offer.

C. Opening of the Tender:

1. The sealed tenders will be opened in the presence of the authorized official of the Consultant Architect/ Officers from **Dibrugarh Zonal Office** on the day and time as specified on the cover pageno.1.

2. Intending tenderers who wish to be present at the time of opening of tenders may be present at the office address as mentioned in cover page no. 1, on the day fixed for opening of the tender.

C. Acceptance of the tender :

1. The rates quoted by the contractors should be valid as specified in the cover page no 1.

2. Dibrugarh Zonal Office / Architect reserves the right to accept / reject summarily any / all tenders in whole or part thereof without assigning any reason whatsoever and also does not bind itself to accept the lowest or any other tender.

3. It will be open to **Dibrugarh Zonal Office** / Architect to negotiate the terms including the rates quoted with the lowest tenderer. The negotiated price by **Dibrugarh Zonal Office** / Architect will be the contract value and work order will be placed for the said amount.

4. The tenders for the work shall remain for acceptance for a period as specified on the cover page or the period that may be extended by mutual agreement and the tenderers shall not cancel / withdraw the tenders during that period.

5. Each tenderer must submit an Earnest Money Deposit as mentioned on the cover page (page no.1) of the tender in the form of a **Demand Draft/ pay order only** in favour **"Dy. Zonal Manager**, Indian Bank, **payable** at Dibrugarh drawn on any Nationalized bank other than the clientele Bank. **No tender will be accepted without EMD.** The EMD will not carry any interest. In case of failure on the part of the contractor for commencement of work / delay in execution of the project, the said amount will be forfeited.





6. The Earnest Money will be returned to the unsuccessful tenderer after the intimation of rejection of the tender is sent. The Earnest Money will be retained in the case of the successful tenderer and will get converted as a part of Security Deposit for the due performance of the contract.

7. Earnest Money Deposit will be forfeited, if the contractor:

a. Revokes the tender or increases the earlier quoted rates within the validity period.

b. Refuse, delay to sign and execute the contract after tender is accepted.

c. Does not commence the work within the time specified in the letter of intent/work order or 7 days from the issue of such letter, whichever is later.

8. The tenders will be rejected;

a. If the contractor does not quote any of the item / sub-item in the tender

b. If the contractors makes any correction in the rate while quoting, not countersigned and duly stamped for the correction of that particular item of work.

9. The tenders which does not fulfill any of the prescribed conditions will not be accepted.

10. Canvassing in connection with the tender is strictly prohibited.

D. Execution of Work :

1. The work should commence *within the period specified on the cover page i.e.7 days* from the date of the receipt of work order or the date that may be indicated in the work order. Accordingly, date of commencement of the work will be reckoned from the day as specified in the cover page.

2. The work should be completed as specified on the cover page calculated i.e. 30 days from the date of commencement of the work/Date of issue of Work Order or within the time limit that may be indicated in the work order.

3. Time allowed for execution of work, as specified in tender, shall be the essence of the contract, However the tenderer shall plan the execution of the said work and it needs to be carried out without disturbing the running of the office or as per the client's instructions strictly within the schedule Time as specified in the Tender.

4. If the tenderer commits default in commencing the work, as required by the work order and found that the date stipulated cannot be adhered to, **Dibrugarh Zonal Office** / Architect shall be entitled without prejudice to any other rights or remedies available and/or may terminate / rescind the contract.

5. If the tenderer fails to carry out the work within the stipulated time mentioned in the work order, the **Dibrugarh Zonal Office**/ Architect will have liberty **to impose penalty @ 2% of the certified final bill per week** of delay subject to an overall limit of 10%, without prejudice to other remedies available. The tenderer has to pay to **Dibrugarh Zonal Office**/ Architect such amount that may fall short over the amount due to them, if any.

6. However, if **Dibrugarh Zonal Office**/ Architect is convinced that the delay in execution of the work is beyond the circumstances created by the tenderer, it may award extension of the same to the extent it feels justified based on the request of the tenderer. In such case liquidated damages will be levied for the balance period, if any as provided as per the condition of the tender.





7. If the tenderer fails to commence the work within the days i.e 7 days as specified on the cover page from the date of receipt of intimation for commencement of the work and / or the contractor fails to show progress in execution of work and **Dibrugarh Zonal Office**/ Architect feels the work cannot be completed within the stipulated time, **Dibrugarh Zonal Office**/ Architect will have the right to terminate the contract by **giving three days notice** to the contractor, at the full discretion of **Dibrugarh Zonal Office**/ Architect will be final and binding. In case of termination of the contract, the payment if any, due to the contractor will be released only on completion of the entire project. The amount that may be spent for completion of the balance work will be recovered from the contractor. It will be the full discretion of **Dibrugarh Zonal Office**/ Architect to carry out the balance work through any agency at any rate as per the specification.

8. All the *materials and workmanship* shall be of the kind described in the schedule of quantities / specifications and in accordance with relevant BIS codes and as per directions of the Engineer-in-charge.

9. The tenderers shall submit photocopies / originals of vouchers / challans etc., for verification of actual purchases of any material, if so, desired by the Engineer-in-charge.

10. The tenderer shall have to carry out testing of all materials brought on site at their own cost in any institute / laboratory / site of works as desired by the Engineer-in-charge. No extra claim will be entertained for such testing of materials.

11. The tenderer shall not at any time do, cause or permit any nuisance on the site/ do anything which shall cause unnecessary disturbances or inconvenience to the occupants / visitors at site or near the site of work.

12. The quantities indicated in the bill of quantities are approximate and the quantities may vary as per the site conditions / requirements. The rate quoted should be firm for the deviated quantities of work also.

13. The tenderer's workers will not be allowed to stay at the work site.

14. The tenderer or his workers can use the common facilities such as water, electricity etc., provided at the premises. However, it should be ensured that the same should be kept in hygienic condition.

15. Water and Electricity as per the availability at site can be made use of by the contractor. If not available the contractor has to arrange it on his own. However, the actual consumptions of water and electricity should be payable by the contractor only. Failure to pay the electricity and water charges will be deducted from the bill of contractor.


16. In case of any damage to the existing structure, the tenderer should rectify the same free of cost up to the satisfaction of the Engineer-in Charge.

17. Dibrugarh Zonal Office/ Architect will have the liberty to modify the design to a reasonable limit. No extra charges will be paid for execution after such modification.

18. The tenderer should protect the work till its completion and handing over against any possible damage, theft, scratches, etc.

19. The tenderer has to make arrangements for cleaning the work site every day and on completion of the work from the work area at his cost.





20. The tenderer should provide samples of the materials for approval of **Dibrugarh Zonal Office**/ Architect and the samples will be kept in the custody of the Engineer-in-charge.

21. Wherever possible the work has to be carried out at the factory of the contractor and the items to be transported to the site.

22. The tenderer should make necessary arrangement for inspection of the items made at his factory / work place by the Engineer-in-charge. The tenderer should complete fabrication and other works at factory and only assembling work and the finishing may be carried out at the site.

23. The tenderer should abide by the rules and regulations for the premises especially on the working hours, entry to the workers to the premises, interpersonal relation with the staff members and other agencies engaged at the site.

24. The tenderer should make necessary arrangement for covering of all the furniture items/ records, if any of the client with cover / cloth during the course of work.

25. The tenderer should arrange a qualified technical supervisor at site during the course of the entire work. The tenderer should not change the supervisor till completion of the work or the contractor should arrange the alternative supervisor at site on the basis of the site requirement. The supervisor should be available at site when the work is in progress.

26. Any damage / loss to Dibrugarh Zonal Office/ Architect will be rectified at the cost & risk of the contractor.

27. The workmanship should be of high quality / standard and the decision of the Engineer-incharge / Consultant shall be final in this regard.

28. The tenderer should not apply primer / putty work / paint or any other finishing material before inspection and certification of the wood work by the Engineer – in – Charge.

29. The tenderer should not engage any person prohibited by the law for execution of the job.

30. The tenderer should carry out the work strictly as per the specification and as directed by the Engineer-in- Charge.

31. All the materials proposed to be used should have the approval of **Dibrugarh Zonal Office**/ Architect . 32. The materials required for the work **should be purchased only from the manufacturers directly or from the approved dealers**. Confirmation for the same may be submitted if so desired by the Engineer-In-Charge.

33. The tenderer should strictly follow the approved colour scheme. The colour scheme will be intimated to the contractor within a week from the date of issue of the work order. However **Dibrugarh Zonal Office**/ Architect has the liberty to make any other modifications as per requirements.

34. The tenderer shall ensure that the dismantled material / debris are removed from the site daily and transported out to the place as designated by the Municipal Corporation at his own cost.

35. The tenderer shall ensure make his own arrangement for storage of materials. **Dibrugarh Zonal Office**/ Architect or the client may provide some space subject to availability (uncovered) within the premises for





storage purpose. Materials only as per requirement are to be stored at site. Security for the material lying at site will be arranged by the contractor.

36. Any damage / loss will be rectified at the cost & risk of the tenderer.

37. The tenderer has to maintain a book for instructions from the Engineer-in-charge.

38. The work needs to be carried out as per the instruction of the **Dibrugarh Zonal Office**/ Architect and completed within the stipulated time period. It is the responsibility of the tenderer to take all kinds of security and safety measures of all the existing office furniture, equipment and valuables at site during the execution of the work. During the execution, in case of any damage to the existing furniture, office equipment etc. It is the responsibility of the contractor to repair/ rectify the same, failing which the cost shall be recovered from the contractor's bill.

39. If required, the entire furniture, office equipment and other accessories shall be strictly covered with plastic sheets etc. to avoid any damages, all the furniture shall be cleaned and workable by the contractor before the start of office every day and one supervisor with required labour shall be made available with the office to attend complaints, if any from the concern official.

40. It is the responsibility of the contractor to get the confirmation certificate from the client after virtual completion of the work. The work will be considered as virtually completed only when the tenderer completes the entire work as per the specification and after joint inspection of work by the Engineer-in-charge and contractor.

41. All the electrification work shall be carried out by a licensed electrician under the supervision of the contractor. After completion of the work, the tenderer/contractor shall submit the test certificate for the electrical work carried out by them.

42. It is the responsibility of the contractor to take all the necessary permissions from the Local Municipal Corporation and other Government agencies/authorities to carry out the contract work.

43. No advance and Running payment will be paid. Contractor shall be made the final payment after joint inspection and final payment recommendation by the concerned architect/ EIC.

44. The entire interior work shall be guaranteed to be free from manufacturing defects, defective workmanship or materials and any defects that may appear within 6 months from the date of issue of completion certificate which in the opinion of the Bank/Consultants have arisen from bad manufacturing, workmanship or materials, shall upon intimation be made good by the Contractor at his own cost within the time specified. During the said period of 6 months the Contractor shall without any extra cost, carry out all routine and special maintenance of the Interior and attend to difficulties and defects that may arise. The Tenderer / Contractors shall associate with him during the execution and free service period, the operation and maintenance staff of the Bank.

45. Contractors shall insure whole work against fire, PICT and third party.

E. BILLS & PAYMENTS TERMS AND CONDITIONS

1(a.)The billing is to be done in the name of the "The Dy. Zonal Manager, Indian Bank. As specified on cover page (page no. 1) of the tender.





1(b) The Contractor has to submit the bill strictly as per the format of the specifications as mentioned on the bill of quantities in the tender document along with the Electric Audit Report done by License Electrical Supervisor (Govt Regd).

NOTE : It is the responsibility of the contractor to take the no objection certificate / no defects certificate from the concerned client on completion of the Defect Liability Period. Dibrugarh Zonal Office/ Architect would not be responsible for the certificate.

In case the no defect certificate / no objection certificate is not taken by the contractor, then the defect liability period will increase till the said no defect certificate / no objection certificate is obtained by the contractor from the concerned Regional Manager.

2. Income Tax, GST and / or any other statutory deductions as per the prevailing rules at the time of execution will be deducted from the payable amount for which certificate will be issued in favor of the tenderer.

3. Tenderer will not be entitled to any interest on Retention Money or Security Deposit or any Running account bill money for the time such money will remain with the Client.

4. The items of works as well as the approximate quantities against these items as given in the schedule of *quantities and the same should not be considered precise quantity of works to be carried out*. The tenderer shall be paid on the basis of the actual quantity of completed work as per the provisions of the contract and as per the specifications.

5. It is possible that certain extra items of work may come up during the course of work. The payment for such items will be made based on Engineering/Market rate analysis. A component of 15% on the cost of material (actual purchase cost / market price without any wastage) and labour will be considered as tenderers profit and other overheads.

6. The Tax invoice and the abstract of the bill should be submitted strictly as per the approved format of **Dibrugarh Zonal Office**/ Architect .

7. The bill should be attached with all necessary measurements, sketches, joint measurements (if any).

F. Escalation :

1. No escalation in rate shall be paid for the works carried out.

2. No claim on account of fluctuation of rates of material and labour will be entertained during the course of work – (from the date of acceptance of the Tender till issue of completion certificate).

3. <u>Contractor should strictly note that the Project cost escalation beyond 10% (Five percent) of the tendered value shall not be entertained</u>.

G. Defect Liability Period :

1. Defect Liability Period as per the terms of the contract is **12 months** from the date of payment of the final bill. The contractor has to satisfactorily carry out all the works and attended to all defects in accordance with the conditions of the contract, including site clearance.





2. The **Retention Money** will be refunded only after the defect liability period of *12 months* and Rectification of the defects occurred whether pointed out in writing or not. It will be the duty of the contractor to inspect the site for defects and rectify the defects within the defect liability period.

3. During the course of Defect Liability Period the tenderer has to rectify all the defects,

4. In case the tenderer fails to attend the rectification work within 7 days of reporting the same in writing, **Dibrugarh Zonal Office**/ Architect will have the liberty to carry out the said work through some other contractor at the cost & risk of the tenderer. Such expenditure incurred to the client will be recovered from the Security Deposit. In case any expenditure incurred is more than the Security Deposit, the tenderer should pay the difference that may fall short.

5. While carrying out the rectification work, the tenderer should ensure that the surroundings should be protected against any possible damage. In case of any damage, the same should be made good by the tenderer.

H. Statutory obligations to be followed :

1. The tenderer should ensure adherence of all statutory requirements under the State and Central Rules in force and other local bodies for smooth and timely completion without any additional cost.

2. The tenderer shall comply with the provisions of all the rules and regulation in respect of labours engaged at site (such as Contract Labour {Regulation & Abolition} Act, 1970, Minimum Wages Act, Apprentice Act and all other labour laws as may be enforced from time to time by the Government Authorities) for execution of work, procurement of material for completion of the entire project **Dibrugarh Zonal Office**/ Architect shall not be held responsible for any penalty on failure to comply with any of the labour regulations or legal requirements or failure of any compliance of any rule in force.

3. The tenderer shall strictly comply with the provision of GST, etc. All the duties / taxes with respect to the work should be borne and paid by the tenderer himself and **Dibrugarh Zonal Office** shall not be responsible for any payment/ penalty on this account at any stage.

4. In case any goods are manufactured at the tenderers office / site, the tenderer has to pay applicable taxes and he has to produce Tax Invoice Copy for removal of goods from the manufacturing site. In case the goods are manufactured or produced at the site then Excise. Invoice showing that the Tax has been paid should be submitted to **Dibrugarh Zonal Office**.

5. The tenderer should submit a statement confirming that all duties / taxes of every nature covered under the contract have been paid and the tenderer shall indemnify the **Dibrugarh Zonal Office** and the Architect against all claims in that behalf.

6. The tenderer should ensure adherence of all the requirements and statutes under the State and Central Rules in force.

7. The tenderers should submit an affidavit / Declaration for payment of Taxes as per the enclosed format.

8. The tenderer should also submit when required, a copy of the declaration filed with the GST for the last financial year.





I. Responsibilities of the tenderer

1. The tenderer should enter into an agreement as per the articles of agreement on stamp paper attached with this notice within 7 days of issue of acceptance of the tender

2. The tenderer shall not sublet the work without written approval from Dibrugarh Zonal Office / Architect

3. The tenderer should co-ordinate with all the other contractors for execution of the project.

4. The tenderer should set out the layout at site before commencement of work and obtain approval for the same from **Dibrugarh Zonal Office** / Architect .

5. The contractor should arrange for sufficient light & power point required for entire project at his cost.

6. The tenderer should clear the site within 7 days of virtual completion of work of all material not paid for. The work will be considered as virtually completed only when the tenderer completes the entire work as per the specification and after joint inspection of work by the Engineer-in-charge and tenderer.

7. The tenderer should submit the schedule and bar chart of work before commencement of the work within 7 days of receipt of work order.

8. The tenderer should take adequate precaution against fire hazard at site. The tenderer should ensure that all fire safety measures are taken during execution and that the work carried out is as per the fire safety norms of the local Fire office.

9. The tenderer should arrange scaffoldings / ladders for proper execution of work, and shall also ensure safety of the workers as per the relevant provisions of the law.

10. The tenderer should submit rate analysis for the extra/deviated items of work before commencement of the work.

11. The tenderer should submit samples of the material proposed to be used for the approval of **Dibrugarh Zonal Office** / Architect .

12. The tenderer should prepare mock-up of the items for the approval of the **Dibrugarh Zonal Office** / Architect and as per the advice of **Dibrugarh Zonal Office** / Architect, the contractor has to modify the mock-up samples till it meets with the approval of the **Dibrugarh Zonal Office** / Architect. The expenditure that may be incurred for making the mock-up samples should be included in the respective items of work.

13. In case the tenderer is a partnership firm, any change in the constitution of the firm shall take place only with the prior approval of **Dibrugarh Zonal Office** / Architect during the contract period.

14. The tenderer should submit shop drawings for all the items for the approval of **Dibrugarh Zonal Office** / Architect before execution of each item of work.





INDIAN BANK, DIBRUGARH ZONAL OFFICE, DIBRUGARH , -782001, Assam

	SUMMARY				
Time of Completion	30 days from the date of commencement of work				
Date of Commencement of work	Within 7 days from the date of issue of work order.				
Liquidated damages	2 % of the total final certified value per week subject to the maximum of 10 % of the final certified value.				
Validity of the offer	180 days from the date of opening the tender.				
Security Deposit (Retention money)	10 % of total value of work done.				
Price escallation	Project cost escalation beyond 10% (Five percent) of the tendered value shall not be entertained				
Defects Liability Period	12 (Twelve) months from the date of final payment of the bill.				
Terms of Payment	 1.No advance 2.No RA bill / Interim Payment shall be paid against the work 3. Final Bill settlement within 30 days from the date of proper submission of all required documents and joint verification of measurements at site by bank's appointed Architect/ Consultant 				
Deductions	 Income Tax at source as per Income Tax Rules /GST TDS as applicable in the statement. Any other Levy/Cess/Tax to be deducted at source by law. 				
Extra / Additional work	Cost of material and labor plus 15% extra towards overheads and profit				

I / We hereby agree and accept the above terms and conditions.

(Seal) Signature of the Tenderer

For (Name and address of the Contractor)





🙇 इलाहाबाद

ALLAHABAD

For (Name of the Contractor and Designation)

Annexure-I (On Rs.100/- non-judicial stamp paper by the successful bidder)

From : The Contractor

To Indian Bank, Dibrugarh Zonal Office, Dibrugarh , Assam

Dear Sirs,

We refer to the tender dated _____

for premises mentioned on cover page (page no.1) of the tender. We hereby confirm that we have complied at the with all formalities in the performance of our Contract for the supply of goods and services under all statutes governing the same, Central, State or Local. We further confirm that we have paid all taxes and duties including sales tax and excise duty in respect of the goods and services supplied to you and undertake to be responsible for the same.

We agree to indemnify and keep you indemnified against any claim or demand and all loss, costs, charges and expenses incurred or suffered by you as a result of any claim being made by any person in respect of our obligation under the said tender for payment of taxes, duties or otherwise.

Yours truly,

Date :



SIGNATURE OF CONTRACTOR



WITH RUBBER STAMP

Annexure – II

(On Rs.100/- non-judicial stamp paper by the successful bidder)

From : The Contractor

To : Indian Bank, Dibrugarh Zonal Office, Dibrugarh , Assam

Dear Sirs,

We / I refer to the tender / contract dated ______ for supply of goods and services at the premises mentioned on cover page (page no.1) of the tender. We / I advise that, we / I are / am covered under the exemption limit prescribed by the Central Excise Act 1944 and no Excise is payable by us / me on the goods and services supplied to you. We / I further confirm that we / I have complied with all the formalities in the performance of our contract for the supply of goods and services and under all statues governing the same, Central, State or local.

We / I undertake that if any taxes and duties including sale tax and Excise duty in respect of goods and services supplied to you by us / me is payable, the responsibility of paying the same shall be our /mine. We / I agree to Indemnify and keep you Indemnified against any claim or demand and all loss, cost, charges and expenses incurred and suffered by you as a result of any claim being made by any person in respect of our / my obligation under the said tender / contract for payment of taxes, duties or otherwise.

Yours truly,

Date : _____





SIGNATURE OF TENDERER WITH RUBBER STAMP

Special conditions of the contract

1. The wood to be used should have similar / uniform grains and should be totally free from white portions, decay, knots etc.

2. All the edges of the plywood should be teak wood beadings. The beading to be fixed with adhesive / screw/ nails.

3. The measurements indicated in the drawings are approximate and may vary as per the site conditions. **Dibrugarh Zonal Office** / Architect's interpretation of the design and the specifications mentioned in the entire document shall be final and without appeal. In case of Errors or inconsistency, if discovered in the drawing and specifications, **Dibrugarh Zonal Office** / Architect's interpretation shall be final and without appeal.

4. The contractor shall submit the Bar Chart & PERT chart before commencement of work and the progress chart during the course of work.

5. For the design and other details mentioned in the entire document **Dibrugarh** Zonal Office / Architect alone has the patent right.

6. The contractor shall take the prior approval from **Dibrugarh Zonal Office** / Architect for subletting the job even if the same is to a specialized agency.

7. In case **Dibrugarh Zonal Office** / Architect rejects a particular work the tenderer shall remove the same within two days and no payment shall be made for such work.

8. The Contractor has to take all safety measures with regard to the workmen employed as per relevant laws and good engineering practices at site and safety measures against the fire hazard.

9. The contractor has to make necessary arrangement for internal lighting at the site.

10. The contractor has to carry out the job strictly as per specification spelt out in the bill of quantities, the drawings, instructions that may be issued by the Engineer-in-charge and the specification of the Bureau of Indian Standards, National Building Code etc.

11. In case of any discrepancy between the specifications and the drawings, the details mentioned in the specifications / Bill of quantities may be taken as final.





12. The electrical installation works are to be carried out by engaging licensed electrical contractor. The successful tenderer shall submit the photocopy of Electrical Contractor's license at the time of execution of work. The copy of license of Electrical Supervisor and electricians also are to be submitted.

13. The contractor shall submit the single line drawing of electrical installations/wiring of completed work along with the final bill.

14. The contractor shall submit the Test Certificate of the Electrical installations carried out by him as per requirement of local Electrical supply Authority, Indian Electricity Rules, and Indian Electricity Act. 15. The work shall be carried out on holidays and Sundays after and before office hours and during office hours on working days. The Contractor shall ensure that there shall not be any problem, disturbance in office/other areas/floors as the work is to be executed in working office.

16. The Contractor shall depute one electrician and one helper during office hours to avoid any electrical breakdown in electrical installation.

17. The contractor has to carry out the job strictly as per specification spelt out in the bill of quantities, the drawings, instructions that may be issued by the Engineer-in-charge and the specification of the Bureau of Indian Standards, National Building Code etc.

18. Contractors shall insure whole work against fire, PICT and third party.

19. In case of any discrepancy between the specifications and the drawings, the details mentioned in the specifications / Bill of quantities may be taken as final.

20. All disputes and differences of any kind whatever arising out of or in connection with the contract or the carrying out of the works (whether during the progress of the works or within 12 months from the date of virtual completion of the work and whether before or within 12 months of determination abandonment or breach of the contract) shall be referred to giving inter-alia full details of the matter under dispute like quantities, rates, amount claimed .and the reason thereto and settled by the Bank who shall state his The Arbitrator shall have power to open up, review and revise any Certificate, opinion, decision requisition or notice, save in regard to the excepted matters, referred to in the preceding Clause and to determine all matters in dispute which shall be submitted to arbitration and of which notice shall have been given as aforesaid. The Arbitrator shall make his award within one year (or such further extended time as may be decided by him or them as the case may be with the consent of the parties) from the date of entering on the reference. In case during the arbitration proceedings the parties mutually settle, compromise or compound their dispute or difference, the reference to arbitration, the reference to arbitration and the appointment of the Arbitrator shall be deemed to have been revoked and the arbitration proceedings shall stand withdrawn or terminated, with effect from the date on which the parties file a joint memorandum of settlement thereof; with the Arbitrator or the Arbitrators as the case may be. The submission shall be deemed to be a submission to arbitration within the meaning of the Indian Arbitration Act, 1996 or any statutory modification thereof. It is agreed that the Contractor shall not delay the carrying out of the works by reason of any such matter, question or dispute being referred to arbitration, but shall proceed with the works with all due diligence and shall, until the decision of the Arbitrator or Arbitrators as the case may be, is given.

21. The work will be awarded to the agency that has given the lowest rate (L-1). Additionally,



The L2 Bidder will be asked to confirm if he can do the work at the lowest rates quoted by L1.

Indian Bank, Dibrugarh Zonal Office, T.R. Phukan Road, Chirang Chapari, Dibrugarh- 786001

Page 20



If the L2 gives a letter confirming that he is ready to carry out the work at the lowest rate (L1), then it can be considered to award the work to him also. The condition of this award of work to L2 on the rates of L1 will be as under:

1. When L1 denies in writing that he does not have capacity to do the work.

2. When it is observed by Dibrugarh Zonal Office / Architect. That L1 has not completed more than 3 sites in time.

3. When defects are found in the work of L1.

4. When L1 does not take up the work as assigned within the stipulated time period as mentioned in the work order.

PREAMBLE TO THE BILL OF QUANTITIES

The work proposed is to be carried out at the Office premises mentioned on the cover page (no.1) of the tender. The premise is proposed to be provided with Furnishing, civil, plumbing works. The quality of work proposed should have *the best* workmanship. The contractor should ensure that only the first quality materials mentioned in the list of material is purchased for the project.

1. The work should be carried out in such a way that the structure is not disturbed.

2. Any difference / discrepancies in the specification should be clarified with the Engineer in charge before submitting the tender. The Engineer in charge will have the liberty to modify the specification to a reasonable limit to suit the basic concept during the course of work; the tenderer should carry out such work without any extra cost.

3. In case of any major modification such items will be considered as an extra items. Payment for such items will be paid based on the Engineering rate / Market rate analysis. **15% of the total cost of material and** *labour* will be considered as **tenderer's profit**.

4. The contractor should co-ordinate with the other contractors employed at the site for smooth flow of work.





SPECIFICATIONS LIST OF PREFFERED MAKE / BRAND ALL WORKS

1

Sr.

No.	LIST OF MATERIALS & SUPPLIERS	SUGGESTED MAKE LIST
1	INTERIOR WORKS	SOUCCEP MARE LIST
	Asbestos Fibre Cement Wall Board	EVEREST or equivalent
	Plywood(any Grade)	Century, Greenply, Duroply, or equivalent
	Block Board(any Grade)	Century, Greenply, Duroply or equivalent
	Laminate	Century/ GreenLam/ Merino/ Sunmica/ Aica
	Adhesive	Fevicol / Araldite/Anchor or equivalent
	Flush Door	Century, Kitply, Greenply, or equivalent
	Polish	Asain / Dulex or equivalent
	Latex	MM Foam or equivalent ISI make
	High density foam	U Foam or equivalent ISI make
	Locks	Godrej / Haffle / Hettich / Ebco or equivalent
	Storage Hardware	Godrej / Haffle / Hettich / Ebco or equivalent
	Screws / Nails & other accessories	GKW / Nettleford or equivalent
	Plain/Toughened glass	Saint- Gobain Indo Asabi, Madi ana i da
	Hardware for main Glass doors (patch fittings)	Saint- Gobain, Indo Asahi , Modi or equivalent Dorma / Euro/ Ozone / Enox / Ebco /Hamco or equivalent
	Door Closers (general use)	Dorma / Euro/ Ozone / Hafele / Ebco /Hamco or equivalent
	Floor springs (general use)	Dorma / Euro/ Ozone / Hafele/ Ebco /Hamco or equivalent
	Floor springs for main glass doors	Dorma / Euro/ Ozone / Hafele / Ebco /Hamco or equivalent
	Aluminium Sections for Paritions	Jindal / Tata steel or equivalent
	False Ceilings: Gypsum	India Gypsum / Saint Gobin / USG Boral
	False Ceilings: Grid (As Approved)	Armstrong / AMF or equivalent
	GI Sections	India Gypsum / Saint Gobin / Jindal or equivalent
	POP Punning	Gyprock / India Gypsum / Birla
	Paint	Asian / Nerolac / Dulex / Berger or equivalent
	Rolling / Vertical Blind	Vista / Peritex / Winfab / MAC or equivalent
	Glass	Saint Gobin / equivalent

	LIST OF MATERIALS & SUPPLIERS	SUGGESTED MAKE LIST
1	ELECTRICAL	
	Light Fittings	Philips / Syska / Havells / Bajaj





......

डलाहाबाट

		ALLAHABAD
	MCCB, MCB, RCCB, DB, ICTPN TP, HRC Fuse, cahnge over switch, switch fuse Unit	L&T, ABB, Legrand, Siemens, Schneider
	FRLS insulated Elec. Wire/ cable armourd, unarmourd, Sheathed, unSheathed, flexible LT cable, Multi core, single core cable, flat cable	
	PVC conduit(HEAVY DUTY ONLY)	CAP/Finolex/Polycab
	PVC insulated copper conductor Wires	Finolex/ Polycab/RR Cable
	Distribution Box	Legrand/ Schneider/ ABB/Siemens
	MCB & MCCB	Legrand/ Schneider/ ABB/Siemens/L&T
	Modular Switches	ABB/Legrand/MK/ANCHOR/ ELLEYS/ROMA
	Power cable	CCI/ Skytone/ Universal/ LAPP/ Torrent
	End Termination	Raychem/ Mahindra/ELMEX
2	Ceiling, Wall & Exhaust Fan	Crompton/Havells/Bajaj/Usha
	Casing Caping	Finolex/Cap or equivalent
	Miniature Circuit Breaker	ABB/MDS/LEXIC/ Clipsil/Siemens/HPL
	Earth Leakage Circuit Breaker	MDS/LEXIS/Siemens/HPL
	MCB Distribution Boards in sheet steel housing (double door)	ABB/MDS/LEXIC/Siemens/HPL
	Telephone Cable	Skytone/ Delton/ NICCO/Polycab/ Finolex
	Switch, TV & Telephone socket & boxes (Modular Type)	CPL/ Legrand/ABB/Anchor
	Timers	L&T/ Legrand/ Schneider/Siemens/GE
	Timer Switch	L&T/Legrand/Schneider/Siemens/GE
2	Networking	C C C C C C C C C C C C C C C C C C C
	Switches	Brocade/Cisco/Digi-Link/3Com/Nortel/Foundry/D-Link
	Patch Panel, Patch cord and I/o	Digi-Link / Tyco(AMP) /Schneider/D-Link
	Cable	Digilink/Clipser/National/Polycab/Lapp/Finolex
	Racks	ComRack / HCL / ValRack / APW President

NOTE :-

- The tenderer shall use all the material strictly as per the list of approved make as stated above, it is mandatory to take the written confirmation well in advance if the material as stated above is not available and / or the same is not suitable (colour, size, shape, texture) as per the site condition.
- In case the tenderer wish to verify the detailed specification of materials, workmanship etc. the same may be verified from the office of Architect before submission of the tender.

Whether a product is equivalent or not will be decided by the Engineer-in-Charge/ Architect only.



ESTIMATED COST SUMMARY INDIAN BANK'S DUBIA BRANCH WITH ONSITE ATM DESCRIPTION	
DESCRIPTION	
	AMOUNT
BRANCH WORKS	AMOUNT
PART.A	
RTITION, COUNTERS, STORAGE, FALSE CEILING	
AL WIRING, CABLING, DATA & TELEPHONE WIRING	
TOTAL OF PART A	
PART-B	CONTRACTOR DESCRIPTION
RKSTATIONS, CHAIR & SOFA	Contraction of the second second
TOTAL OF PART B	The second second second second second
PART C	
IONING WORKS	
TOTAL OF PART C	
DADT D	
BUNDS SUCCESTION BOX EDOCTED TO US	
ACRYLIC FRAMES	IN
TOTAL OF PART D	
TAL (A+B+C+D)	
	RTITION, COUNTERS, STORAGE, FALSE CEILING AL WIRING, CABLING, DATA & TELEPHONE WIRING TOTAL OF PART A PART-B DRKSTATIONS, CHAIR & SOFA AL FIXTURE TOTAL OF PART B PART C TONING WORKS TOTAL OF PART C PART-D : BLINDS, SUGGESTION BOX, FROSTED FILIMS, MIRROR, COLUM 5, ACRYLIC FRAMES



PROJECT NAME - ESTIMATED BOQ FOR CARPENTRY WORKS OF DUBIA BRANCH WITH ONSITE ATM CLIENT NAME- INDIAN BANK, DIBRUGARH ZONAL OFFICE WORK TYPE- CARPENTRY WORKS							
R.NC	DESCRIPTION	UNIT					
A	PART-A (I) : DOOR, PARTITION, COUNTERS, STORAGE, FALSE CEILING	UNIT	QNTY	RATE	AMOUNT		
1	PARTITION WORKS						
	Note :- The rate shall be include of frame work above false ceiling level. Measurement should be taken	_					
а	FULL HEIGHT PARTLY GLAZED PARTITION						
(i)	BOTH SIDE LAMINATE						
	Providing and fixing partition framing which shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.	SFT	168.00				
ii	FULL HEIGHT SOUD BARTITION IN DOTINGED IN THE						
	FULL HEIGHT SOLID PARTITION IN BOTH SIDE LAMINATE Providing and fixing Full Height Solid partition in aluminium framing which shall consist of Heavy duty Aluminium Bay Sections Former	SFT	196.00				
	Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be fixed with 8/9 mm thk. commercial grade plywood on both side and finished with 1mm Laminate of approved shade and make . Approved make 5/6 mm thick itched Float glass or clear glass fixed with frosted film as per design, to be fixed at an height as mentioned in the drawing or as directed by the architect . The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood should be finished with melamine Polish.						
).	Semi ht Solid / Glazed Partition	SFT	38.00		-		
	Specification same as 4 above but of low ht as per the drawing. All external surface and edges to be finish with 1mm thk laminate of approved shade & make. Providing and Fixing inserted Soft board / White boards / Glass maintaining the vertical surface lines and no extra measurements would be taken for the soft boards / white boards / Glass.	51	28.00				
	ALUMINIUM HEAVY DUTY FRONT GLAZING WITH ANODISED SECTIONS (As per Colour Specified by Bank)	SFT	136.00				
	Providing and fixing fully glazed heavy duty alluminium sections (14 Guage) at the main entrance as shown in the drwng. Glazing shall consist of approved make heavy duty 6" x 2" sections for the top & bottom rails and 2" x 2" sections for the vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the framing. Rate shall include necessary etching film / 1060, and any necessary hardware items. (Heavy Duty 6" & 2" thick frames(14 Guage) - approved make).						
-	DOORS	-					
_	ENTRANCE DOORS - IN ALLUMINIUM POWDER COATED SECTIONS (HEAVY DUTY-14 GUAGE) , BANKING				2. Auguste		
	HALL - FULLY GLAZED (12MM THK GLASS)	SFT	46.00				
1	Providing and fixing fully glazed alluminium (heavy duty-14 guage) doors at the main entrance as shown in the drg. Door shall consist of approved make heavy duty-14 guage sections 6" x 2" for top & bottom rails, 2" X 2" for vertical styles. 10mm thk. approved make clear float glass shall be provided and fixed in the traming. Rate shall include necessary etching film / Logo, Pad Lock (GODREJ MAKE), 1 pair of 12" long S. S. Handles (Curved shape , C Shape in Elevation), floor springs (MAKE EVERITE / GOLDEN /HARDWIN //EVEREST MAKE), gaskets & any other necessary hardware items.						
1	PARTLY GLAZED/ SOLID FLUSH DOOR (Without door frame) FINISHED ON BOTH SIDES/ ONE SIDE WITH	-					
t s f n	providing and fixing in position 35mm thick solid core flush door shutters conforming to IS 2202 with/ without(as per design) 6mm thick plain Clear Glass(vision panel) finished with frosting film of approved nake as per design and pattern. The shutter is to be finished with 1.0mm thk laminate of approved shade and make on both the sides. All edges should be finished with Second Class Teak Wood lipping (minimum hickness 12 mm) with three or more coats of melamine polish. The glass shall be fixed with the flush door hutter by using suitable beading from both sides made out of second class teak wood. Rate shall include he cost of all approved quality hardwares required like nails, screws, handles, lock, heavy duty hinges, door toppers etc. in case of veneer partition, the rate shall be inclusive of melamine polish of 2-3 coats or urther as per the satisfiction of the architect/ engineer incharge, so as to achive a glossy finish without any narks on the surface. Item to be completed in all respects as per drawings & instructions from EIC Architect.						
hiv	enfronsparentets Enginees	CIT	100.00				
	Architects Enginees	SFI	128,00	10000	2		



3	4'-0" high wicked door COUNTERS	SFT	10.00		
1			40.00		
	LINEAR WORK STATIONS (RUNNING COUNTER)-1050 MM WIDTH (WITH CUSTOMER LEDGE)	0.57			
	Flowling and fixing a Clerical Desk/ Linear Work Station and the	RFT	18		
		1200			
		11-2-1			
	and the capie as per design. All the inner curraces shall be that he had	SRN .			
		1.12		1	
		616 J	10.0		
		1.0	A State of the		
	I have a second the condition of the counter should be finished with a second		- 2		
	and other external surfaces to be finished in 1.0 mm Thk Laminata laund finitial		100		
	I set that out of 1911111 the plywood as per the design or as directed built		a la la		
i	the international of the inclusive of all peressant approved fittings the				
-	CONTEX 1050 mm x 1950 mm, with partitions Rear Door etc. all complete	NOS	2		
	Providing and fixing Cash Counter in Laminate finish of clear internal dimension 5'-6" X 6'-6" all complete				
	Biological partition in 12 mm trik itched glass as per design in front including room down for the second		1.4.1		
	The councer shall be provided with a table top of 7'6" doop of 1 1/31 411				
	The counter shall comprises of a Motal key based T				
	Trolley, Wire Manager etc. A drawer unit comprising of three drawer set shall be fixed with the counter or as directed by the architect. The drawer with the line of the line				
	and a standard and the drawer unit shall have a central locking arrangement and the				
	Board indice, nates shall be inclusive of all hardware fittings like locks handles https://	1			
	channel etc as required. A foot rest made out of 19mm thk plywood as per the design or as directed by the				
3	architect shall also be provide below the counter. provision should be made on side by providing a niche of size 6" x 6" on sides of counter for boucher procise NOTE. Deale the made on side by providing a niche of	1			
	size 6" x 6" on side of counter for boucher passing. <u>NOTE- Rates shall be inclusive of all semi ht semi</u> glazed partition of maximum height 6'-0" from FFL on sides and back and no claim of partition in cash	1	1.1.1		
	cabin will be entertained extra. i)Working top made with 25mm thick plywood finished with 1mm thick	9			
	laminate. Outside edge of the working top shall be provided with 1%"X1" Teak Wood moulding finished		1.5		
	The second				
	of a solid partition over working top and fixed with a ledge(transaction tex)			-	
	pry wood and next ply and finished with 6mm the Corian of approved shade and make O2L CIL 6				
	(wintor Polished) rounded and taken below as apron with peressan groowing for this lists				
- 1	design the ledge should be such that it is projecting 4" inside the counte and 8" outside the source of				
. 1	Tourided and taken down to 2-6" above Finished floor level on customer side v) A gap of A"should be left		and the second second	. 1	
	above the transaction top (all along the width of the teller counter) vi)Glazed partition baving bailet 41 of		1.1.1		
1	above the transaction top (in facia) and also above 4" clear gap shall be provided with 12 mm thisle at				
1	increase as per unawing. The edges of cut out and the top edge of glass are to be mirror poliched and the	1.1	22 1 2		
- 1	Service to partition as per fixing details and to boxing with concealed S. S. finished (D' herelisted				
	in the drawing, vii)FOLL Glazed (IN FRONT, SIDES AND BACK till 6'-0" [v] from ground lovel) partition		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
1	browded with 12mm thick glass (itched) above the slit to be fixed to partition as per fixing dotails and the				
ľ	boxing with concealed S. S. finished 'D' brackets as shown in the drawing The exposed adapt shall be		and the second		
1	missied in mirror polisn.ix) relescopic CPU Stand/ ready made Keyboard tray shall be provided of another in				
	under and make x1 contrest made with T W/ member of size All X4 1/ // 5 1 1		a hale		
	(i) Drawer units as per drawing shall be provided and each drawer should have vertical partitions for complex the summer and the second sec				
ľ	seeping the currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with				
1	Imm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be				
F	provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant /				
E	Bank.xii) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall				
	a provided below the table to find the first shall				
1	be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone				
V	vire conduiting. The item to include all necessary hardware and fittings in Stainless Steel finish,.				
M	lecessary beadings with matching melamine polish for fixing the glass are to be provided as per				
	rawing/ as directed Rates shall also be inclusive of Demonstration of Demo				
N	Irawing/ as directed.Rates shall also be inclusive of Doors with Godrej Night Latch for Cash counters Iote- Since no partition is to be executed on one side of the Cash Counter sharing the existing Brick		1.1		
	Hell to be the the to be the tote of the side of the Cash Counter sharing the existing Brick				
1	Vall, it should be done with full ht panelling and the rate quoted for the cash counter shall be inclusive				
0	f the same. If panelling is not done on the same wall inside the Cash Counter then necessary deduction				
	hall be made for that area as per the quoted rate of panleiing works.	1			
S	TORAGES				
-				-	1000
L	OW HT RUNNING STORAGE (1'-6"DX2'-6"HT) (BACK CADENZA)	SFT	96		



11	Providing and laying low ht Storage unit of sizes as mentioned above. They shall consist of 3/4" thk plywood for top, base and sides and base 1/4" thk marine plywood, 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & PVC lipping matching with the approved shade of laminate on all the edges. All external surfaces shall be finished with 1.0mm thk laminate of approved shade and make. Divisions of the shutter shall be make equally according to the length of the storage. A 3/4" thk fixed ply wood shelf on battens shall be provided @16" intervals from the base. Suitable wooden moulding (as per Architects design) with mellamine polish shall be provided to the edges of the storage top. All inner surfaces including shutters shall be finished with natural french polish. Rates shall be inclusive of all necessary approved fittings like hinges(haffle make), locks, 3" long brushed finish handle, tower bolts and any other misc hardware items of approved make SHUTTER BOXING Providing and Fixing Shutter Boxing with 19mm thk Marine Ply and Finished with Aluminium Composite Panel. The boxing of shutter should be made opennable type for periodic maintainance. Note the mode of measurement would be the multiplication of the length and the height of the boxing OVER HEAD STORAGE IN SERVER ROOM	SFT	76		
	Providing and fixing over-head storages which consists of 3/4" thk plywood shutter with self closing hinges of haffle make(full ovel open) & t.w lipping matching with approved laminate on all the edges. They shall consist of 3/4" thk plywood top, sides and bottom and 1/4" thk marine plywood back. A 3/4" thk ply wood palmet shall be provided below the storage to house the tube light. All the external surfaces shall be finished with 1.0mm thk laminate of approved shade. Divisions of shuttershall be made equally in accordance to the length of the storage. All internal surfaces shall be finished with french polish including the shutter. Rate shall be inclusive of all necessary hardware fittings of approved make like- hinges, locks, towerbolts, handles etc.Note- the pelmet for tubelights will not be considered as seperate item on in the measurement				
iv	FULL HT. STORAGE Providing and fixing storage units of full height as per drwng. They shall consist of 18mm thk.comm. ply top, sides,back, bottom, shelves and shutters. The bottom of the storages shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The shutter with box type higes of approved make & steam beach lipping finished with melamine with approved laminate on all the shutter edges. Division of the shutters shall be made equally according to the length of the storages (as approved by Bank/ architect). All the external surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make. 18mm thk. Comm. Ply shelves removable type supported on side steam beach wood battens on both sides at 16" interval (approximately / divided equally) shall be provided. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, 150mm long SS brushed finish handles,tower bolts, locks and any necessary hardware items. The top ply edge should be fitted with 19mm x 7mm size steam beach moulding finished with melamine.	SFT	112.00		
	TOTAL OF PART-A (I) : DOOR, PARTITION, COUNTERS, STORAGE, FALSE CEILING				
3	PART-B (I) : TABLE, WORKSTATIONS, CHAIR & SOFA				
	TABLES & WORK STATIONS				
-	OFFICER'S TABLE (2'3" x 4'-6" x 2'-6" ht) Providing and fixing a desk of overall size of top as mentioned. It shall consist of 3/4" thk plywood top as per design(double edge on the front and the back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk plywood verticals. Suitable (as per architect's design) wooden moulding with				
	mellamine polish shall be provided to the edges of the top. A 3/4" thk plywood apron shall be provided as per architect's design with necessary pattern. The table top shall be finished with 1.0 mm thk laminate of approved shade and all external surfaces to be finished with 1.0mm thk laminate of approved shade. Each top shall be provided with a pedestal (set of three drawers with central locking system either movable or fixed to the table), 1.no metal computer key board tray as per architect's design fixed with telescopic /double (haffle/albihari/solo make) sliders, a 3" dia PVC wire manager of approved quality near the CPU/Monitor position as shown in the drg. 1 no Metal CPU Trolley to be provided below the desk as shown in the drg and a foot rest made out of 19mm thk plywood as per the design or as directed by the architect shall also be provide below the counter. All the inner surfaces shall be finished with Laminate finish of approved shade. Rates shall be inclusive of all necessary approved fittings like locks(godrej/vijayan ventionsArchitectsEnginees .				
		and # Elean	तेक IND 14 A	OFFICE # NNYS	

ii	CLERICAL TABLE (2'0" x 4'-0" x 2'-6" ht)	-			
	Specifications same as above but of overall size as mentioned here	NOS			
iii	MANAGER'S TABLE(2'-6" X 6'-0" X 2'-6") WITH 6MM THK CLEAR GLASS WITH POLISHED EDGES ON				
	rioviding and fixing a desk of overall size of top as mentioned the hell and the hell	NOS	1		
			100 000		
		1.5			138.25
			A. Baile	1.1	
			1.1		
			100.00		an Near
	provided which a pedesial (set of infee drawers with control leading and	1000			
	fixed to the table), 1.no metal computer key board tray as per architect's design fixed with telescopic /double (haffle/albihari/solo make) sliders ,a 3" dia PVC wire manager of approved quality near the CPU/Monitor position as shown in the attempt of the solution of				
	Provident of position as shown in the drg. 1 no Metal CPU Trollow to be president in the		18		
	and a root rest made out of 19mm the plywood as par the data	1.00		1.6	
		1.1			
	makel for drawers and any misc, hardware items			1.00	
iv	SUB-STAFF TABLE- 1050MM X 500MM				and a second
	Providing and laying a Plain Table for Sub-Staff with a Pencil Drawers for over all size of top as mentioned	NOS	1		
	the share consist of 3/4 tilk. Comm, PIV top as per design (double adda as the fact the start of				
	the Comm Pluvertical at a still	12	1.1	10.00	
	Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the edge of the top. The top of the counter should be finite during a share of the state of the sta	-21-51		12.11	
	top. The top of the counter should be finished with 1.0mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish) of approved make.	1.12	1		
	approved make.				
v	SIDE CADENZA				
				1.1.1.1.1	21.1 Sec.
	Providing and laying side cadenza of above sizes and as mentioned in the drawing. It shall consist of 3/4" thk		1.1		
	1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1				
	are integer s design/wooden moulding with melamine finish A pair of 3//" wood shutters will be		1.00		
	which will slide on 1" x1" wooden battens above skirting. 1"a3/8" deep vertical depression shall be made on each shutters to act as handle as shown in the drawing. All external surfaces should be finished in	1	1	1	
	A 3/4" the fixed ply wood shalf an better a shall an	1		1.1	
	provided at 10 intervals from the base. Rates shall be inclusive of necessary approved fittings like all discussions and the state of t	-			
	is and any other misc. hardware items		1	1.2.1	
(a)	SIZE - 1050MM X 400MM X 750MM (For BM only)	NOS	1		
(b) vi	SIZE - 975MM X 400MM X 750MM	NOS			
VI	BACK OFFICE RUNNING COUNTER FOR SUB-STAFF/ SERVER ROOM	RFT	5		Contract of
					2
	Providing and laying wall mounted Plain Table for Substaff with a Pencil Drawers for over all size of top as			1.00	
	mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the former of	1			
	back with 1 1/2" thk half round moulding on the edges) supported on X" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the				
	edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external	1	100		
	surfaces to be minished in 1.0 mm. Ink. Laminate (suede finish) of approved make				
vii	WALL MOUNTED WRITING TABLE 0'-10" TO 1'- 0" WIDE(In Branch and ATM 4' + 2'	RFT	6		
	Providing and Fixing wall mounted writing ledge as per design. The top shall be made of 19 mm thk	in i	0		144 S 1
1.1	prywood fixed with fiext ply to achieve curved surfaces on either sides as per design and fixed with Grow the				
	contail, mintor polished, or approved shade and make. The ledge shall be provided with 10" high phased			100	
	selves with necessary partitions in between made out of 19mm thk plywood and finished with laminate of approved shade. ledge should be supported on 19mm thick comm. ply on rear side for fixing to the wall.				
	The bottom ply piece to be supported additionally with 2 Nos. of SS Brackets.				
	450MM WIDE CASH SORTING TABLE	RFT	4.24		
	Providing and laying a Plain Running Table for Cash Sorting, with a Pencil Drawers for over all size of top as	in i	4.24		
	mentioned above. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and				
	back with 1 1/2" thk half round moulding on the edges) supported on X" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with mellamine shall be provided to the				
	edge of the top. The top of the counter should be finished with 1.0mm Laminate and all other external				
	surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish)of approved make.				
	TOTAL OF PART - B (I) : TABLE, WORKSTATIONS, CHAIR & SOFA				
	PART-D (REVENUE) : BLINDS, SUGGESTION BOX, FROSTED FILIMS,				
	MIPPOP COLUMN DANELLING A CONTRACT OF A CONT			States Int	
	MIRROR, COLUMN PANELLING, ACRYLIC FRAMES PANELLING ON COLUMNS/WALLS/DOORS WITH/ WITHOUT FRAMING				
	N PLYWOOD FINISHED WITH LAMINATE FINISH				
		SFT			

Archiventions- Architects Enginees

IND ARU

0	Supplying and Fixing VERTICAL BLINDS Vista/Mac/Parytex make. Blinds made using 100% polyester with acrylic polymer coating, of the shade and colour as approved by the Arcitect/ Bank fficial(only for external	SFT	112.00		
6	VERTICAL BLINDS				
	Supplying, fabricating and installation of Bank's Logo made of coloured acrylic sheet 5-6mm thk in box section, and as per the sizes as mentioned in the detailed drawings. This Coloured Acrylic sheet box logo should be fixed with light from inside so as to have a back lit, as per the direction of the architect.	NOS			
5	COLOURED ACRYLIC SHEET LOGO FOR THE BANK, (BACK LIT) OVERALL SIZE 450MM X 450 MM-	NOC			
	Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made of 19mm thick phenol formaldehyde bonded plyboard and the curved portion at top made out of 90 mm x 90 mm C.P teak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick phenol formaldehyde bonded block board is to be provided at 1.50 mm above finished floor level. All the exposed timber surfaces including all free edges are to be finished with 1 mm thick laminate sheet of combination shade .Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamal paint of approved shade and quality over a coat of approved primer.Rate to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved designand quality.				
4	CHEQUE DROP BOX	NOS	1		
	Supplying and erecting free-standing complain box of overall size 300 mm long x 200 mm deep x 450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete with hardware fittings and fixtures of approved make and quality. Top and all exposed surfaces of block board are to be finished with 1.00 mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with minimum two coats of synthetic enamal paint of approved shade and quality over a coat of approved primer.				
3	COMPLAIN BOX & SUGGESTION BOX Supplying and erecting free-standing complain how of a sub-	NOS	1	-	
	Providing and fixing notice board size as required/ directed (matching with the panel of the cabin) with openable shutter on the front. Made out of 19mm thick Steam beech veneered block board frame and outer frame in 2 1/2" x 1 1/2" Steam beech wood section, concealed hinges, locking arrangement, and glass of (5.5mm thick) with rear panel of SITATEX board, covered with fabric of approved shade. (Basic rate Rs.100/-per mtr, 48" width), fixed to back ply 6mm thick. All complete including melamine polish in stain of required shade. All complete as per approval of the Architect / employer				
2	NOTICE BOARD Providing and fixing notice board size as seguined (direct b)	SFT	12		
	Note- Panelling should be done till 4'-0" height at places as directed by the architect	-			
	Providing and fixing panelling on walls/ columns with or without framing as per the directions of the architect. Framing if required and provided, shall consists of aluminium sections 50mm x 40mm(wall thickness 2mm) @ 2'-0" c/c both ways horizontally and vertically on the wall. The framing would be covered with 1/4" thk plywood finished in approved shade of laminate of thickness 1.0mm. Wooden moulding, lipping etc as directed by the architect shall be provided wherever required. The panelling should be done in such a way that it can house the sliding folding partition when fully opened and remain in flush with the panelling	1			



Archiventions- Architects Enginees

ESTIMATED BOQ FOR ELECTRICAL WORKS FOR DERGAON BRANCH WITH ONSITE				
CLIENT NAME- INDIAN BANK, DIBRUGARH ZONAL OFFICE	ATM			
WORK TYPE- ELECTRICAL WORKS		Carlo an		
LILOTHICAL WORKS				
SENERAL NOTE			1	
		1940	-	
UPS input and Output wiring should be done with FRLS Insulated stranded copper conductor All wires for circuit wiring and other wiring should be drawn inside M.S. Conduits Only and	or laid th	rough	M.S Condu	ict. (From
All wires for circuit wiring and other wiring should be drawn inside M. S. Conduits Only unle Specifications of all wires should be followed strictly as mentioned in the BOQ	ess other	wise s	pecified	
All makes of materials should be strictly followed scrictly as mentioned in the BOQ				1997
All makes of materials should be strictly followed as mentioned in the BOQ Earthing Test Certificate should be provided alongwith the Final bill for further bill verification Single Line diagram showing the all the unities in the line of the strictly as mentioned in the BOQ	s of the	Tender	document	
Single Line diagram showing the all the wiring including point with	on			
Single Line diagram showing the all the wiring including point wiring, computer and RAW po Only DATA and Voice point wiring is allowed to be carried out through PVC Conduits	wer wiri	ng, Cir	cuit wiring	etc. all
ART A: ELECTRICAL WIRING, CABLING, DATA & TELEPHONE WIRING				
. No [Description				
S.I.T.C. of Factory ManufacturedSingle/ 3 Phase & Neutral Double Door Distribution board	Unit	Qty	Rate	Amount
induce out of 10 Swd sneet steel enclosure with cutouts for operating MCD /MCD / MCD	No.	1		
throws a consisting of Flidse, Neutral & Earth Bushars with tannad halas also		118	1	1.0
covers with removable plates on Top & bottom for Incoming & Outgoing Cables . D.B.'s shall be flush mounting time for both right and the state of th			1.	
three phase.				
S.I.T.C. of 3 phase & N 4 way Double Door Vertical Distribution Board with following	-		1.1.1	
The stype c, osamp w.c.b. as incomer - 1 no s	-	1	12.00	S. Carton
SP, Type C, 25 Amp M.C.B -1 no. For RAW POWER DB INPUT (Water Dispenser & Markile	-			
Charger Loau)		1	1.1.1	
SP,Type C, 25 Amp M.C.B - 2 no. For LIGHT DB & RAW POWER DB INPUT	-	100		
SP, Type C, 25 Amp M.C.B-1 no. For U.P.S. Incomer (3-4 KVA UPS WILL BE USED)	-	100	C. Test	
1.1. 22 All WICB -1 No. For Inverter Input				
S.P. 16 Amp MCB - 2 Nos For AC	-	1 1		
S.P. 20 Amp MCB - 2 no.s For AC	-			
Blanking Plates - 2 nos.			1.27	-
Note- Rates Shall be inclusive of S.I.T.C. of 4 X16 Sq.mm. F.R.L.S. Copper Flexible wires with 2				14-1
X 10 Sqmm Copper Earth Wires in Rigid PVC conduit from 100 A MCCB in Metal Box (Metering	L			
Cabinet) at the output of Br. Meter to Main DB through MAIN SWITCH				
Supply and fixing of following MCCB Unt with MCCB in sheet steel enclosure on M.S. angle	No.	1		1000
frame / M.S. legs on wall complete with interconnection, mending good damages to original				1.00
finish, painting, etc. as required.	13.0			and the second
a)63A 4P 16KA MCCB	-			
MCB DISTRIBUTION BOARD	-			1
Supplying, installation, testing and commissioning of surface/recess mounting, 220/415 volts	-	+ +		
prewred MCB distribution boards with all switchgears as specified below of sheet stool duct	1.00			
protected, duly phosphatized and powder painted, inclusive of 200 amos tipped uniformly				
rated electrolytic copper bus-bar, common neutral link, earth bar, din bar for mounting	1			
MCB/MCCB/RCCBs detachable gland/knock out plates and with built in loose wire box, and	1			
superior make terminal connectors for all incoming and outgoings circuits, duly prewired with				
adequate size of FR PVC insulated copper conductor upto the terminal connector/neutral link	1000			
and ready for installation as specified below:				
				and the same
S.I.T.C. Of L.D.B. [MCBDBL] (LIGHT DB)				
Light DB- S & I of 6 Way SPN, DB for distribution to all Light points of different areas (as	No.	1	C. Salar	
indicated in the circuit diagram), having below mentioned switchgears (Earth bar inside these	1			
DB should be insulated from the body) - 1 no 25A(30mA) DP RCCB as incomer, 4 nos 6A SP MCB as outgoing				
LIVICE as outgoing				
Note- Rates Shall be inclusive of S.I.T.C. of 3X 2.5 Sq.mm. F.R.L.S. copper flexible wires in 19/20 mm. Medium Guage PVC conduit from Main D.B To L.D.B				
S.I.T.C. Of P.D.B. [MCBDB-POWER] (Raw Power DB)				1 in case

E



	SITC of Single Di				
	S.I.T.C. of Single Phase 6 way Double door D.B. with Incomer. Double pole 100 Milliamp & 4 Amp R.C.C.B 1 No .	IN NO	11	1	
		110.	1		
	10 Amp S.P. Amp M.C.B 3 No and				
	10 A/16 A MCB- 1 Nos Spare (One MCB for Branch Sign Board).				
	with all wiring connections. (Max, 2 work-Station Points to be looped as a store of			1000	
-		1.0			
	Note- Rates Shall be inclusive of S.I.T.C. of 3 X 4 Sq.mm. F.R.L.S. Copper Flexible wires in Rigid		-		
-	The second	- 2.5		12.201	
С	U.P.S. D.B. : (Output) [MCBDB-UPS/1]	-	-		
	S.I.T.C. of Single Phase 6 way Double door D.B. with Incomer. Double pole 63 Milliamp & 40	No	1		
	1	110.	1		
	10 Amp S.P. Amp M.C.B 3 No and			1	100
	10 A/16 A MCB- 1 Nos Spare (One MCB for Branch Sign Board).			123.5	12
	with all wiring connections. (Max. 2 work-Station Points to be learned as an attest			12.	
1	excentional case)				100
	Note- Rates Shall be inclusive of S.I.T.C. of 3 X 4 Sq.mm. F.R.L.S. Copper Flexible wires in Rigid		-	1	
d	The second of th			1.00	
u	Shire of ACDB [IVICBDB- AC]		-	-	
	Supply Installation Testing and Commissioning of Three Phase 4 way Double door Distribution	No.	1		-
	contra with an winnig connections.		-		
	Incomer : - 40A FP RCCB (100mA) : - 1 No.				
	Outgoing : - 6A SP MCB : - 18 Nos.				
	Note- Rates Shall be inclusive of S.I.T.C. of 4 x 6.0mm2 + 2x4.0 mm2 F.R.L.S. copper flexible		-		
2	wires in 19/20 mm. Medium Guage PVC conduit from Main Panel To Lighting DB				
-					-
	4 Pole 63 Amp Manual Changeover Switch For Mains to D.G. supply switching (If D.G. Back-up is provided)	No.	1		
			-		-
	Note- Rates Shall be inclusive of S.I.T.C. of 4 X16 Sq.mm. F.R.L.S. Copper Flexible wires with 2	1000		1. 1. 1. 1. 1.	
	X 10 Sqmm Copper Earth Wires in Rigid PVC conduit from DB to the Changeover switch				1.
	S.I.T.C of UPS Input and Out Put Point as under-				
	40A FP MCB with IP 45 Enclosure (For UPS input & output, for 2 Nos UPS)	No.	4		
	Note-Rates Shall be inclusive of SITC of 4x 60/40				
	Note- Rates Shall be inclusive of S.I.T.C. of 4 x 6.0/10sqmm+ 2x4.0 sqmm F.R.L.S. copper flexible wires in 19/20 mm. Medium Guage PVC conduit				
5	UPS Input and Output for 1 Set of UPS , involving 40A DP MCB, including all required wiring all				Sec. 20.
	complet	Set	2		
	POINT WIRING				
.1					
-	Supply & Installation of concealed point wiring using 3 x 1.5 sqmm stranded FRLS copper				
	conductor in <u>M.S Conduit</u> including the cost of circuit wiring from the relevant DB's with 3x 1.5				
	is finite stranded FRLS copper conductor in M.S Conduit PIN GRIP lugs should be used for				11.0
	connection, terminations at both the ends with proper colour coding of phase neutral and				
	earth wire (Phase R,Y,B Neutral-Black & Earth - Green Colour) The rate shall also include	C. Pro			
	concealed M.S Box, Cover Plate and Switches of grid plate type switches and sockats of				
	approved shade and make as approved by Bank / Architect, Each circuit should not have mare	1.4			
	than 8 points / 800 W in one loop as per the following configuration.	E Y			
(:)					
(i)	Primary light points including the cost of 6A switch	Pts	18		1
)	Primary light points including the cost of 6A switch in UPS Power	Pts	6		
	Secondary light points looped from the above point - a(i)	Pts	7		
-	6A plug point as primary point. [SO]	Pts	2		
-	Secondary 6A Plug point on switch board. [SO]	Pts	2		
-	16A Plug Point directly taken from DB for hotplate/gevser / zerov / fridge [p]	Pts	2	1.2.1.1.1.1	
	It xhaust fan/ Wall Fan point consisting of 6A cocket need for a line with the	Pts	2	1.1.1.1.1.1	
	Ceiling fan point with electronic regulator (2 module step, 100 watt (min.)	Dta		Sec. 1	
	Wiring for Signages with 2R v2 5 Some and 1 Bu 1 F Come Duck	Pts	7		
	flexible cable to be connected to the SPN D/D consumer along with a Timer and Contactor unit	Set	2		A CAR
	installed in Electrical Room room				
	S.I.T.C. of call bell with bell point				
2	COMPUTER/ RAW POWER WIRING	Nos.	1		
	UND/AL				

जगव

BRUGARH

101× ×

T OFFICE A

	Note- All sockets should be placed below the workstations as mentioned in the drawings but the controlling switch should fixed above the work stations				
	the controlling switch should fixed above the work stations as mentioned in the drawings but architect				-
	architect				1
а	Supply & Installation of concealed UPS or stabilized power plug points on workstations / table				
	for computers using 3 x 1.5 some strends of 50 and 50	Pts	10		
	I set of the west of the set of t			1.1	
	the ends with proper colour coding of phase, neutral and earth wire (Phase R,Y,B Neutral-Black	1			
	& Earth - Green Colour) Each point shall				
	Contraction of the state of the				1.11.1
	the concerner for the point Switches and sectors in the			1.0	1.1
	Comy 2 codes served by one circuit from LIDC DD / Mat man at	1000		1 1 1	
	Per loop cost is inclusive of necessary cutting the well.			12.5	
	the wires through M.S Conduit and againg finishing the walls with Putty/ Cement/ POP to				1.1.1
	receive the final paint [SOC] 2 Nos in ATM	1			
-				1.00	
	S & I of points similar to above but to be used as raw power point on the tables consisting of one 6/16A socket with switch of other colors	Pts	10		
	a state of the second of the second s	Pts	10		
	The second of th				
	and through walls/ partitions inside M.S. Conduits as raceways are not provided. Cost is	100		-	
	inclusive of necessary outting the well	1.5			
	inclusive of necessary cutting the walls and including M.S. Conduits as required for taking the wires 2 Nos in ATM	1		1	
	1 Nos of 6A sockets/SWITCH with one No of CA	1			
	1 Nos of 6A sockets/SWITCH with one No. of 6A switch UPS Power/Raw Power ON CASH COUNTER	Pts	2		
5	1 No of 6A/16A switch sockets 6pin. Raw Power/Raw power FOR PRINTERS/ XEROX & OTHER UTILITIES,	Pts	2		
	EARTHING (1 NO FOR RAW POWER AND 1 NO FOR UPS POWER SUPPLY)		_		
	Earthing with copper earth plate 600 mm x 600mm x 3 mm thick including accessories, and		-		
	providing masonary enclosure with cover plate having locking arrangement and watering pipe	Each	1		
	etc. with charcoal or cake and acht			1	
	and could of cone and sall complete as required (for papels served bit)				
	of stern the rate shall be inclusive of necessary 8 SWG dia conner wire on surface or in such				
	Note- Test Certificate for Earthing Shall be submitted with final bill for processing of final bill for payment		1		
	to payment				
-	WIRING FOR DATA AND VOICE OUTLETS (Inclufing 2 Nos in ATM)				
	Supplying, laying and termination of 4 pair Copper solid, twisted pair G600 CAT6 cables				
	through specified dia PVC conduits / raceways. Cables must meet and exceed category 6/ class E				
	Standards requirements in ISO/IEC11801, CENELEC EN50173 & TIA 568-B2-1 and providing 8			1	
	commuting with N-45 (Krone make) with face plates / 1/O Ports in suitable machine / Archan				
	from server / EPABX room to individual work stations and terminating other end with RJ-45		1		1
	connector including numbering with forula. Note Date Date to the automating other end with RJ-45				
	connector including numbering with ferule. Note- Rates shall be all inclusive as mentioned in				
	the description above and the payment for the same item shall be made on the number of				
	points provided based on the above description				
	RJ-45 for data points (THROUGH False ceiling and wall)				
	5' Long Patch chord with crimping on both ends	points	10		-
	Network Rack Mount Recessed Frame for DATA Terminations including Cat 6 Jack Panel for 12	Nos.	10		
	DATA Points	VO.	1		
	A.C. POINT WIRING(Including 1 no in ATM)	-			-
	20A AC Points consisting of 16A socket near the AC and Switch on Switch Board with 3 x 6 sqmm N				
	stranded FRLS copper conductor in M.S Conduit . Rates Shall be inclusive of S.I.T.C. of 4 x	los.	5		
	6.0mm2 + 2x4.0 mm2 E.B.L.S. compara flavible in the tables shall be inclusive of S.I.T.C. of 4 x				1.0
	6.0mm2 + 2x4.0 mm2 F.R.L.S. copper flexible wires in 19/20 mm. Medium Guage MS conduit from ACDB till the socket				a sector
	TOTAL OF PART A: ELECTRICAL WIRING, CABLING, DATA & TELEPHONE WIRING				
	CABLING, DATA & TELEPHONE WIRING				
T	B: ELECTRICAL FITTINGS & FIXTURES				
-					
-	LIGHTING FIXTURES (Bajaj or equivalent)				
	S & I of lighting fixtures as per the details given below including necessary hardware such as				
	clamps, nuts, bolts, nails, screws and suspension chains as required for fixing the fixtures in	100			and the second
-	position as directed by architect / Consultant.				



	PANEL LIGHT - MAGIK VISION PRO Ultra Slim and Light weight2' X 2' (recess / Surface) Panel Light, Wattage-36W, 6500 K. Product Code, PCVPD25C2010, 1250000, 1250000, 125000000000000000000000000000000000000	I Fach	-	
1	from CENTURY LED LTD. or Phillips, Havells, Bajaj as approved by the Engineer-incharge/	Each	14	
b	DOWN LIGHT TYPE 1 - MAGIK HELIO PLUS Slim Panel Round light, having Product Code- PCHP018N0966, Wattage-18W, CCT- 4000 K, MAGIK Lighting from CENTURY LED LTD. or Phillips, Havells, Bajaj as approved by the Engineer-incharge/ Architect	Each	5	-
с	DOWN LIGHT TYPE 2 - MAGIK HELIO PLUS Slim Panel Round light, having Product Code- PCHP015N0960, Wattage-18W, CCT- 4000 K, MAGIK Lighting from CENTURY LED LTD. or Phillips, Havells, Bajaj as approved by the Engineer-incharge/ Architect	Each		
C	1200 MM TUBE LIGHT MAGIK ULTIMA LINE LED BATTEN tubes, Glaze LED Batten, having Product Code- BWUA020W1295, Wattage-20W, CCT- 3000 K, MAGIK Lighting from CENTURY LED LTD. Or Phillips, Havells, Bajaj as approved by the Engineer-incharge/ Architect	Each	13	
4	600 MM TUBE LIGHT Product Code- BWUA012W1299 , Wattage-20W, CCT- 3000 K, MAGIK Lighting from CENTURY LED LTD. Or Phillips, Havells, Bajaj as approved by the Engineer-incharge/ Architect.	Each		
	Supply and fixing of 10" - 12" PVC exhaust fans with louvers.[EF]			
	Supplying including fitting fixing of following star rated A.C. Ceiling fan complete with all accessories like down rod, canopy etc. of following sweeps with making necessary connection cable, as approved by the Deptt.s etc. as required complete and as directed by the Department [Without regulator]. (ORIENT PSPO make / Usha make/ CROMPTON make/ATC/ V GAURD make)	EACH	2	
	a) 1200 mm sweep [F]			a ser a
	b) 600 mm sweep [F]		5	
	Supplying including fitting fixing of following star rated Plastic Blade, new 400-450 mm dia bracket/wall fan of Ivory Colour, complete with all accessories of following sweeps with making necessary connection cable, as approved by the Deptt.s etc. as required complete and as directed by the Department	EACH	2	
OTA	a) 400- 450 mm sweep	EACH	1	
UTAI	OF PART B: ELECTRICAL FITTINGS & FIXTURES			



