



PREMISES DEPARTMENT  
ZONAL OFFICE HAMIRPUR

**TENDER DOCUMENT  
INTERIOR FURNISHING WORK IN NEW PREMISES OF  
INDIAN BANK - ZONAL OFFICE, DISTRICT - BANDA**

**PART II - FINANCIAL BID**

Date : **17.02.2023**

Issued to:

.....  
.....  
.....

<b>Last date of submission of Bid</b>	<b>03/03/2023</b> upto 15:00 HRS at Indian Bank, Zonal Office, Premises Department, 10/379, Rameni Tarauns, Hamirpur - 210301
<b>Date of opening of Technical Bid</b>	<b>04/03/2023</b> at 16:00 HRS Indian Bank, Zonal Office, Premises Department, 10/379, Rameni Tarauns, Hamirpur - 210301
<b>Date of opening of Financial Bid</b>	To be intimated separately to the Firms Qualifying in Technical Bids

**CONSULTANT:**

M/s Mohit and Associates  
Architects, Interiors & Estimators,

**L-2/554-, Vineet Khand,  
Gomti Nagar, Lucknow-226010**

E-Mail: [mohitg.gupta2783@gmail.com](mailto:mohitg.gupta2783@gmail.com)

Mobile No: 742821765, 9582218092



**SCHEDULE OF QUANTITIES**

**INTERIOR FURNISHING WORK IN NEW PREMISES OF  
INDIAN BANK - ZONAL OFFICE , DISTRICT - BANDA**

S. NO	DESCRIPTION OF ITEM	UNIT	QTY	RATE (Rs.)	AMOUNT (Rs.)
<b>1.0</b>	<b>SUSPENDED FALSE CEILING</b>				
<b>1.1</b>	<b>FALSE CEILING ( GYPSUM BAORD)</b>				
	Providing and fixing Gypsum false ceiling as per drawing including of providing and fixing G.I. Frame work shall comprise of G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam to the required curvature with nylon sleeves and screws at not exceeding 610 mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc.	<b>Sq Ft</b>	<b>1500</b>		
	The joints to be properly mended with paper tapes and gypsum compound all complete. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification, approval of the bank. No Drop or design (if any) will be considered as extra measurement it will be considered flat ceiling. (Only plan area to be measured for payment) .No extra payment will be made for the cutting of light points, stain glass, cove lighting etc. The measurement will be taken in one level, rate should include the drops also, and no extra amount will be paid for the drops.				
<b>1.2</b>	<b>FALSE CEILING (ARMSTRONG CEILINGS - FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL)</b>				
	Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the	<b>Sq Ft</b>	<b>1628</b>		



	periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID(BLACK REVEAL) ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% , having Fire Performance CLASS 0 / CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete.(Branch & ATM).				
	<b>TOTAL OF SUSPENDED FALSE CEILING</b>				
<b>2</b>	<b>PARTITIONS WORK</b>				
<b>2.1</b>	<b>FULL / LOW HEIGHT SOLID PARTITION</b>	<b>Sq Ft</b>	<b>280</b>		
	Full ht. Solid Partition including flush door & strong room partition up to 7' only WITH LOUVRE :- Providing and fixing solid partition, the framing shall made out of aluminum hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL as internal frame structure placed horizontally & vertically at max distance of 2'-0" x 2'-0" center to center. Fixing 6 mm thick commercial ply on both sides with 1.0mm thick laminate on top of approved shade with groove pattern as per instructions of Architect. The rate shall include the cost of providing skirting of 100mm wide lined with 1mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1mm thk laminate complete. Laminate Should be considered up to two or three color combination. The edge beadings with steam beach wood should be finished with melamine polish if required, frame work above false ceiling done shall not be measured but contractor may factor it while quoting their rates as measurement up to false ceiling lvl.				
	The rate inclusive of providing & fixing of required flush door of 37mm thick approx. with 1.0mm th. laminate both side with steem beech wood chowkhat of size 75mm x 65mm approx and Item includes Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) with screws etc. The shade of laminate finish to be got approved from Bank. . All as per the design and instructions Bank.				
	<b>Note:</b> - For the purpose of payment partition shall be measured including the area of door/door frames up to false ceiling height.				
	Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2'-0" c/c with dash fasteners.				
<b>2.3</b>	<b>Full height Glazed partition Manager cabin</b>	<b>Sq Ft</b>	<b>605</b>		
	Same as of Solid ht. partition, providing 8mm thick Modi/saint Gobin float glass above 1'-0" / 3'-0" & up to 7'-0" fixed with steam beech wood beading of finished size 1 1/2" X 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant, joint shall be located strictly as shown in the drawing. All exposed woodwork to be mealamine polished. Item includes frosted/striped/designer glass film of 3m, Avery Dennison or				

	equivalent (basic rate of Film Rs. 50/ Sq ft) on existing glass as per manufacturer's specifications. All as per the design and instruction Bank.				
<b>2.5</b>	<b>Low. Height Semi Glazed Partition</b>	<b>Sq Ft</b>	<b>235</b>		
	Same as above but of Low height as per design including 10mm Toughened glass with edges polished to be used. All other specs are same as of above, Edges of the partition to be covered with 3" X 1.5" Steam beech wood duly melmine polished moulding. 38mm thick flush door: wicket gate also shall be included for a measurement. All as per the design and instruction bank.				
	<b>TOTAL OF PARTITIONS WORK</b>				
<b>3</b>	<b>DOOR &amp; ACCESSORIES</b>				
<b>3.1</b>	<b>Main Entrance Door PT Door</b>	<b>Sq Ft</b>	<b>140</b>		
	Providing and fixing toughened glass door shutters of 12mm thickness in opening of glazed partitions with stainless steel patch fittings of approved make (DORMA / OZONE / HETTICH/GEZE/DLINE or approved equivalent) including heavy duty double action floor-spring with steel cover plate of approved make, pull handle SS brushed finishes 24" long thick 25mm on both sides of door shutters, locking arrangement of Dorma / D Line or equivalent or better quality as approved by Engineer-in-charge. Exposed edges of glass shall be machine cut & polished. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing floor spring and patch fittings. All complete as per approval of the Architect.				
<b>3.2</b>	<b>Main Entrance Fixed PT Glazing</b>	<b>Sq Ft</b>	<b>180</b>		
	Providing and fixing toughened glass partition of 12mm thickness with stainless steel patch fittings of approved make ( DORMA/ OZONE / HETTICH /DLINE / GEZE or approved equivalent as approved by Engineer-in-charge. Exposed edges of glass shall be machine cut & polished. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing patch fittings. All complete as per approval of the Architect.				
3.3	Supplying and fixing of Dorma/GEZE Dline / Hardwyn/Godrej or approved equivalent Door Closer for wooden door for Branch manager, Banking hall, Chief Cashier, Dinning, UPS, Toilet	<b>Nos</b>	<b>12</b>		
3.4	Supplying and fixing of mortice door lock of hardwyn make HML-480 Lock Body 304 Stainless Stell. (In BM Cabin, Store room 0. Cash cabin shall be Godrej Night latch. (atm 1 No.)	<b>Nos</b>	<b>3</b>		
3.5	Supplying and fixing of door stopper SS Grade 304, HESSF-2C hardwyn make.	<b>Nos</b>	<b>12</b>		
	<b>TOTAL OF DOOR &amp; ACCESSORIES</b>				
<b>4</b>	<b>WORKING COUNTER</b>				
<b>4.2</b>	<b>RUNNING COUNTER</b>	<b>Rft.</b>	<b>45</b>		
	Providing and fixing staff counter @ 2'-6" (750 mm) each respectively shall be made of 19mm thick ply wood and finished in 1 mm thick laminate. Working top having steam beech wood edging of size 1 ½" x 1". Vertical face shall have 19 mm thick commercial ply over pine wood framework as				



	per requirement of design. All exposed edges of ply wood sealed with Steam beech wood beading of size 1/4" x 3/4". All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade.				
	The item includes Chest of drawers (size 1'-4" x 2'-0" x 2'- 5") made of 19mm thick commercial ply wood having One drawers at top and a storage cabinet below having shutters of 19mm thick ply wood finished with 1.0mm thick Laminate on all sides. 1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L - brackets for securing to the table top for each seat. All beading and exposed wood shall be melamine polished and the Internal surfaces shall be .75 mm thick laminate. Item includes 1'-3" high 12mm thick toughened glass above upper tier and readymade metal powder coated CPU trolley, grommet, foot rest for each seat. All complete as per approval and instructions of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement.				
	The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thk laminate complete.				
	<b>BACK OFFICE RUNNING COUNTER (2'-0" /2'-3" WIDE)</b>	<b>Rft.</b>	<b>8</b>		
	Providing and laying a Plain running counter with only key board and Pencil Drawers at every 4'-0" length for overall size of top as mentioned bellow. It shall consist of 3/4" thk. Comm. Ply top as per design (double edge on the front and back with 1 1/2" thk half round moulding on the edges) supported on 3/4" thk. Comm. Ply verticals at every 3' length. Suitable (as per Architects design) wooden moulding with melamine shall be provided to the edge of the top. The top of the counter should be finished with 1.5mm Laminate and all other external surfaces to be finished in 1.0 mm. Thk. Laminate (suede finish) of approved make.				
	1no. Computer key board tray (either readymade / made to the order as per architects design using 3/4" thk comm ply base and 1" x 2" round edged moulding on the front fixed with telescopic/double(Hafele/ebco make) approved sliders)				
	1no. Pencil drawer unit as shown in the drg shall be provided. Drawer shall consist of 1/2" thk. Comm. Ply sides, back and 1/4" thk. Comm. Ply base. Facia of drawers shall be of 3/4" thk. Comm. Ply finished in 1.5 mm. Thk. Laminate and with a wooden moulding on top/bottom edge for handle. Each drawer shall slide on a pair of hafele make telescopic drawer sliders. Each desk shall be provided with a 3" dia PVC wire manager at the given location.				
	<b>TOTAL OF WORKING COUNTER</b>				
<b>5</b>	<b>TABLE &amp; FURNITURE</b>				
<b>5.1</b>	<b>ZONAL MANAGER TABLE ( Size:- 8'-0" x 3'-6") ht. 2'-6"</b>	<b>Nos</b>	<b>1</b>		
	Providing and fixing tables made out of 19 mm thick commercial ply over hard wood frame work finished with 1				



	mm thick laminate of approved shade. Top having steam beech wood edging of size 2" x 1 3/4". 10mm thick clear float glass with beveled edges shall be provided on the finished to 19mm thk Comm.ply wood of approved make cladded with 1mm thk. Laminate (color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk ply wood with 1.0 mm laminate finish in the front, and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer shall be .75 mm thick laminate. & Table back side wil be 1mm laminate. A leg rest to be provided duly polished made out of 3"x2" Wooden Section. The rate inclusive of providing &fixing wooden cabinet to suit the DVR for size 2'X6"X1'9" or as per the requirements)				
	A shutter to be made by 19 mm ply wood cladded with 1.0mm laminate .The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The necessary wire managers (SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. All the exposed areas to be duly malamine polished The work to be completed as per design and approval of the Bank. The table should have key board tray and CPU Trolley to be Modular. All as per the design and instructions Bank the Internal surfaces shall be .75 mm thick laminate.				
5.1	<b>DEPUTY ZONAL MANAGER TABLE</b> ( Size: 6'-0" x 3'-0") ht. 2'-6"	<b>Nos</b>	<b>1</b>		
5.2	<b>OFFICER TABLE</b> ( Size:- 5'-0" x 2'-6") ht. 2'-6" same as above specification without glass top	<b>Nos</b>	<b>5</b>		
5.3	<b>SERVER TABLE ( 2'-6" WIDE )</b>	<b>Rft.</b>	<b>15.50</b>		
	Providing and fixing of Utility/Server Counter 2'-0" wide top made up of 19mm thick commercial pasted on 1.0 mm thk laminate. The Top of table will be finish with 1.00 thk laminate. All hardware fittings fixtures etc. The drawers to be made out of 19mm thk board with 1.0 mm laminate finish in the front, sides to be made out of 12mm plywood and bottom to be made out of 6mm plywood and it should play in drawer sliding telescopic channels. The inside of the drawer to be .75 LAMINATE. All exposed edges to have wooden lipping stained to match the desk and melamine finished. Design and detail of the table shall be as per design. (As per Site, Designing of Table and specification may be Changed). The works to include a keyboard try and CPU trolley to be modular. All as per the design and instructions Bank. (S.S. Finish Lock & Handle to be included )				
12	<b>CONFERENCE ROOM TABLE - (4' x 27')</b>	<b>Nos</b>	<b>1</b>		
a.	<b>IN LAMINATE FINISH</b>				
	Providing and making a table of overall size of top as mentioned above. It shall consist of 19 mm thk. Comm. Ply top as per design (double edge on outer edge with 37mm x 10mm				



	thk moulding with steam beach wood on the edges) supported on three boxes of size 24" x 6" made of 19 mm thk. Comm. Ply inter connected with boxing 4" x 6" (as approved by bank / architect). All external surfaces to be finished in 1mm laminate of approved shade.				
	<b>TOTAL OF TABLE &amp; FURNITURE</b>				
<b>6</b>	<b>STORAGE &amp; SIDE UNIT</b>				
<b>6.1</b>	<b>Side and Back Unit</b>				
	Providing and fixing Side Unit/ Back unit 400 mm depth made out of 19mm ply wood finished with 1.0mm laminate in all exposed areas and top shall be 1 mm thick. The drawers to be made out of 19mm commercial plywood and clad with 1.0mm laminate and bottom made out of 6mm comm ply duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm commercial ply wood and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit shall be .75 mm thick laminate in matching tone. All the exposed edges of the boards/ply woods to be covered with woden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect.	<b>Nos</b>	<b>7</b>		
<b>6.2</b>	<b>LOW / FULL HT CABINET</b>	<b>Sq Ft</b>	<b>1150</b>		
	Providing and fixing Full /Low height Cabiner400mm deep made out of 19mm thk plywood finished with 1.0mm laminate in all exposed areas. The Shutter to be made out of 19mm ply wood in the front clad with 1.0mm laminate( color, vertical grain) . and bottom made out of 6mm plywood duly laminated in matching tone and shelves 19mm thk comm ply wood to fixed inside storage. The shutters to be made out of 19mm ply wood. The necessary locks, handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit shall be .75 mm thick laminate finish. All the exposed edges of the boards/plywoods to be covered with wooden lippings/mouldings duly polished all complete. All as per the design and instructions Bank.				
<b>6.3</b>	<b>OVERHEAD / BELOW COUNTERE WOODEN STORAGE IN PANTRY</b>	<b>Sq Ft</b>	<b>45</b>		
	Providing and fixing modular type Overhead/Below counter wooden storage units with shelves (As per the drawing) in pantry/washrooms made out of 19mm thick BWP plywood. The exposed surfaces of cabinets shall be finished with 1.0mm thick laminate of approved shade & colour and inside surfaces shall be finished with 0.80mm thick white laminate with wooden lipping all round. The interior of the unit shall have provision for drawers and locker arrangement including all brass hardware such as hinges, sliding channel, door handle, drawer pull, drawer channels of M/s Hettich or equivalent and Godrej/Europa door locks etc., complete all as shown in drawing and specified and directed by the Officer- in - charge.				

	<p><b>Note:</b>                      a) Make of Plywood and laminate shall be of M/s Archidply/Kitply/Green ply/Century.                      b) Glazing shall be measured under relevant item and paid separately                      c) Rate quoted for the item deemed to include all wastages</p>				
<b>6.4</b>	<b>DRESSING MIRROR</b>	<b>Sq Ft</b>	<b>10</b>		
	<p>Dressing Unit With Full height Mirror: Providing dressing mirror with drawer units (As per the drawing) made out of the 19mm thick BWP plywood and external and internal surfaces of cabinets shall be finished with 4mm thick natural teak veneer of approved shade with two coats of Melamine polish and wooden lipping allround. The cabinet shall be provided with 8mm thick mirror with bevelled edges of first quality, approved brand, Manufactured by M/s Saintgobain/Modiguard with plywood backing and designer beading. The interior of the dressing unit shall have provision for drawers and locker arrangement including all brass hardware such as hinges, sliding channel, door handle, drawer pull, drawer channels of M/s Hettich amke or equivalent and lockin arrangement of M/s Godrej/Europa make etc., complete all as shown in drawing and specified and directed by the Officer- in - charge.</p> <p><b>Note :</b>                      a) Make of Plywood and laminate shall be of M/s Archidply/Kitply/Green ply/Century.                      b) Rate quoted for the item deemed to include all wastages</p>				
<b>6.5</b>	<b>TV cabinet units</b>	<b>Sq Ft</b>	<b>110</b>		
	<p>Providing and fixing modular type TV cabinet units with shelves (As per the drawing) in room made out of 19mm thick BWP plywood. The exposed surfaces of cabinets shall be finished with 1.0mm thick laminate of approved shade &amp; colour and inside surfaces shall be finished with 0.80mm thick white laminate with wooden lipping allround. The interior of the unit shall have provision for drawers and locker arrangement including all brass hardware such as hinges, sliding channel, door handle, drawer pull, drawer channels of M/s Hettich or equivalent and Godrej/Europa door locks etc., complete all as shown in drawing and specified and directed by the Officer- in - charge.</p> <p><b>Note :</b>                      a) Make of Plywood and laminate shall be of M/s Archidply/Kitply/Green ply/Century.                      b) Rate quoted for the item deemed to include all wastages</p>				
<b>6.6</b>	<b>PEGEON HOLE SHELVES FOR DESPATCH</b>	<b>Sq Ft</b>	<b>70</b>		
	<p>Providing and fixing Pigeon Hole units of full height and 1'6" depth as per drawing. They shall be made of 19 mm thk. comm. ply for both verticals and horizontal members. The bottom of the unit shall be at 3" from FFL. The top of storages shall touch the false ceiling level or 7'-0" ht. The facing edges of all ply wood sections should be provided with steam beach lipping finished with melamine with approved laminate on all the shutter edges. The size of pegeon hole to be adjusted</p>				





	equally as per the site condition. Approximate size of each pegeon hole should be 10" x 10" as per drawings and in consultation with Architect. All the Internal surfaces shall be finished with 1.0mm thk. Laminate (suede finish) of approved make.				
<b>6.7</b>	<b>Main Electrical Panel Cabinet</b>	<b>Sq Ft</b>	<b>40</b>		
	Providing and fixing of DB Shuttering formed of 12mm thk plywood wood on 12mm thick Gypsum board (fire Proof) with finish as per Item no 1 for inside and outside shutters finished with laminate on outer surface with SS (4Nos) louver perforation and necessary hardware, hinges etc complete as per details. All as per the design and instructions Bank. Only front face taken for measurement only				
	<b>TOTAL OF STORAGE &amp; SIDE UNIT</b>				
<b>7</b>	<b>OTHER MISCELLANEOUS ITEMS</b>				
<b>7.1</b>	<b>PIN UP BOARD</b>				
	Providing and fixing soft board with necessary framework with 12mm BWR plywood on top 12 jolly board to be fixed finished with fabric @Rs80, with necessary mouldings duly polished along the periferi. All as per the design and instructions Bank.	<b>Sq Ft</b>	<b>100</b>		
<b>7.2</b>	<b>BOXING FOR ROLLING SHUTTER</b>				
	<b>WITH ACP FINISH</b>	<b>Sq Ft</b>	<b>200</b>		
	Providing and fixing boxing for the rolling shutters.l. Framing shall consist of Aluminium Sections of 50 mm x 25 mm @ 600mm C/C. Both ways horizontally and vertically on the wall / with Aluminum Sections of 2"x1" as directed by Bank / Architect. This framing would be covered by with 2mm thick "Aluminum Composite Panel". The rate shall inclusive of necessary fixtures and fittings, sealant etc. complete.				
<b>7.3</b>	<b>WOODEN WALL PANELLING</b>	<b>Sq.Ft.</b>	<b>600</b>		
	Fabricating and fixing wall/column paneling, the framing shall made out of aluminum hollow section of 65mm x 37mm size 1.5mm thick of JINDAL / INDAL at spacing not exceeding 600mm both ways (horizontal and vertical). Paneling framework to be secured to wall surface/column surface. Paneling framework to be clad on one side with 9mm thick ply finished with 1.0mm thk laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. All as per the design and instructions Bank.				
<b>7.4</b>	<b>KEY BOX</b>	<b>No</b>	<b>1</b>		
	Providing and fixing key box of size 1' 6"x1' 6"x 6" with all sides and back with 19 mm thick comm. Ply wood and lockable glass shutters in 19 mm ply , with 5 mm glass. Necessary hooks to be provided inside the box. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beeding polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, locks, hooks etc. and any necessary hardware items.				



<b>7.5</b>	<b>VERTICAL BLINDS WITH SCOTCH GUARD</b>	<b>S.FT.</b>	<b>50</b>		
	Providing & fixing in place 100 mm. Vertical blinds of approved make, quality and colour shade & pattern. Rate shall include necessary scotch guard treatment on both sides. The overlaps should be uniform & adequate. Vista Make or Equivalent Make				
<b>7.6</b>	<b>3M SYNTHETIC DOOR MATS (4'-0" x 2'-0")</b>	<b>NOS.</b>	<b>2</b>		
	Providing & laying in place Synthetic Door Mats (3M) of sizes not less than 4' x 2').				
<b>7.7</b>	<b>FIXING THE POSTERS &amp; DANGLERS</b>	<b>NOS.</b>	<b>25</b>		
	Providing & Fixing the Poster Holders & Dangers (Supplied by the Banks Vendor) as directed by the Bank Staff / Architect on the walls/ panels / glazing etc. complete in all respect without spoiling the décor				
<b>7.8</b>	<b>FROST FILM / ETCHING FILM OVER GLASS</b>	<b>S.FT.</b>	<b>250</b>		
	Providing and fixing etching film as directed by Bank/ Architect for excess area (for additional area other than 1feet depth and full length of glass, along with portion spec.) to proper level, without air bubbles / cuts / folds etc. complete.				
<b>7.9</b>	<b>M.S. SLOTTED ANGLE STORAGE</b>	<b>S.FT.</b>	<b>50</b>		
	Providing and making M.S. slotted angle storage using angles of 18 gauge thickness and shelves of 20 gauge designed as per the specifications of standard manufacturers. Shelves shall be provided at 1'-6" c/c & supported on frames on all four sides with vertical supports as per manufacturers' standard specifications.				
	<b>TOTAL OF OTHER MISCELLANEOUS ITEMS</b>				
	<b>GRAND TOTAL FOR FURNISHING (A)</b>				
	<b>* GST EXTRA AS APPLICABLE</b>				

Place:

Signature & Seal of the Tenderer

Date: