

## SCHEDULE OF QUANTITIES FOR SWR PIPE LINE REPLACEMENT

### Terms and conditions:

1. Bidders to submit the duly filled in offer in the letter head of the firm after signing all the pages, accepting the terms and conditions.
2. Wastage, transportation, loading/unloading, disposal of waste / malba / unserviceable material out of Bank's premises at the place earmarked by the local authority.
3. Contractor should visit the site and may obtain clarification, if any, required regarding items of work/drawing/design considered in schedule of quotation, from estate department/Architect before submitting their quotation.
4. Quantities mentioned are tentative and may vary as per site requirement; however work shall be completed as per site requirement in all respect.
5. Bank have right to delete or add items as per site requirement.
6. The Contractor shall visit and ascertain the nature of work to be done and shall accept all the responsibility for the cost of the work involved including liaisoning with & taking NOC/Permission with the Local Authorities/KMC etc. and public nuisance during the progress of the work.
7. Any overwriting/ correction/ applying correction fluid shall be avoided and in case any correction is made same must be initialized and stamped. No conditional offer will be entertained.
8. Successful contractor to execute the work without infringement of any safety rules and guidelines in presence of competent supervisor.
9. Prior approval shall be taken from Bank official/ Engineer for materials/ spares to be used other than the brands specified. Contractor to submit the material purchase challan along with the final bill for payment.
10. Completion certificate shall be obtained from the respective residents and payment shall be made after satisfactory completion of work.
11. Bank will deduct TDS from the contractor's bill as per standard rule.
12. Start date of RFQ issue: 10.02.23 & last date of submission of quotation is 17.02.23 @ 11:30 Hr.
13. Work shall be commenced within 07 days from the date of receipt of work order.
14. Address of the site :

**a. Sundaram Residential Complex**

97/1 – Chandighosh Road

Tollygunge

Kolkata – 700 091

**SCHEDULE OF QUANTITIES FOR SWR PIPE LINE REPLACEMENT**

SI No	Description of works	UOM	Qty	Rate (₹ in rft)	Total amount (₹)
<b>A. SWR Pipe Line replacement:</b>					
1.	Carefully dismantling of old MS pipes and other fittings including necessary M.S. Scaffolding as per site requirement.	L.S.			
2.	Supply & fitting of 04" dia SWR UPVC pipeline (Type A) conforming to IS:13592-1992 with all necessary hardware fittings, Tee, Socket, hooks & Clamps etc. including making holes in walls etc, if necessary & mending good damages including jointing with jointing materials(Spun, Yarn, Valamoid/ Bitumen/ M-Seal etc.) complete in all respect as per the site condition/ requirement.	Rft	2500		
3.	Buy-back of old MS pipelines after removal from the site.	L.S.		<b>(Less)</b>	
4.				<b>Total</b>	
5.				<b>GST @ _____%</b>	
6.				<b>Grand Total</b>	

**APPROVED MAKE LIST OF MATERIALS TO BE USED**

SI No.	ITEM*	BRAND NAME/ (APPROVED BY AUTHORITY)
1.	UPVC pipe, socket, clamp, necessary fittings, all hardware fittings	Supreme, Astral & Ashirvad

Date: \_\_\_\_\_

Place: \_\_\_\_\_

Signature of Contractor  
with Seal