
 इंडियन बैंक	 Indian Bank	अंचल कार्यालय, एस सी ओ - ४४सी, अर्बन एस्टेट फेज़-२, जलंधर 144022	ZO: JALANDHAR SCF-44C, URBAN ESTATE, PHASE-II, JALANDHAR- 144022
		इलाहाबाद ALLAHABAD	
		ईमेल E-mail: zojalandhar@indianbank.co.in	
		वेबसाइट Website: www.indianbank.in	

Tender Ref No.IND/ZO-JAL/2022-23/

Date: 14/03/2023

**NOTICE INVITING TENDER FOR SUPPLY & INSTALLATION
OF AC FOR BANK'S VARIOUS BRANCHES**

Indian Bank invites sealed quotations for supply & installation of AC from Bank's preferred vendors or Authorized dealer of Voltas, Carrier, Llyod (capacity 1.5 ton, 2.00 ton) for Bank's various Branches in Jalandhar Zone at following terms & conditions:

SI No	Details	Particulars
1	Details of work to be done	Sealed quotations are invited from vendors supplying AC with installation & buy back.
2	Form of Contract	Item wise rate/ brands preferred in AC are Voltas, Carrier, Llyod with stabilizer (capacity 1.5 ton, 2 ton, 1.0 ton)
3	Branches where AC will be installed	Various Branches as per requirement
4	Earnest Money Deposit (EMD)	<p>Rs. 5,000/- (Rupees Five Thousand only)</p> <p>EMD is to be submitted to the following address before tender opening date & time in the form of Demand Draft only (valid for a period of 90 days from the date of publication of the tender in the aforesaid System Portal), drawn from any scheduled Nationalized Bank in favour of Indian Bank and payable at Jalandhar:</p> <p>To Chief Manager, Indian Bank ZO: Jalandhar SCF-44C, Urban Estate, Phase-II, JALANDHAR-144022</p> <p>In case the EMD is not received within the aforesaid period, the bid will be out rightly rejected.</p>
5	Availability of Tender	The Tender Documents can be downloaded from the Bank's website www.indianbank.in
6	Tentative date of issue/ floating of quotations	From 15.03.2023
7	Last date of submission of Tenders	23.03.2023 (Upto 4.00 PM)
8	Date and Time of Opening of the Tender	<p>23.03.2023 at 4.30 AM</p> <p>In case the tender opening date is declared as holiday the tender will be opened in the next working day at the same time.</p>




9	Address where the quotations to be delivered	Tender will be submitted in the Drop Box of the following Given address before time. After the closing period tender will not accepted. Indian Bank ZO: Jalandhar SCF-44C, Urban Estate, Phase-II, JALANDHAR-144022
10	Period of contract/ time of completion	7 Days
11	Defect Liability Period	12 months (Twelve months) from the date of virtual completion as certified by Architect / employer
12	Period of submitting of Final bill	15 days from the date of completion
13	For Tender related queries	<u>Contact Persons:</u> 1. Mr. Mintu Kumar Mobile No.: +91 9413689357 2. Mr. Varun Suri Mobile No.: +91 9899668909

The Bank reserves the right to cancel all or reject any tender without assigning any reason whatsoever.

Jalandhar
Date: 14.03.2023


Chief Manager





SCHEDULE OF QUANTITIES

AIR CONDITIONING WORKS IN INDIAN BANK BRANCHES JALANDHAR ZONE

s.no	Description	Unit	Quantity	Rate
1	Split AC 1.50 3 Star rating	No	1	
2	Split AC 2.00 3 Star rating	No	1	
3	Split AC 1.00 3 Star rating	No	1	
4	Supplying and laying of 16 SWG Extra copper refrigerant (beyond 3 meters as supplied by the OEM) for suction and return of suitable dia. The rate shall include Copper Pipe and insulation with 19mm thick Nitrile Rubber Tube (As per Unit Manufacturer Recommendation) and necessary installation accessories such as supports and clamps. The sizes given shall be verified by the supplier for adequacy and size based on the manufacturer standards. This includes all the fittings and accessories, breaking of wall for making hole wherever required refrigerant piping Running along the partition wall shall be concealed in the wall with necessary hasing in the wall and closing the same with sand cement plastic with chicken wire mesh. Wherever, it is not possible to conceal <u>the piping, the piping work should be done on the surface only after consultation and approval by Bank's Engineer</u>	Rft	1	
5	Supplying and laying of Extra Electrical interconnecting control cable of suitable IS/BIS standard Cable of 1.1-2.2 KV, Multi strand from indoor to outdoor of size as specified by the manufacturer suitable for 1.5 /2.0 TR Split type AC.	Rft	1	
6	SITC of drain piping (1 inch or as specified by OEM) constructed out of CPVC / HDPE hard pipes, fittings, accessories, bends, elbows, tees, flanges, tappings, wall sleeves, hangers, supports, anchor fasteners, etc and connecting the drain line till ground level as directed by Engineer-In-Charge or Architect. The work includes cutting / chiselling in walls, fixing with GI clamps, floor and making good of all the chases / cuts, etc and discharging the drain pipe into the floor trap or gully trap as per site conditions. Drain piping running along the partition wall shall be concealed in the wall with necessary chasing in the wall and closing the same with with sand cement plastic with chicken wire mesh.	Rft	1	



7	Supply and Installation of Digital Voltage Stabilizer (Wall Mounted) with under voltage and over voltage protection and Auto-Start Feature for AC (4 KVA) with working range between 130 V- 300 V. Make - VGUARD/ MICROTEK / LIVGUARD / BLUEBIRD (Only Copper Transformer) Minimum Warranty - 3 years	No	1	
8	Supply and Installation of Digital Voltage Stabilizer (Wall Mounted) with under voltage and over voltage protection and Auto-Start Feature for AC (5 KVA) with working range between 130 V- 300 V. Make - VGUARD/ MICROTEK / LIVGUARD / BLUEBIRD (Only Copper Transformer) Minimum Warranty - 3 years	No	1	
9	Installation of IDU & ODU of 2.0 Tr / 1.5 Tr unit with first oil & gas charge & commissioning, etc. Rate includes ceiling mounted suspension kit, etc complete	lumpsum		
10	Installation of above 2.0 Tr / 1.5 Tr Split AC Unit with first oil & gas charge & commissioning, etc.	lumpsum		
11	Providing and fixing standard powder coated support MS Stand / Wall Brackets for providing proper support to the Outdoor Unit	No	1	
12	Providing and fixing AC Protection Grill Cage with locking arrangement for the outdoor units of the above split units including primer with paint, welding, etc and all other required accessories and work.	No	1	
13	Buy back of Old AC	No	1	

Amount in Words:

Rupees.....
.....Only

Place :

Date

Signature & Seal of Bidder

