

Project- Rate Contract for Air conditioning work			
Bank- Indian Bank			
Zonal Office: Allahabad			
Branch: Various Branches in 6 districts of Allahabad zone during 90 days from the opening of tender			
<ul style="list-style-type: none"> <li>All Items are exclusive of Taxes (Taxes to mentioned by contractor)</li> <li>All work to be done as per tender conditions</li> </ul>			
Sr.No.	Description	Unit	Unit Rate Excluding GST
A)	Providing & Fixing High-Wall Split Air conditioners including piping. Installation, stabilizer etc. High wall split (at-least 3-Star Rating with Copper Condensing Coil and Copper Evaporation coil) air-conditioner units with branded cordless remote control. The rate of units is including the supply and laying of 03 mtr copper pipe with insulations, cables, rubbers, white cements etc. Copper and Drain pipe of adequate length should be provided. The basic rate of the A/C with all necessary components should be quoted. Unit rate per Split-units given below :		
1.	High Wall Split AC. Machines. Of 1.0 Ton Capacity, non Inverter (at least 3-Star Rating with Copper Condensing Coil and Copper Evaporation coil) of Blue Star Company	Per No.	
2.	High Wall Split AC. Machines. Of 1.5 Ton Capacity, non Inverter (at least 3-Star Rating with Copper Condensing Coil and Copper Evaporation coil) of Blue Star Company	Per No.	
3.	High Wall Split AC. Machines. Of 2.0 Ton Capacity, non Inverter (at least 3-Star Rating with Copper Condensing Coil and Copper Evaporation coil) of Blue Star Company	Per No.	
4.	Charges for Installation of Split Air-condition units. Inclusive drilling of holes etc.	Per AC Unit	
5.	Supply, Installation, Testing and Commissioning (SITC) of extra copper Piping approved brand (Ryoku) with installation.	Per mtr.	
6.	SITC. Of Drain PVC. Drain Pipe including with proper Clamping, elbow, T etc. complete.	Per mtr.	
7.	Additional Inter-connecting 3 Core- 2.5 Sq.mm. Cu flexible cable of branded (Havells) Only.	Per mtr.	
8.	Prov. & fix. 4 KVA automatic voltage stabilizer with 3-4 step relay and input voltage range from 130V to 280 V and output to be 220V of approved brand (V-Guard / Blue Bird / Blue Star) (Copper winding) at given Position	Per No.	

9.	Prov. & fix. 5 KVA automatic voltage stabilizer with 3-4 step relay and input voltage range from 130V to 280 V and output to be 220V of approved brand (V-Guard / Blue Bird / Blue Star) (Copper winding) at given Position	Per No.	
10.	Prov. & fix. of outdoor stand at given Position.	Per No.	
11.	Supply & Installation of 32A modular AC box with top in a specified company manufactured box with suitable rating MCB (Havells) for AIR CONDITIONS	Per No.	
12.	Timmer of approved brand (Blue Star) (for ATM room/server room)	Per No.	
13.	Annual Maintenance Charges (after Free Service), if required by the Bank	Per AC unit	

Signature of contractor with Stamp/ Seal.