

**BILLS OF QUANTITIES FOR PROPOSED CIVIL (TOILET REPAIRS, FLOORING AND MISC. WORK) AND FURNISHING
WORK OF INDIAN BANK FOR LARGE CORPORATE BRANCH AT 5TH FLOOR,
ANAM - 1 BUILDING, AHMEDABAD.**

PRICE BID					
Sr. No.	Description	Quantity	Unit	Rate	Amount
<p>Note : Rate should be inclusive of material,labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills</p>					
[A]	CIVIL WORK				
1	CONCRETE WORK				
1.1	Filling of sunk slab portion of toiles with removed usable material in toilet block, drop slabs including compacting etc. complete at all levels.	2	CMT		
1.2	Providing and Laying 75 mm thick water Proof Indian patten stone in 1:2:4 concrete Mix.In Toilet Sunk Slab Providing and laying plain cement concrete flooring (PCC) 1:2:4 (1 Cement:2 Coarse Sand: 4 Stone aggregate 20 mm nominal size) admixed with water proof compound Conplast X421 IC of Fosroc or Equivalent company. curing etc. complete as directed.	4	SMT		
2	MASONRY WORK				
2.1	P/C 115 MM THICK BRICK PARTITION WALLS Providing and constructing 115 mm thick brick masonry in partition walls with approved good quality bricks having a crushing strength of 35 kg/sq.cm for super structure in CM 1:4 (1 cement : 4 coarse sand) including scaffolding, racking out joints, reinforcement of 2 nos. 8 mm dia MS bars at every fouth leayer, curing etc. complete as directed at all heights as follows. (Rate includes the cost of MS bars or Iron hoop)	14	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
3	FINISHING WORK				
3.1	<p>P/A 12 MM THICK CEMENT PLASTER ON OLD WALL AND CEILLING</p> <p>Providing and applying 12mm thick finish cement plaster at all heights and below plinth in 1:4 cement mortar to the walls, beams, ceiling, stair, column, pattias, patch work grooves including scaffolding, curing & finishing smooth. The plaster surface shall be rubbed with 'Iron plate'. till the surfae shows cement paste in line and level complete as directed. Including dismantling existing plaster.cleaning the site and carting away debris at all levels. Its disposal also Rates includes removing switch board plates and refixing same after plastering.</p>	20	SMT		
3.2	<p>P/A 12MM THICK FINISH CEMENT PLASTER ON NEW WALL AND CEILLING</p> <p>Providing and applying 12mm thick finish cement plaster at all heights and below plinth in 1:4 cement mortar to the walls, beams, ceiling, stair, column, pattias, grooves including scaffolding, curing & finishing smooth. The plaster surface shall be rubbed with 'Iron plate'. till the surfae shows cement paste in line and level complete as directed. Plaster on New walls and ceiling</p>	32	SMT		
4	PAINTING WORK				
[a]	<p>P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)</p> <p>Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying FULL primer and putty, at all heights complete as per manufacturer's specification and as directed.</p>	37	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
5	FLOORING WORK				
5.1	<p>P/L VITRIFIED TILES FLOORING IN TOILET [With EPOXY Grouting]</p> <p>Providing & fixing 600 x 600 mm coloured Vitrified Tiles Flooring of approved make first quality Vitrified tiles for flooring as per design, Laying Tiles in CM in 1:4 over cement mortar bedding laid to proper slope, line & level as specified. The rate includes curing acid cleaning, cutting etc. complete. Rate shall be same for all levels (Toilet). Sample of the tiles must be got approved from Architect/Bank. Rate includes dismantling of existing tiles flooring and disposal complete as directed. (Basic price of tiles shall be Rs. 500=00 Per Sqmt)</p> <p>Make- Somany Delmon Grey, Millenium Blaze grey matt Finish or equivalent.</p> <p>Only finished surface area shall be measured for payment</p>	4	SMT		
5.2	<p>P/F VITRIFIED TILES DADO ON WALL [With EPOXY Grouting]</p> <p>Providing & laying wall dado of 5 to 6 mm thick coloured Glazed tiles(Mat Finish) of 600 x 600 of approved make first quality fixed cover 13mm thick plaster in CM 1:3, including providing groove upto 3mm wide if directed to do so and using grey cement in pointing of joints and applying neat cement paste about 3 Kg/Sq.m. The rate shall be inclusive of centre point fittings i.e. extra labour, material etc. to be considered so as to get outlet of plumbing/sanitary fittings at the junction. Rate shall be same for all levels. Sample of the tiles must be got approved from Architect/Bank. Rate all so includes backing coat of rough cement plaster. Rate includes dismantling of existing tiles and disposal complete as directed. (Basic price of tiles shall be Rs. 500=00 Per Sqmt)</p> <p>Make - Somany Montano Grey, Millenium Pietra Grey Glossy Finish or equivalent.</p> <p>Only finished surface area shall be measured for payment</p>	13	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
5.3	<p>P/F GRANITE FOR PANTRY PLATFORM</p> <p>Providing and fixing selected black jet granite, mirror polish, 18 mm to 19 mm thick with machine cut edges, in required length and width as per architects detail for sandwich platform etc. including cutting holes etc. for sink etc. providing & fixing borders, facia at platform with machine cut & mirror polish edges filling joints with balck colour pigment mixed in white black colour pigment in white cement, using araldite for borders & facias will be paid in square meter only. Facia Patti also will be measured. For Pantry Platform Basic price of Granite shall be Rs.1700=00 per Sq. Mt (Excluding GST)</p>	2	SMT		
5.4	<p>P/F POLISHED KOTA STONE FOR PANTRY PLATFORM SUPPORT</p> <p>Providing and laying single piece one side polished green kotah stone with machine out edges for pantry platform veticals & horizontal support. Rate includes hand and wax polishing as directed. Including cutting holes etc complete.</p>	4	SMT		
5.5	<p>P/F GRANITE DOOR FRAME</p> <p>Providing and fixing 19 mm thick Granite Door frame [jams] of size 6" and 3" wide with two members all edges shall be half round moulded mirror polished as per design and instruction complete as directed. making drilling hole for fixing hinges and aldrop. Granite patta will be paid in square meter only. Basic price of Granite shall be Rs. 1700=00 per Sq. Mt (Excluding GST)</p>	3	SMT		
5.6	<p>P/F GRANITE DOOR SILL</p> <p>Providing and fixing selected black jet granite, mirror polish, 18mm to 19 mm thick with machine cut edges, in required length and width as per architects detail for Door sill and Tread & Risers etc. providing mirror polish round moulded edges in tread, filling joints with balck colour pigment mixed in white cement, for measurment shall be Sqmt and paid in square meter only. The rates include removal of existing Flooring & its disposal (Basic price of Granite shall be Rs.1700=00 Per Sqmt)</p>	1	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
5.7	<p>WATER PROOFING IN SUNK AT TOILET</p> <p>1. Clean surface with wire brush, blower and water.</p> <p>2. Open the cracks & cut a rectangular groove (aprx 4 mm wide & 8 mm deep) and Filling the groove with PU sealant of 5000% elongation.</p> <p>3. Apply neat coat of BASF SBR 131 (35 Sqft /Liters) Then apply 6 mm thick plaster in 1:2 C.M with integrated water proofing compound of BASF 141 then apply 3 coat of 1cement:2 Kg Cement: 4 Liters water subsiquently. Then do brick bat coba concrete to cover the drainage pipe and finish the top surface in 1:2 cement mortar finally apply a coat of 1 SBR: 1 water and again repeat 1:2:4 as above and pond testing to be done</p> <p>4. Curing for 3 to 5 days</p> <p>The contractor should give 10 year Guarantee to any leakage on stamp paper</p>	4	SMT		
6	ALUMINIUM / STEEL /WOODEN WORK				
6.1	<p>P/F ALUMINIUM VENTILATORS</p> <p>Providing and fixing in position powder coated aluminium frame size 63.50x38.10 x 1.28 mm thick with adjustable 100 mm wide and 4 mm thick glass louvers with mechanism ventilators Sample of one ventilator with adjustable mechanism shall be got approved from Consultant/Bank.</p>	1	SMT		
6.2	<p>P/F FLUSH DOOR SHUTTER WITH BOTH SIDE LAMINATE FINISH WITHOUT FRAME</p> <p>Providing & fixing flush door shutter 30 mm thk BWP of Archid/Green Lam/Kit ply/Century or Approved ISI make , Water proof, thermosetting synthetic resin bond solid batten core of blockboard construction with 30 mm thick lipping of first quality teak wood battens on all edges of shutters with both side laminate as per architect's detail, supplying & fixing approved fixtures & fittings such as S.S hinges 4" long,tower bolts 8" long, handles 6" long ,Aldrops 12" Long, as per the details flush shutters are without frame (measurement will be out to out of shutter only). at all levels. [Approx Size 650/750 mmx2050mm</p>	4	SMT		
7	MISCELLANEOUS WORK				
7.1	Charges for dismantling work including stacking debris and reusable material as directed including carting away debris all levels.				
[a]	Dismantling Brick wall/ Brick partition wall with or without plaster etc.	25	CMT		
[b]	Removing of Existing Plaster and carting away debris	5	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
8	WATER SUPPLY WORK				
8.1	Providing and fixing concealed SCH-80 UPVC water supply line ISI approved mark, including all necessary specials, making zaries, making holes, cutting floors and making good after work is complete etc. complete as directed for. Pipe shall be Astral/Supreme make. at all levels				
[a]	- Do - for 15 mm dia line.	20	RMT		
[b]	- Do - for 25 mm dia line.	20	RMT		
8.2	Providing and fixing following fixtures of Jaquar make or its equivalent with chromium plated disce etc. complete for concealed pipe lines as directed by Architect Jaquar CP continental ISI Marked or equivalent make				
[a]	Providing and fixing Bib Cock of Catalogue No - 037	1	NO.		
[b]	Providing and Fixing Wall Mounted Sink Cock of Catalogue No - 347	1	NO.		
[c]	Providing and fixing angle cock of Catalogue No -053	1	NO		
[d]	Providing and fixing 25 mm, chromium plated brass Flush valve Catalogue No -1081A [Continental Range]. [Control Valve]	1	NO		
[e]	Providing and fixing 25 mm dia handle valve of approved Zoloto quality, for pipe lines etc complete as directed.	1	NO		
[f]	Providing and Fixing brass chromium plated soap dish of approved make & quality etc. complete as directed. Sample shall be got approved from Bank/Architect.	1	NO		
[g]	Providing and fixing brass chromium plated Napking Ring of approved make etc. complete as directed.	1	NO		
[h]	Providing and fixing Health Faucet [No 573]	1	NO		

Sr. No.	Description	Quantity	Unit	Rate	Amount
9	SANITARY WORK				
9.1	Providing & laying & fixing UPVC SWR drainage line concealed/open in the structure as per details and requirement with necessary specials such as Y-2, T-2, offset, plugs, bends and filling the joints with approved adhesive including cutting of wall floor and making good after the work is cover etc. all as above. Pipe shall be Prince/Supreme / Astral make at all levels.				
[a]	For 75 mm dia 6 Kg/Cm2	20	RMT		
[b]	For 100 m dia pipe 6 Kg/Cm2	15	RMT		
[c]	Providing laying & fixing concealed 38 mm dia P.V.C. waste water pipe line complete as directed.	15	RMT		
9.2	P/F UPVC NAHNI TRAP Providing and fixing UPVC Nahni Trap of Astral or Supreme. Rate includes cutting of floor/wall, necessary outlet pipe with necessary adhesive. Upto downtake pipe, Fixing PVC Jali of approved make complete as directed.	3	NO		
9.3	P/F WALL HUNG EWC CERA first quality or equivalent make wall hunhg extended EWC complete with adjustable sleeve and wall flange, connection pipes, etc making holes in walls, floors and making good the same. (Rate is including everything complete. except angle cock) CLAIR S1031102 EWC wall hung Extended 'P' Providing Snow white coloure EWC S1060102 Cistern B1510108 Soft close chair seat cover B1810105 Twin Flush Fitting CI Chair Bracket	1	NO		
9.4	P & L Brick Partition wall for walls & Plumbing wall of Wall Hung WC Providing and constructing 115 mm thick brick masonry in partition walls with approved good quality bricks having a crushing strength of 35 kg/sq.cm for super structure in CM 1:4 (1 cement : 4 coarse sand) including scaffolding, racking out joints, curing etc. complete as directed at all heights as follows. (Rate includes the cost of MS bars or Iron hoop)	1	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
9.5	<p>P/F LARGE FLAT BACK URINAL</p> <p>Providing and fixing Large flat back snow white glazed first quality lipped urinal of Cera make cat No.S4020107 including Approved make chromum plated angular cock of Jaquar Cat. No-PRS-CHR-077 (PRESS MATRIC) chromium plated , connecting PVCpipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No- 709 [ALLIED] , CP brass spreader and CP pipe, with necessary connecting pipe wall flange ,38 mm dia chromum plated waste coupling Approved make with required length of 32 mm dia concealed GI pipe upto the drain and bend, fixing clamps complete as directed.</p>	1	NO		
9.6	<p>P/F GRANITE STONE URINAL PARTITION</p> <p>Providing & fixing urinal partition made out of both side polished Granite stone 18 to 20 mm thick with round moulded edges of shape as directed. Including all incidental etc. complete.</p>	2	SMT		
9.7	<p>P/F WASH BASIN</p> <p>Providing and fixing first quality Snow white wash basin of 550 mm x 400 mm size, M Cera Cat No. S2040103 [Cornet] approved shape as per detail of approved make and quality such Cera/Hindustan/Nycer or equivalent with necessary specials, one chromum plated brass pillar cock 15 mm size of Jaquar make cat. No-PRS-CHR-031 (PRESS MATRIC) [Continental], one 15 mm CP angle valve of Jaquar Cat. No-053[Continental]chromium plated , connecting PVCpipes with nuts and all fittings, 32 mm dia CP waste coupling of Jaquar make cat. No- 709 [ALLIED] and rubber plug heavy brackets with two coats of aluminium paint over brackets, and 32 mm dia CP brass bottle trap of Jaquar make cat. No-773 [ALLIED] with necessary connection pipe wall flange etc. complete as directed</p>	1	NO		
9.8	<p>P/F MIRROR</p> <p>Providing and fixing 1'-6"x2'-0" Mirror above wash basin 6 mm thick Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.</p>	1	NO		

Sr. No.	Description	Quantity	Unit	Rate	Amount
9.9	P/F S.S SINK Providing and fixing stainless steel sink of Nirali make or approved equivalent make Standard rangers of overal size 17" x 17" (Bowl size 14"x14" x 7" depth in to in) including all necessary fittings such as CI brackets, overflow, rubber plugs, Cp brass chain, PVC connection and PVC waste pipe applying two coats of aluminium paint to the brackets etc. complete as directed.	1	NO		

TOTAL COST OF CIVIL WORK [A]

Rs. _____

Note: Rate includes Dismanttaling of exisiting toilet accessories like Urinal, Wash basin, W.C pan, EWC, NT, Flush Cock, Bib Cock, Stop cock, GI/CI pipe, Pvc Pipe line of any dia. and Removing door and windows etc.as directed by Bank nothing extra shall be paid for then

Sr. No.	Description	Quantity	Unit	Rate	Amount
[B]	FURNISHING WORK				
	TABLES				
1	<p>DGM TABLE SIZE: 7'-0" X 3'-0" X2'-6" HT. with Laminate finish on Table Top, sides and all other visible surfaces etc complete as follows</p> <p>Supplying and installation of Table as per the following description: Size 7'-0" x 3'-0". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make, grouplock, S.S. Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the CABINET shall have laminate, Foot rest of 1 1/2" x 3" T.W members shall be provided. All internal surface will have 0.60 mm thick balacing laminate.</p> <p>Apron (Modesty Panel) made from 18 mm thick ply wood finished with laminate.</p> <p>Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.</p> <p>Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.</p> <p>Table shall have stand for keeping CPU and metalic cable Manager shall be provided in table top. All exposed edges of teak wood shall have polished with smooth edges & corners</p> <p>Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.</p> <p>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc complete as directed.</p> <p>All the surface without laminate / balancing laminate shall be lacquered polished of approved shade.</p> <p>As per drawing and instruction of Architect/Bank work to be Completed.</p>	1	NO		

Sr. No.	Description	Quantity	Unit	Rate	Amount
	FINISHING DETAILS IN NUTSHELL: 1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished 2) Front Apron & Sides: 1.0 mm thick Dark Laminate 3) Facing of Drawers: 1.0 mm thick Dark Laminate 4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate Note: Rate includes Foot rest and CPU Trolley with castors				
1[a]	Same as above Item-no-1 but Size: 6'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces.. (For AGM)	1	NO		
1[b]	Same as above Item-no-1 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces. (For CM)	5	NO		
1[c]	Same as above item no-1 but Size: 4'-6"x2'-3" without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces. (For OFFICERS)	12	NO		
2	MEETING ROOM TABLE : Approx. Size: Length 10'-0" Width 3'-6" Top shall be made from 18mm th Commercial plywood with necessary in between supports with both side laminate as directed complete. 1mm thick laminate with 18 + 75mm wide 18mm thick MR Grade plywood with 36mm moulded steam beach beading shall be provided to the top as per instruction of the Architects complete as directed. Providing foot rest by using 3" x 1/2" T.W member, making necessary arrangement for installing Audio and computer system as directed complete. All visible surfaces of Table shall have liquer polish as per instructions of Architects. Preiliminary drawing of the Table is enclosed herewith there may be some modifications suggested during execution. All the non visible Inside and bottom portion of table should be 0.80 mm thick balancing laminate [Only Top shall be measured for payment purpose.]	3.5	SQ MT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
3	SIDE CREDENZA (SIDE TABLE)				
3[a]	<p>Side Credenza Size 3'-0"/ 3'-3"x1'-4" x 2'-6" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. Rate for length Less then 3'-3"</p> <p>Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate</p> <p>Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.</p> <p>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</p> <p>FINISHING DETAILS IN NUTSHELL:</p> <p>1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade</p> <p>2) Front Apron & Sides: Frosty White Laminate</p>	5	SQ.MT		
3[b]	<p>SIDE CREDENZA (SIDE TABLE) with partly Drawers Same as above Item No 3 all external surfaces to be finished with 1.0 mm thick Laminate (approved shades). Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with Partly drawers & Partly openable shutters as directed.</p> <p>FINISHING DETAILS IN NUTSHELL:</p> <p>1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade</p> <p>2) Front Apron & Sides: Frosty White Laminate</p>	9	SQ.MT		
3[c]	<p>STORAGE CABINET with Top & Front laminate finished. Storage of any height</p> <p>Same as above Item No-3, but all external surfaces to be finished with Laminate (approved shades)</p> <p>FINISHING DETAILS IN NUTSHELL:</p> <p>1) Top : Dark Laminate & Burma Teak beading on Edges with polishade</p> <p>2) Front Apron & Sides: Dark Laminate/Frosty white Laminate as per design & instructions</p>	4	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
4	P/F ELECTRIC CUB BOARD Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.	4	SQMT		
5	P/F PANTRY PLATFORM CUB BOARD SHUTTER Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamel paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface	2	SQMT		
LOW HEIGHT PARTITION WORK					
6	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed steam beach members / edges as directed. Laminate to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.	32	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
FULL HEIGHT PARTITION WORK					
7	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides, 1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.	39	SQMT		
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				
7[a]	Providing and Fixing Partition For Server Room/UPS Room Same as above item no 7 but Providing both side 8 mm thick Hilux board over aluminium framing with one side laminate & other side plastic paint of approved make & specifications etc complete as directed.	46	SQMT		
8	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows. Providing and fixing 4"x2" steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing & instructions.	2	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
GLASS DOORS AND PARTITIONS					
9	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS FOR MAIN ENTRANCE & AGM CABIN Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push. The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.	5.5	SQMT		
9[a]	Same as above item but P & F FULLY GLAZED PARTITION With Patch Fitting [FIXED PORTION] For AGM CABIN	2	SQMT		
PANELLING WORK					
10	P/F Wall panelling with laminate finishing for wall and Pillar etc Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect.	34	SQMT		
10[a]	P/A WALL PAPERS Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft	4	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
	FALSE CEILING WORK				
11	P/F GYPSUM BOARD FALSE CEILING Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.	78	SMT		
	Note: (1) Rate includes making necessary cutouts for lighting fixtures. (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft). (3) Only finished surface area shall be measured for payment.				
11[a]	Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications	77	SMT		
11[b]	P & F WOODEN FALSE CEILING Do same as Item No. 11 but for providing and fixing false ceiling made from 12mm thick FR plywood in pattern including providing and fixing approx 3.5mm thick veneer finished with melamine polish. Fixing the same with using of enamel painted MS framing as per detail. The rate should be inclusive of all necessary accessories and hardware items. etc complete as per detail and directed. Only finished surface area shall be measured for payment.	9	SMT		
12	SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.	2	SQMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
13	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST)	33	SQMT		
14	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	5	SQMT		
15	Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure.	6	NO		
16	Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows. Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.	2	NO		
16[a]	Same as above but size 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy	2	NO		
17	P & S of Visitors sofa. The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 ½" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.900/- per meter. It will have wooden handles as / drawing. outer length with armrest will be considered for measurement purpose.	8	RMT		
18	Providing and fixing 12mm thick Toughended Glass Self on wall for display as follows. 12 mm thick Toughended float glass with polished edges shall be fixed with necessary S.S Brush finish brackets support on wall as directed. all edges of glass shall be Diamond cut polished edges as directed complete.	1	SQ.MT		
20	Providing and fixing aprox. 3.5 mm thick veneer of basic rate of Rs. 95=00 per Sft on any existing Laminate surface for Table, Side Table, Storage cup board, wall panelling etc in approved pattern as per drawing and directions including PU Coating finish etc. complete.	42	SMT		

Sr. No.	Description	Quantity	Unit	Rate	Amount
21	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond with 0.25 mm foil with 2" x 1" x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building This item will be carried out as per manufacturer specifications. Rate also including trap door shutter including hinges stopers etc complete as directed. Design as per Bank standered Drawing and Architects instruction etc complete.	10	SMT		

TOTAL COST OF FURNITURE WORK

Rs. _____

GST will be extra as applicable

Note:

- [a] In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this
- [b] All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.

TOTAL COST SUMMARY

[A]	CIVIL WORK	Rs.	_____
[B]	FURNISHING WORK	Rs.	_____
	TOTAL AMOUNT OF CIVIL & FURNISHING WORK [A + B]	Rs.	_____

Tender Amount(In Words) Rupees:

(SIGNATURE OF TENDERER/FIRM)

NAME OF TENDERER

(SEAL OF FIRM)

PLACE:

DATE: