T.PALUR BRANCH & ATM - INTERIOR, FURNISHING, ELECTRICAL, DATA CABLING AND AIR CONDITIONING WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

Α	MAIN WORKS	Amount(Rs.)
1	INTERIOR WORK	
2	FIXTURES WORK	
2	BRANCH ELECTRICAL WORK	
3	BRANCH & ATM DATA CABLING WORK	
4	BRANCH A/C WORK	
5	ATM INTERIOR WORK	
5	ATM ELECTRICAL WORK	
6	ATM A/C WORK	
	TOTAL	

(RUPEES ONLY)

ALL RATES ARE INCLUSIVE OF 18% GST

T.PALUR BRANCH - INTERIOR, FURNISHING WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

S NO	PARTICULARS	QTY	UNIT	RATE(Rs)	AMOUNT(Rs)
1	<u>PARTITIONS</u>				
а	Full & Half Blocked Partition				
	Providing full height double skin fully blocked partitions upto RCC ceiling ht using Aluminium plain rectangular sections of 2 1/2"x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (Bank approved colors) with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base and a 100mm wide border (Brown) at the top including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.(Record, dining, strong room, ups room)	236.00	Sft		
b	Partly Glazed Partition Manager & Server Cabin:				
	Providing full height double skin partly glazed partitions using aluminium sections of 2 1/2"x11/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate with necessary grooves of 1mm thick. The rate shall include the cost of providing 100mm wide skirting with 1mm tk. laminate (Black) at base and a 100mm wide border (Brown) at the top and shall include the cost of providing 8mm tk. plain float glass with etching Design to suitable sizes, including making necessary slots for cable conduits to pass through and all incidental materials etc., complete.	250.00	Sft		
С	Low Height Partition				
	Providing low height double skin partitions along with Counter Divider partition wicket gate of the same type using aluminium sections of 2 1/2" x 1 1/2" size spaced at 2'0" c/c maximum for the frame work, fixed with 6mm plywood on both sides and lined with 1mm tk. laminate (bank approved laminates only) with necessary grooves of 1mm thick.	90.00	Sft		

	<u></u>		I	I	
	The rate shall include the cost of providing 100mm				
	wide skirting with 1mm tk. laminate (Black) at base&				
	including making necessary slots for cable conduits				
	to pass through and all incidental materials etc.,				
	complete.				
d	CASH PARTITIONS (BULK CASH)				
	Providing full height upto 7' 3" from floor level, semi	59.00	Sft		
	grilled plywood partition for cash cabin, using				
	aluminium sections of 2 1/2" x 1 1/2" size spaced at				
	2'0" c/c maximum for the frame work , fixed with				
	6mm plywood on both sides and lined with 1mm tk.				
	laminate (bank approved laminates only) with				
	necessary grooves of 1mm thick, The rate shall				
	include the cost of providing 100mm wide skirting				
	with 1mm tk. laminate (Black) at base and a 100mm				
	wide border (Brown) shade at the top and shall				
	include the cost of providing ornamental aluminium				
	grille to suitable sizes, including making necessary				
	slots for cable conduits to pass through and all				
	incidental materials etc., complete.				
е	CASH CABIN TOP ALUMINIUM GRIL				
	Providing and fixing in position readymade anodized	47.00	Sft		
	alumium grill of approved design and quality fixed				
	with continuous steam beech				
	/ teak wood beads of approved shape (finished 35 x				
	25 mm) all round polished (in cash cabin)				
2	FRONT COUNTER 12MM GLASS				
	Providing front glazing for cash cabin above counter	57.00	Sft		
	from 3'9" to 7'0" height, and inbetween banking	37.00	311		
	counters using 12mm thick plain glass including edge				
	polishing & etching.				
3	DOORS				
a)	ENTRANCE DOOR				
	To be made out of 12mm thk glass with etching as	42.00	Sft		
	per design. The glass with etching has to be fixed				
	with top & sides rails of 2½"x4" and bottom rails of				
	size 2½" x 6". The rails to be made out of beech				
	wood The door shall have 18" long s/s handle (as				
	shown in the drawing) and also double action floor				
	spring of specified make.				

	The door frame to be mde out of 5"x 2½" best quality beech wood. The etching in glass pattern to be done strictly following instructions of the Architect or following the drawing attached. The exposed wood of frames, rails to be polished as per			
	instructions of the architect. NB: The size of the door may slightly vary as per site conditions for matching the elevation on the fixed glazing. All exposed edges of the glass to be machine polished. The rails are to be made as per the design of the architect. Bank			
	Entrance door (4'0" X 7'0")			
b)	FLUSH DOORS			
i)	Door (3'0" x 7'0")	2.00	No	
i)	Door (2'6" x 5'0")	1.00	No	
c)	SEMIGLAZED DOORS			
i)	Manager (3'0" x 7'0")	1.00	No	
ii)	Manager, Server & B.cash (2'6"x 7'0")	2.00	No	
d)	WICKET DOOR			
i)	Wicket Door (3'0"x3'0")	1.00	No	
4	SERVER ROOM WORKING COUNTER			
5	Working top will be 2' - 6" ht to be provided as per instructions given by the architect. Rest of the working counter as per specifications in fabricated out of 18mm ply for top, sides and 6mm ply for back. The work station will have drawer units, keyboard tray, cpu platforms, leg rest etc., and drawings attached in tender and specifications. All clarificationss to be taken before quoting the prices and no extra cost shall be entertained at the time of execution. The entire work as per the instruction of the Architect at the time of execution. Cheque drop box/ Complaint	4.00	Rft	
5		1 00	No	
	Providing cheque drop box / complaint/Suggestion 1'6" length, 0'9" wide and 1'6" height with 19mm tk. Plywood and lined with 1mm tHk. Laminate(Fusion Maple - Wood finish) for top & exposed sides. Exposed edges of plywood shall be fixed with teak wood beading suitably polished and the back side shall be covered with 6mm tk. plywood. The inner sides shall be painted with two coats of enamel paint over acoat of primer & two coats of putty.	1.00	No	

6	Vertical Blinds:				
	Providing and fixing 100mm wide Vista Make or	99.00	Sft		
	equavalent vertical blinds of approved make quality				
	and colour shade and pattern. Rate shall include				
	necessary scotch guard treatment on both side. The				
	overlaps should be uniform and adequate				
7	FALSE CEILING (GYPBOARD)				
	Providing & fixing suspended gypboard false ceiling,	1100.00	Sft		
	which includes Providing & fixing G.I perimeter				
	channels of size 27mm, 0.5mm thk having one flange				
	of 20mm & another flange of 20mm along with				
	perimeter of the ceiling, screws fixed to brick				
	wall/partitions with the help of rawl plugs & Screws.				
	Then suspending G.I intermediate channels of size				
	45mm, 0.9mm thk with two flanges of 15mm each				
	from the soffit at 1200mm centres with stell G.I				
	hanger of width 25mm,0.5mm thk fixed to soffit				
	with G.I. cleat & steel expansion fasteners. Ceiling				
	section of 0.5mm thickness having knurled wedge of				
	51.5mm and two flanges of 26mm each with leafs of				
	10.5mm are then fixed to the intermediate channel				
	with the help of connecting clips and in direction				
	perpendicular to the intermediate channel at				
	450mm centres. 12.5mm tapered edge gypboard is				
	then screwed fixed to ceiling section with 25mm dry				
	wall screws at 230mm centres Screw fixing will be				
	done mechanically either with screw driver or drilling				
	machine with suitable attachment. Finally the				
	with requiste jointing compound, paper tapes,				
	finisher and premier suitable for Gypsum plaster				
	boards. The entire work shall be finished as per				
	instructions of the Architect. And also finished with				
	two or more coats of acrylic emulsion paint of				
	approved shade and make. No extra cost shall be				
	entertained in completing the entire work in all				
	respect.				
	Total Interior Works				
L				l .	

T.PALUR BRANCH - INTERIOR & FIXTURES WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

S NO	PARTICULARS	QTY	UNIT	RATE(Rs)	AMOUNT (Rs)
1	TABLE				
	Manager table as per drawing done with				
	structure made of 18mm plywood with				
	drawer unit comprising of 1 drawer, 1 filing				
	shelf fixed with pull out door (box type				
	hinges), locks, D type handles and all				
	accessories to be provided.All drawers,				
	corners, doors to be finished with beach				
	wood lipping/beading, melamine polished.,				
	push in type keyboard, all drawers and key				
	board on telescopic channels. All exposed				
	edges Teak/beach wood beadings is finished				
	with melamine polished and inside laminated				
	with 0.8mm laminate. The table to be topped				
	with 12mm float glass with beveling on all				
	four sides. The side unit is provided with two				
a)	Branch Manager 6'0"x2'6"	1.00	No		
2	FRONT COUNTER AND BULK CASH COUNTER				
	Providing and assembling banking counter				
	and Cash, single window counter unit as				
	shown in drawing of size not less than 5'0" x				
	2'6" x 2'6" or as per site requirements, with				
	regular drawer - 1 No. and shelves on one				
	side, a keyboard drawer at centre and a				
	platform for CPU onto other side for each				
	counter as shown in drawing using 19mm				
	thick commerical plywood lined with 1.0mm				
	thick laminate(Bank approved colors) Cash				
	and single window with 12mm thick glass (to				
	be strictly followed) in front side for all the				
	exposed surfaces, including providing skirting				
	4" wide with 1.0mm thk laminate (Black) on				
	both sides to match with the adjoining				
	partition and 4" wide border at top with				
<u> </u>	1.0mm thk laminate (Brown).The customer				

	lana a a a a a a a a a a		1	I	1
	All the plywood edges shall have teak wood				
	lipping and all inner surfaces shall be painted				
	with two coats of enamel paint over a coat of				
	primer & two coats of putty. The rate shall				
	include providing, fixing & painting a foot rest				
	using first class seasoned country frame of				
	size 3" x 1 1/2". Necessary hardware fittings				
	like draw sliders, hinges, multipurpose locks				
i)	Bulk cash	5.00	Rft		
ii)	Working counters	29.00	Rft		
2	STORAGE				
	Providing and fixing filing cabinet in manager				
	cabin for a height of 2'6" & 7' ht. made of				
	18mm plywood structure comprising of				
	suitable intermediate horizontal racks with				
	open type doors, finished with 1mm laminate				
	and teak wood beadings neatly melamine				
	polished and inside finished with 0.8mm				
i)	Manager Sc	10.00	Sft		
ii)	B.Cash Sc	10.00	Sft		
ii)	Banking Hall Sc	60.00	Sft		
ii)	Banking Hall Sc	13.00	Sft		
iii)	Record Room Sc	161.00	Sft		
3	WRITING LEDGE WITH 12mm GLASS TOP				
	Made out 18 mm ply as per design and	1.00	No		
	exposed external surfaces to be laminated				
	and internal surface to be painted with top				
	provided 12 mm thk etched glass with				
	machine polished edges . The entire work has				
	to be done to the satisfaction of the				
	architect. The design given has to be strictly				
	followed				
4	NOTICE BOARD				
	Providing and fixing of the soft board on the	12.00	Sft		
	customer lobby made of jolly board with a				
	fabric of B / R @ 200 / - per meter .The				
	design and the entire work has to be done as				
	per the instructions of the architect a the				
	time of execution				
5	ROLLING SHUTTER COVER BOX				
	Supplying & fixing of rolling shutter box using	48.00	sft		
	19mm thk plywood with adequate support at				
	the ends and finished with lamination of				
1	the chas and mished with lammation of				
	approved make and colour etc., complete				

T.PALUR BRANCH - ELECTRICAL WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

Sl.No	Description Of Work		0+	Data	A
	Description Of Work Supply&Installation&Commission of the following	Unit	Qty	Rate	Amount
A 1	MAIN DB (8WAY VTPN DB)				
	Three Phase, Vertical Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provision of MCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer:				
	100A TPN MCCB -1Nos				
	Outgoings:				
	63A TP MCB -4Nos				
	32/25/20A SP MCBs- 5Nos	Set	1		
	32/23/20M 3F WICDS- JINOS	361	т_		
В	Supply&Installation&Commisioing of the following				
1	LIGHTING DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 40A TPN MCB				
	Outgoings:				
	10/6A SP MCBs- 12Nos	Set	1		
2	POWER DB(4WAY TPN DB)				
	Three Phase, Phase Segrigated Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any.The DB should be IP 42 metallic				
	double door with provisioin of MCB&ELCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 63A TPN MCB				
	Outgoings:				
	32/25/20A SP MCBs- 12Nos	Set	1		

_	COMPLITED DD/OWAY CDN DD)				
3	COMPUTER DB(8WAY SPN DB)				
	12 Way SPN Distribution board				
	with nuetral bar,earth bar,cables ties,top and				
	bottom removable gland plate and with necessary				
	adopter boxes if any. The DB should be IP 42 metallic				
	double door with provisioin of MCB&ELCB etc as				
	required including cuting of wall and plastering the				
	same with neat finish.It comprising as flolows:-				
	Incomer : 40ADP MCB				
	Outgoings:				
	10A SP MCBs- 6Nos	Set	2		
4	Supply&Installation of the following with the necessary				
	enclosure and adopter boxes if necessary,				
	a)63A TPN MCB	Set	2		
	b)63A DP MCB	Set	4		
5	Supply&Installation of 32A Metal Clad Socket with				
	top in a specified company manufactured box with				
	suitable rating MCB for AIR CONDITIONS	set	5		
6	Supply&Installation of 63A 4Pole Change over switch	set	1		
	Tapper, amountained of our in one change over striken	300			
7	Supply and Fixing for 63A Phase Selector switch with				
	enclosure and adopter boxes if necessary,	set	2		
	on order of the despect source in the coolery,	300			
С	LT CABLES				
1	Supply&Laying of the following cables in built up				
	trenches, on wall, or in the ground as per the case may be,				
	with proper clamping with necessary fixing materials etc.				
	Installing testing&commission of 1100V grede UG				
	cable as per IS 7098/1554 (Finolex/ Universal)				
	3.5Corex50Sqmm Aluminium Armored cable Main DB	N /1+ ==	42		
	3.5Corex35Sqmm Aluminium Armored cable Main DB 3.5Corex35Sqmm Aluminium Armored cable power DB	Mtr	42		
	·	Mtr	32		
	3.5Corex16Sqmm Aluminium Armored cable LDB Main	Mtr	38		
2	End Termination of the above cables with proper Glands				
	and Lugs				
	3.5Corex50Sqmm Aluminium Armored cable Main DB	Set	2		
	3.5Corex35Sqmm Aluminium Armored cable power DB	Set	2		
	3.5Corex16Sqmm Aluminium Armored cable LDB Main	Set	4		
		\perp			
D	WIRING				
1	Light/Fan point wiring with 3 of 1.5 sqmm PVC				
	insulated copper conductor to be laid in 2mm suitable				
	PVC conduit with Bend,Couplings, etc And fixing with				
	clamps screws etc.All conduits to be laid above the				
	false ceiling/partition/concealed in the wall				

	etc. Wiring to be connected with supply&Fixing of			1
	6A Modular type switch(MK/ROMA) with suitable			
	Modular plate and metal Box			†
	a) One light Controlled by One Switch	Pts	20	†
	b) Two light Controlled by One Switch	pts	15	
	c) 6A Switch box Sockets in the switch board itself	Pts	10	†
	d) Ceiling fan with regulator	Pts	5	†
	e) wall bracket fan point (6A socket with 6A switch)	pts	12	
	f) Calling bell point with Calling bell instrument	Pts	1	
	g)Exhaust fan point	pts	3	
	g)Exhaust full point	ριs		
2	Supply&Wiring with Flame Retardant			
	insulated PVc wire as per grade IS 994			
	for Circuits,Computer point,Power points within 2mm thk			
	PVc conduits with necessary accessories and with			
	proper clamps and to be concealed below the false			
	ceiling It comprises as follows:-			
	a) 3Runs of 2.5Sqmmcopper wire in PVC conduit for			
	lighting circuit mains	Mtr	170	
	b) 3Runs of 2.5Sqmmcopper wire in PVC conduit for			
	Power points	Mtr	202	
	C) 3Runs of 2.5Sqmm copper wire in PVC conduit for	1710		†
	computer points	Mtr	218	
	d) 2Runs of 4Sqmm copper wire+1.5Sqmm copper	17161		
	wire in PVC conduit A/C Wiring	Mtr	220	†
	e) 2Runs of 6Sqmm copper wire+2.5Sqmm copper	1710	220	
	wire in PVC conduit	Mtr	35	
	f) 4Runs of 6Sqmm copper wire+2.5Sqmm copper	1710	- 33	†
	wire in PVC conduit	Mtr	25	
	wife in the conduct	1710		
Е	POWER POINT OUTLETS			
1	Supply&Installation of 3 Nos of 6A Sockets controlled by			
	2of 5A Switches with front plate with enclosure and			
	other accessories etc(MK /ROMA)	Set	12	
2	Supply&Installation of 1Nos of 6A Socket controlled by			
	1No 6A Switch with front plate with enclosure and other			
	accessories etc(MK /ROMA)	Set	10	
3	Supply&Installation of 1Nos of 16A Socket controlled by			
	1No 16A Switch with front plate with enclosure and other			
	accessories etc(MK /ROMA)	set	4	
F	LIGHTING FIXTURES			
1	Supply, Fixing & Commisioning of Recess mounting type			
	compact vertical Flat Panel 34W LED fitting in Down Rods with			
	white finish and other fixing accessories.(Crompton,			
	Wipro,Philips)	set	20	

				I	
2	Supply, Fixing & Commissioning of Recess mounting type				
	compact vertical round shaped 1x15W LED downlighter fitting				
	with white finish and other fixing accessories.,(Crompton,				
	Wipro,Philips)	set	4		
3	Supply&Fixing of Patti Type LED 20Watts Fiitings (Crompton,				
	Wipro,Philips)	Set	10		
4	Supply&Fixing exhaust fan(Crompton, Almonard)	set	3		
5	Supply&Fixing & Commisioning of wall mounting fan				
	with necessary Down Rods and with all				
	fixing accessories.,(Crompton / Havells)	Set	12		
6	Supply&Fixing & Commisioning of 48" ceiling fan				
	with necessary Down Rods and with all				
	fixing accessories.,(Crompton / Havells)	Set	3		
G	EARTHING				
1	Providing dedicated earthing with 600x600x3.15				
	mm copper plate along with 50mm dia.10feet				
	long G.I pipe with other accessories in the earth				
	filled with necessary salt, charcoal, etc. It should				
	be covered with G.I Manhole cover with necessary				
	civil works.etc	Set	1		
2	Supply & Laying of 10 Sqmm PVC Insulated Multi				
	strand copper conductor laid in 25mm dia PVC pipe for				
	Dedicated earth leads from the earth electrodes to				
	the UPSsystem	Mtr	35		
	and or objecting	1416.	- 33		
3	Providing general earthing with 50mm dia.10feet				
Ť	long G.I pipe with other accessories in the earth				
	filled with necessary salt, charcoal, etc. It should				
	be covered with G.I Manhole cover with necessary				
	civil works.etc	Set	1		
	CIVII WOLKS. Etc	361			
4	Supply&Laying of 8SWG copper wire	Mtr	50		
4	Supply&Laying of 83WG copper wife	IVILI	30		
F	TELECOMMUNICATION				
1	Supply&Laying of 2 Pair Telephone Cable within PVC	N // ±	100		
	Conduit and its necessary accessories etc	Mtr	160		
	S and Old the stage (20Detection of the 1911 DVS				
2	Supply&Laying of 20Pair Telephone Cable within PVC	B. 4 :	2.0		
	Conduit and its necessary accessories etc	Mtr	30		
3	Supply&Installation of RJ II Jack with necessary Face				
	plate and Box for connecting telephone points	Set	10		
4	Supply & fixing of 10 pair KRONE Box with lock and key	Set	1		
	TOTAL				

T.PALUR BRANCH & ATM - DATA CABLING WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

	BILL OF QUANTITIES							
S.No	Description Of Work	Unit	Qty	Rate	Amount			
	DATA CABLING							
1	Supply&Laying of CAT 6 Data Communication cable in 2mm							
	thk heavy duty 20mm dia PVC conduit and makinng holes in							
	the aluminium partitions/wall all accessories as required (DLink)	Mtr	210					
2	Supply&Installation,Testing&Commisioing of Modular type							
	1Nos of RJ45 Female Jack housed in GI anodised metal box							
	with suitable Faceplate fixing the same in the wall/partitions							
	with all accessories etc. as required.	Set	10					
3	Supply and fixing of 1M Mounting Cord	Set	10					
4	Supply and fixing of 2M Mounting Cord	Set	10					
5	Supply&Installation of 24por cat6 SWITCH	Set	1					
6	Supply and installation of 24port cat 6 jack panel	Set	1					
7	Supply and installation of 9u wall mounting rack	Set	1					
	TOTAL							

T.PALUR BRANCH - AIR CONDITIONING WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

Sl.No	Description Of Work	Unit	Qty	Rate	Amount
1	Supply, Testing and commissioning of				
	indoor and outdoor split air conditioner with remote				
	control, with 3 star rating units and necessary civil				
	works etc., The rate of units is including the supply				
	and laying of 3 mtr of copper pipes with insulations,				
	rubbers, white cements etc., (Brand: Voltas)				
а	1.5 TR - Manager	2	No		
b	2 TR - Banking hall	4	No		
2	Supply and laying of copper pipes with rubber				
	insulations, rubbers, white cements etc.,	60	Mtr		
3	Supply and installation of Stabilizer for following				
	units				
а	1.5 TR - 4 KVA	2	No		
b	2 TR - 5 KVA	4	No		
	Installation Charges for 1 Tr,2 Tr Split Air Conditioner				
b		6	No		
4	Supply and Installation of Outdoor Stand with				
	necessary civil works	6	No		
5	Supply and laying of PVC Blue pipes for water				
	drain from the indoor units.	40	Mtr		
	Civil works like cutting AC hole, packing, drain pipe cutting and				
6	packing with mortar etc.	1	Ls		
7	Supply and fixing Timer controlled for server Unit	1	No		
	Airconditioning works Total:				

T.PALUR - ATM INTERIOR WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

S.No	ITEMS AND DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	FULLY GLAZED ALUMINIUM PARTITION & DOOR				
a	FRONT BOTH SIDE FIXED PARTITION: Providing and fixing Fully glazed partition in ATM Entrance, made of aluminium MRF vapocured twin style frame work of size:-58 x38mm, 20 micron of IB-Black colour finished with 10 mm thk float glass with derk silicon (SAINT GOBAIN or MODIGUARD) up to the false ceiling level. Support to be done to the rcc ceiling, but measurements would be taken below the false ceiling level only.	135	Sft		
b	ENTRANCE DOOR (Size: 3'6"x7'0"): Providing and fixing of Fully glazed door for ATM entrance, made of aluminium MRF vapocured twin style frame of size:- 100 x 50 mm, 20 micron of approved colour finished with 10 mm edge polished glass with silicon (SAINT GOBAIN or MODIGUARD) up to the 7'0" height, door to be provided with dorma make 12" SS handle, lock and door closure(approved make) & stopper	50	Sft		
3	ACP WALL PANELLING Providing and fixing Wall Panelling using 3mm thk Aluminium Composite Panels of Alstrong or equivalant make over necessary frame work. The joints formed by the junction of two panels shall be filled with silicon sealent. The Wall Panelling / Boxing shall be erected 75 mm above the Highest False Ceiling Level. However, only exposed portions below the Highest False Ceiling Level shall be considered for payment. Pattern of wall panelling to be got colour approved from the Bank.	216	Sft		

4	GYPBOARD FALSE CEILING			
4		90	of+	
	Supply and erection of gypboard false ceiling for		sft	
	Manager cabin area at single level with framework of			
	G.I. Section of spacing 4'0" x 2'0" above with 12mm			
	gypboard fixing. Recessed ceiling is to be done as per			
	architects instruction to have provision for indirect			
	lighting rate is included for cutouts for lights, smoke			
	detectors and AC grills. The ceiling is putty finished			
	and sanded to form clean and homogeneous surface.			
	Rate is included for two coats of acrylic emulsion			
	painting.			
5	ATM SOCKETS COVER BOX (1'0"X1'0"x6" - 1no)			
	All ATM Sockets, IO Box to be covered using 12mm	2	nos	
	plywood structure with 1mm thk lamination finish			
	(matching ACP color colour), Shutter type door (up &			
	down) with lock, handle and necessary wire manager			
	groove (at bottom) to be provided.			
6	PIN-UP NOTICE BOARD			
	Providing & fixing Pin-up Board of approx size of	1	no	
	600mm x 800mm made of textile wrapped on 12 mm			
	thick soft board with 6 mm com ply backing and a			
	frame work of 50mm wide with 24 mm thk com ply,			
	finished with 1 mm thk Laminate. The Pin-up Board			
	shall be set into the wall panelling with necessary			
	fittings as directed by the Bank.			
7	WRITING DESK			
	Writing desk to be done as per plan with 12mm glass	1	no	
	topped with pigeon holes made with 18mm plywood			
	structure with additional boxing as per design,			
8	CHEQUE DROP BOX/ COMPLAINT			
	Providing cheque drop box/Complaint/Suggestion	1	no	
	1'6" length, 0'9" wideand 1'6" height with 19mmtk.			
	Plywood and lined with 1mmtk. Laminate (Fusion			
	Maple Wood finish) for top & exposed sides. Exposed			
	edges of plywood shall be fixed with teak wood be			
	ading suitably polished and the back sides hall be			
	covered with 6mmtk. plywood. The innersides shall			
	be painted with two coats of enamel paint over a coat			
	of primer & two coats of putty.			
9	ROLLING SHUTTER COVER BOX			
	Supplying & fixing of shutter box using 19 mm	75	sft	
	plywood, boxing with above entrance partiton and			
	rolling shutter and finished with 1mm lamination.			
	TOTAL			
	1011111			

SI.	Description	Qty	Unit	Rate	Amou
A	MAINS & DISTRIBUTION BOARDS			11010	
1	Supply, erection, testing and commissioning of three				
	phase 4 WAY, TPN MCB DB double door vertical type,				
	IP 42 powder coated with				
	40A TPN MCB – 1No as INCOMER				
	32A DP MCB-1No For UPS				
	10/25/32A – 4No.s as OUTGOING				
	Including all interconnections & accessories etc	1	No		
В	POWER CABLES & CONDUIT WIRING				
1	Supplying, laying, testing & commissioning of PVC /				
	LT insulated 1.1KV grade aluminium armoured				
	conductor cables of the following sizes, laid in trenches				
	below ground level/ clamped on to the walls as per site				
	condition.				
а	3.5C x 25Sqmm aluminium armoured PVC cable	28	mtr		
С	Supplying and terminating the end of cables of the				
	following sizes using Siemens type single compression				
	cable glands, crimping type aluminium / copper				
	sockets of required size, gland earthing clips etc.,				
	complete.				
а	3.5C x 25Sqmm aluminium armoured PVC cable	2	Set		
D	AIR CONDITIONING WIRING & ACCESSORIES				
1	Supply&Installation of 32A Metal Clad Socket with				
	top in a specified company manufactured box with				
	suitable rating MCB for AIR CONDITIONS	2	No		
2	Wiring in position 2 runs of 4.0 sq.mm. cable and 1 run				
	of 2.5 sq.mm cable for earth from Main D.B. to 2 Nos				
	split air – conditioners in P.V.C. conduit pipes including				
	chasing in walls / floor wherever necessary.	26	Mtr		
Е	UPS WIRING & ACCESSORIES				
1	Supply, erection, testing and commissioning of single				
	phase 6 WAY, SPN MCBDB double door type, IP 42				
	powder coated for UPS and Emergency Lighting with				
	40A DP MCB – 1No as INCOMER				
	10A SP MCB – 4Nos. as OUTGOING				
	Including all interconnections & accessories etc.,				
	complete.	1	Set		
2	Wiring in position 2 runs of 6.0 sq.mm. cable and 1 run				
	of 4.0 sq.mm cable for earth from Main D.B. to UPS and				
	UPS to UPS DB.	13	Mtr		
3	Wiring in position 3 runs of 2.5.sq.mm cable for circuits from				
	UPS.Lighting,Raw power required places in P.V.C. Conduit pipes				
	including chasing in walls / floor wherever necessary	38	Mtr		

4	Supply, fixing, testing & commissioning of 2No. 16A			
	multi pin socket outlet in UPS circuit controlled with			
	1No. 16A one way switch in a steel sheet enclosure with			
	8 module top plate including dummies and incidental			
	materials etc.,	2	No	
F	LIGHTING WIRING			
	Supply, fixing, testing & commissioning of the following			
	switch controls in steel sheet enclosure including 3 runs			
	of 1.5sqmm, steel sheet enclosure & modular top plate			
	and all incidental materials etc., complete.			
1	One light Controlled by One Switch	2	No	
2	1 No. 6A socket controlled by single switch	1	No	
G	LIGHTING & FIXTURES			
1	SFTC for the following light fittings with required			
	hardwares such as suspension wires from ceiling, false			
	ceiling, anchor fasteners, chains, bolts, nuts etc.,			
	complete.			
a	36 watts LED light fitting with 2'X2'	1	No	
b	15 watts LED round fitting with LED as 2	4	No	
С	20watts LED Patty fitting	1	No	
Н	DATA POINT			
1	Supply&Laying of CAT 6 Data Communication cable in 2mm thk heavy			
	duty 20mm dia PVC conduit	38	mtr	
2	Supply&Installation,Testing&Commission of Modular type			
	1Nos of RJ45 Female Jack housed in GI anodised metal box			
	with suitable Faceplate fixing the same in the wall/partitions			
	with all accessories etc. as required.	2	No	
I	EARTHING			
1	Providing earthing two numbers , One for ATM and			
	another for AIR-CONDITIONERS including excavating			
	the P.C.C. floor/ earth to 6'0" depth and providing			
	earthing with 50mm dia. G.I. pipe with perforations			
	connected through copper wire including copper flat			
	including copper plate of size 300mm x 300mm, G.I.			
	bolts and filled up with layers of charcoal, salt and			
	earth. (Earth provided for computers shall not be used			
	for any other purpose)	1	No	
2	Supplying and laying of 6 Sqmm multi stranded copper			
	wire for UPS earth in suitable PVC conduit with all			
	incidental materials etc., complete.	20	Mtr	
	Total			

T.PALUR ATM - AIR CONDITIONING WORKS FOR INDIAN BANK (KUMBAKONAM ZONE)

BILL OF QUANTITIES						
Sl.No	Description Of Work	Unit	Qty	Rate	Amount	
1	Supply, Testing and commissioning of					
	indoor and outdoor split air conditioner with remote					
	control, with 3 star rating units and necessary civil					
	works etc., The rate of units is including the supply					
	and laying of 3 mtr of copper pipes with insulations,					
	rubbers, white cements etc., (Brand: Voltas)					
a	1 TR - ATM	2	No			
2	Supply and laying of copper pipes with rubber					
	insulations, rubbers, white cements etc.,	10	Mtr			
3	Supply and installation of Stabilizer for following					
	units					
а	1.0 TR - 4 KVA	2	No			
b	Installation Charges for 1 Tr Split Air Conditioner	2	No			
4	Supply and Installation of Outdoor Stand with					
	necessary civil works	2	No			
5	Supply and laying of PVC Blue pipes for water					
	drain from the indoor units.	15	Mtr			
6	Civil works like cutting AC hole,packing,drain pipe cutting					
	and packing with mortar etc.	1	Ls			
7	Supply and fixing for Timer for A/C Controlled	1	No			
	Airconditioning works Total:					