



**INTERIOR FURNISHING IN INDIAN BANK MID
CORPORATE BRANCH ERODE, 1ST FLOOR 50A/2,
PERUNDURAI ROAD, NEAR ERODE MEDICAL CENTER
HOSPITAL, ERODE – 638011.**

INDIAN BANK

REQUEST FOR QUOTATION (RFQ)

FOR

**INTERIOR FURNISHING WORKS IN INDIAN BANK
MID CORPORATE BRANCH ERODE, 1ST FLOOR 50A/2, PERUNDURAI ROAD, NEAR
ERODE MEDICAL CENTER HOSPITAL, ERODE – 638011.**

Ref:No: ZO:SLM:MCB Erode -01

Date : 23.08.2024

From:

.....
.....
.....

This Bid document contains 17 pages

I N D E X

Sr. No.	DESCRIPTION	PAGE No.
1	INDEX	2
2	NOTICE INVITING QUOTATION	3-5
3	GENERAL RULES AND INSTRUCTION FOR THE GUIDANCE OF BIDDERS	6 - 8
4	TECHNICAL BID	9
5	DECLARATION	10
6	QUOTATION	11 - 16
7	CONCEPTUAL DRAWINGS	17

INDIAN BANK

NOTICE INVITING QUOTATION

Indian Bank, Zonal Office, Salem invites sealed Quotation (Single bid System) for 'Interior Furnishing Works in Proposed Indian Bank Mid Corporate Branch Erode, 1st Floor 50a/2, Perundurai Road, Near Erode Medical Center Hospital, Erode – 638011, from the experienced and technically qualified contractors.

1.	Name of work	Invitation of tender for "Interior Furnishing Works in Proposed Indian Bank Mid Corporate Branch Erode, 1 st Floor 50a/2, Perundurai Road, Near Erode Medical Center Hospital, Erode – 638011 from the experienced and technically qualified contractors.
2.	Estimated cost of work	Rs.8.90 Lakh
3.	Period of completion	20 days reckoned from the date of issue of the Work Order
4.	Validity of Quotation	60 Days from the date of opening
5.	Defects Liability Period	6 Months from the date of virtual completion of work
6.	Initial Security Deposit (I.S.D)	2% of the Quoted Value.
7.	Retention Money/ Security Deposit	5% of the Final Bill Amount (No interim bill will be permitted).
8.	Retention Money/ Security Deposit period	Retention Money will be paid after expiry of defect liability period of one year from the date of payment of final bill.
9.	Liquidated Damages	1% per week of the Contract Value for the delay subject to a maximum total of 5% of Contract value
10.	Tender Documents	The Tender Documents can be downloaded from the Bank's website (www.indianbank.in under Tenders column)
11.	Cost of Tender Document	Nil
12.	Earnest Money Deposit	Nil
13.	Last date of submission of RFQ	29.08.2024 upto 16.00Hrs. at Indian Bank, Zonal Office, Premises, Estate & Expenditure dept, Third Floor, No. Divya Towers, Shevapet, Salem, 636 001.
14.	Date of opening RFQ	29.08.2024 at 16.30Hrs. at Indian Bank, Zonal Office, Premises, Estate & Expenditure dept, Third Floor, No. Divya Towers, Shevapet, Salem, 636 001.

Note:

1. Technical bid and Price bid should be submitted in single sealed covers.
2. The bank reserves the right to reject any tender/bid without assigning any reason.
3. The rates quoted by the tenderer shall be based only on the specifications and conditions of the tender documents.
4. Bank is not liable to make any payment to tenderers for preparation to submit the tender/bid.

DEPUTY GENERAL MANAGER (P&E)

Indian Bank, Zonal Office, Salem,
Third Floor, Divya Towers,
Shevapet, Salem – 636 001.
Ph: 0427 – 2216499.
Email: zosalem@indianbank.co.in

Signature & Seal of the Tenderer

Note:

1.0 GENERAL

Bidders are advised to acquaint themselves fully with the description of work, scope of services, time schedule and terms and conditions including all the provisions of the RFQ document before firming up their Quotation.

Though adequate care has been taken while preparing this RFQ Document, the Bidders shall satisfy themselves that the document is complete in all respects. Intimation of any discrepancy shall be given to this office immediately. If no intimation is received from any Bidder within the last dated of submission of RFW, it shall be considered that the Tender Document is complete in all respects.

2.0 SUBMISSION OF BID

The Bidders shall submit their quotation in line with this RFQ Document.

RFQ Document should be in a proper sealed envelope superscripted as “Interior Furnishing Works in Proposed Indian Bank Mid Corporate Branch Erode, 1st Floor 50a/2, Perundurai Road, Near Erode Medical Center Hospital, Erode – 638011.

More than one bid from same owner shall be summarily rejected.

3.0 SITE PARTICULARS

Bidders are advised to inspect and examine the site and its surroundings between **10 am to 5 pm** on any of the working days of the Bank and satisfy themselves before submitting their bids as to nature of work, site conditions, flooring conditions, means of access to the site etc. Non-familiarity with the site conditions will not be considered a reason either for extra claims or for not carrying out the work in strict conformity with the specifications. For site visit you may contact Branch Manager (Erode Branch) in 0424-2253268.

4.0 SCOPE OF WORK

4.1 “Interior Furnishing Works in Proposed Indian Bank Mid Corporate Branch Erode, 1st Floor 50a/2, Perundurai Road, Near Erode Medical Center Hospital, Erode – 638011”.

4.2 Rates quoted shall be deemed to be inclusive of manpower, material, machinery, tools and tackles, installation, all taxes (except GST), duties, cartage, freight loading & unloading, insurance etc.

4.3 No escalation of whatsoever nature shall be payable in future.

4.4 Only GST will be paid by the Bank. Any other tax shall be payable by the contractor.

4.5 Bank reserves the right to modify/ relax/ withdraw any of the terms and conditions of the contract if it is found necessary in the interest/ benefit of the Bank.

4.6 Prospective Bidders are requested to remain updated for any notices / amendments/ clarifications etc. to the Tender Document through our Banks website. No separate notifications will be issued for such notices / amendments / clarifications etc. in the print media or individually.

4.7 The contract as a whole or part thereof is NON TRANSFERABLE.

5.0 MINIMUM ELIGIBILITY CRITERIA

- 5.1 The bidder should be in Business for the Past 3 Years.
- 5.2 Self attested Copy of GST & PAN number.
- 5.3 24 x 7 local service set –up in Salem or inTamilnadu (address proof to be furnished).
- 5.4 Affidavit/ undertaking certifying that the firm has not been blacklisted by anyone (page -10 of this RFQ).

The contractor should have the technical competence, sound financial resources, experience, equipments, manpower and reputation to perform the contract to the satisfaction of Bank.

6.0 EVALUATION CRITERIA/ FINAL SELECTION

- 6.1 Bids submitted without the requisite documents for 5.0 (Minimum Eligibility Criteria) will be summarily rejected and the price quoted by them will not be considered for evaluation. Qualified parties have no right to claim for award of the work. Bank reserves the right to cancel or award the work to any party / Bidder. Bidders who wish to attend the opening of the bids may ensure their presence on the mentioned date and time as specified in the Date sheet.
- 6.2 The lowest bidder (L-1) shall be considered for award of work, though not binding and the decision of the Bank in this regard will be final and binding.
- 7.0 The bank reserves the right to reject any tender/ bid without assigning any reason.
- 8.0 The rates quoted by the bidder shall be based only on the specifications and conditions of the bid documents.
- 9.0 Bank is not liable to make any payment to bidders for preparation to submit the tender/bid.

DEPUTY GENERAL MANAGER (P&E)

Indian Bank, Zonal Office, Salem,
Third Floor, Divya Towers,
Shevapat, Salem – 636 001.
Ph: 0427 – 2216499
Email: zosalem@indianbank.co.in

GENERAL RULES AND INSTRUCTION FOR THE GUIDANCE OF BIDDERS

1. Bids, which should always be placed in sealed cover, with the name of the work written on the envelope “Interior Furnishing Works in Proposed Indian Bank Mid Corporate Branch Erode, 1st Floor 50a/2, Perundurai Road, Near Erode Medical Center Hospital, Erode – 638011’ will be received by Deputy General Manager, Indian Bank, Zonal Office, Salem, Third Floor, Divya Towers, Shevapet, Salem – 636 001.
2. The Indian Bank does not bind itself to accept the lowest or any quote/ bid and reserves to itself the right of accepting the whole or any part of the quote/ bid and the tenderer/ bidder shall be bound to perform the same at the rate quoted.
3. The rate quoted by the Tenderer/ bidder shall be net, up to the stage of incorporation and handing over site. All taxes on material or on finished works like work’s contract tax, Turn-over Tax, including taxes that may be newly introduced subsequent to the tender/ bid etc. in respect of this contract shall be payable by the Tenderer/ bidder and the Indian Bank will not entertain any claim whatsoever in this respect except the GST to the overall bid amount.
4. The Tenderer/ bidder shall give a list of his relatives working with the Indian Bank along with their designations and addresses.
5. No employee of the Indian Bank is allowed to work as a contractor for a period of two years of his retirement from Indian Bank service, without the previous permission of the Indian Bank. The contract is liable to be cancelled if either the contractor or any of his employees is found at any time to be such a person who had not obtained the permission of the Indian Bank as aforesaid before submission of the tender/ bid or engagement in the Tenderer/ bidders service.
6. The tender/ bid for works shall remain open for acceptance for a period of 60 days from the date of opening of Tender/ bid. If any tenderer/ bidder who withdraws his tender/ bid before the said period, then the Indian Bank shall be at liberty to debar the contractor from the panel.
7. **Retention money shall be deducted from the final bill @ 5 % of the gross value of the bill.** This will be refunded after completion of the Defect Liability Period of 12 months, provided he has satisfactorily carried out all the work and attended to all the defects in accordance with the conditions of the contract. No interest is allowed on retention money.
8. The acceptance of a quote will rest with the Indian Bank and the Indian Bank reserves to itself the authority to reject any or all of the quotes received without the assignment of a reason. Quotes in which any of the prescribed conditions are not fulfilled (or) are incomplete in any respect are liable to be rejected. The Indian Bank reserves the right to accept the quote in full or in part and the tenderer/ bidder shall have no claim for revision of rates or other conditions if his quote is accepted in parts.
9. Canvassing in connection with quotes is strictly prohibited and the tenders/ bids submitted by the Tenderer/ bidders who resort to canvassing will be liable to rejection.

All rates shall be quoted on the proper form of the quote alone. **All the entries to be made legibly in ink only.** Rates written in pencil or any other mode shall not be considered for evaluation and will be rejected.
10. An item rate quote containing percentage below/ above will be summarily rejected. However, where a tenderer/ bidder voluntarily offers a rebate for payment along with sealed quote, the same may be considered.
11. On acceptance of the tender/ bid the name of the accredited representative(s) of the Tenderer/ bidder who would be responsible for taking instructions from the Indian Bank shall be communicated to the Indian Bank.

12. Special care should be taken to write the rates in figures as well as in words and the amounts in figures only, in such a way that interpolation is not possible. The total amount should be written both in words and in figures.
13. The Contractor shall comply with and give all notices required under any law, rules, regulations, or bye-law of Parliament, State Legislature or Local Authority relating to works. If needed, the Contractor has to obtain required permission/ approval from the required statutory bodies/ organizations.
14. The Contractor shall be required to maintain the site and the building areas in a neat and clean condition at all times to the satisfaction of the Employer. The Contractor shall especially take care of their materials free from getting drenched or damaged.
15. Debris and unwanted items have to be neatly stacked at site and then periodically removed (maximum of one week), carried away by the Contractor and disposed off as per the rules and regulations of the Local Authorities concerned. No debris shall be thrown loose from upper floors. No floor, roof or other part of the building shall be over-loaded with debris or materials as to render it unsafe.
16. Employer reserves the right to insist on selection of material, workmanship, detailing and finishes, paint which they consider, is appropriate, and suitable for the intended use. The contractor is not eligible to claim extra on this account.
17. Employer will require the contractor to produce, samples of all the materials, accessories/ finishes prior to procurement/ manufacture. The samples of the materials for the work shall be got approved from the Employer. Failure to comply with these instructions can result in rejection of the work/ materials.
18. The Tenderer/ bidder should note that he should execute his part of work without causing any damage to any component of the building and also without disturbing the occupants or other contractors. Any damage so caused shall be made good at the cost & risk of the tenderer/ bidder.
19. The successful tenderer/ bidders shall include, in the quoted price, all allied works and no extra payments will be made for any such case arises.
20. **The successful contractor shall also be responsible for the safety and security of all their men & materials** and also for ensuring fire prevention steps at all times in the working premises including their part of the work. The successful contractor has to place full time representative at site, the representative should have thorough subject knowledge. **Bank will not be responsible for any untoward accident caused by the negligence of the contractor.**
21. **Only one interim bill will be permitted after completion of works.** The bills in proper forms must be duly accompanied by detailed measurements in support of the quantities of work done and must show deductions for all previous payments, retention money etc. The Employer after detailed scrutiny of the interim bill shall certify full payment within **10 days** of the date of receipt of bill from the Contractor subject to submission of documentation as required.
22. **The contractor should ensure payment of minimum wages + VDA to all laborers / workmen staff employed by him inline with central/ state labour wage act whichever higher.**
 - a) The Contractor shall at all times indemnify and keep indemnified the Employer against all losses, claims, damages or compensation including under the provisions of the payment of the Wages Act 1936, Minimum Wages Act 1948, Employer's Liability Act 1938, Workman's Compensation Act 1923, the Maternity Benefit Act 1961, the Bombay Shops and Establishments Act 1947, Industrial Disputes Act 1947, and Contract Labour (Regulation and Abolition) Act 1970 and Employees State Insurance Act 1948, Motor Vehicles Act 1988 or any modifications thereof or under any other law relating thereto and rules made there under from time to time or as a consequence of any accident or injury to any workman or other

person in or about the work whether in the employment of the Employer or Contractor or not, and also against all costs, charges and expenses of any suit, action or proceedings whatsoever out of such accident or injury or combination of any such claims.

23. The contractor shall effect the insurance necessary and indemnify the Employer entirely from all responsibility in this respect. The insurance must be placed with a Insurance Company approved by the Employer and must be jointly in the name of the contractor and the Employer and the policy lodged with the latter. The scope of insurance is to include damage or loss to the contract itself till this is made over in a complete state. Insurance is compulsory and must be effected from the very initial stage. The contractor shall also be responsible for anything which may be executed from damage to any property arising out of incidents, negligence, or defects carrying out of this contract.
24. The Employer shall be at liberty and is hereby empowered to deduct the amount of any damages, compensations, costs, charges and expenses arising or accruing from or in respect of any such claim for damages from any sums due or to become due to the contractor.
25. The contractor shall maintain all registers as required by the Regional Labour Commissioner and should furnish the same to the Bank or its representative as and when required.
26. If the work is not started within **4 days** from the date of issue of work order then Employer may terminate the work order without assigning any reason. If during the execution of the work, the progress of work is not considered to be satisfactory; and not in proportion to the commitment made, inconsistent with the period of completion of the work provided in the Time schedule, then the Bank may terminate the work order by giving an immediate final notice to the contractor.
27. The time allowed for completing the works is **20 days** to be reckoned from the date of Work Order. Tenderer/ bidders shall submit a programme (time schedule) for executing the entire project and shall furnish the details of their scheme indicating the proposed deployment of their machinery and resources.
28. If the Contractor fails to complete any or all the works by the date/s named in "Date of Completion" or within any extended time (in case Bank Permits) then the Contractor shall pay or allow the Employer the sum to be worked out at **1.0%** of contract value per week to be recovered as Liquidated Damages (and not by way of penalty) for the delay, beyond the said date or extended time, as the case may be, during which the works shall remain unfinished and such damages may be deducted from any moneys due or which may become due to the Contractor. The maximum amount of Liquidated damages shall be **5%** of contract value. The contractor shall be bound to extend validity of Insurance Cover till such period of completion as may be considered necessary at their cost.

DEPUTY GENERAL MANAGER (P&E),

Indian Bank Zonal Office Salem,
Third Floor,
Divya Towers, Shevapet,
Salem – 636 001.

Signature & Seal of the Bidder

DETAILS

S. No.	Particulars	Details to be filled
1	Name & Designation of Contact Person	
2	Mobile No (s) of the Contact Person / Firm	
3	Address for Communication	
4	Office / Local service set-up in Chennai address	
5	E-mail address of Contact Person / Firm	

(Signature of Authorized Signatory)

Name & Designation

Contact No.

NAME OF THE AGENCY WITH SEAL



**INTERIOR FURNISHING IN INDIAN BANK MID
CORPORATE BRANCH ERODE, 1ST FLOOR 50A/2,
PERUNDURAI ROAD, NEAR ERODE MEDICAL CENTER
HOSPITAL, ERODE – 638011.**

DECLARATION

To

DEPUTY GENERAL MANAGER (P&E)

Indian Bank, Zonal Office, Salem,
Third Floor, Divya Towers,
Shevapet, Salem – 636 001.

I hereby declare as below:

- 1) All the information furnished by me/ us here above is correct to the best of my knowledge and belief.
- 2) I/We have no objection if enquiries are made about the work listed by me/ us in the accompanying sheets/ annexures.
- 3) I/We agree that the decision of Indian Bank in selection of L-1 bidder will be final and binding to me/ us.
- 4) I/We hereby confirm that my/ our firm has not been disqualified / debarred / blacklisted by any Governments, Semi-governments, PSUs, Banks including any of the Offices/ Branch of Indian Bank/ erstwhile Allahabad Bank as on the date of publication of this notice.
- 5) I/We hereby confirm that all information, particulars, copies of certificates and testimonials submitted are correct and genuine. I am / We are, therefore, liable to face appropriate actions as deemed fit by the Indian Bank in the event of any of the information, particulars, copies of certificates and testimonials are not found correct and genuine.

PLACE :

DATE:

NAME & DESIGNATION

NAME OF THE TENDERER WITH SEAL

**Quotation
Price Bid**

Schedule of Quantities

Interior Furnishing works					
S.No	FURNISHING WORK	Qty	Unit	Rate	Amount
	FALSE CEILING				
1.	Providing, fabricating and erecting in position totally flushed suspended false ceiling with 12.0mm thick Gypsum board, fixed to a metal frame work comprising of ceiling channel of size 80mmx26mmx0.5mm @ every 457cm centre, inter channel 45mmx15mmx0.9mm @ every 1220 cm centres, peri-meter channel 20mmx26 mm all along the wall/partitions, strap hanger suspenders 25mmx0.5mm with nuts and bolts 6.4mmx12.7mm, connecting clips 2.6mm thick, dry walls screws 25m long, soffit cleats 27mmx37mmx25mmx1.6mm thick and dash fasteners / rawl plugs 12.5 mm diax35mm long with 6mm dia bolts etc. complete with recommended fillers, paper tapes and applying two coats of acrylic emulsion paint of approved shade and make over a coat of primer including making necessary cut outs for light fittings/ ACs etc. complete as per manufacture's specifications. (Quantity as per layout plan/site requirement).	Sqft.	1150		
2.	Providing and fixing 600 mm x 600 mm mineral fiber tiles false ceiling of Armstrong/Gypboard/equivalent approved make of micro look system including suspension system as per manufacturer's specifications and instructions of Architect/ Engineer complete in all respects including making cutouts where necessary for electrical lighting fittings etc. complete all as directed by the Bank. (Quantity as per layout plan/site requirement)	Sqft.	400		
	WALL PANELING/ COLUMN ENCASING: -				
3.	Supplying and erecting Wall paneling / Column encasing (up to false ceiling) as per drawing and design and conforming to the following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: To be finished with 6 mm thick BWP grade plywood on face.	Sqft.	150		

	<p>Finishing: 1.0mm thick laminate sheet of same or combination shades with grooves as per instructions. Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. Note: Quoted rates shall include all necessary materials, accessories and labour and also for making provisions for electrical/telephone/computer wiring, conduits and switch boxes, etc. wherever required. (quantity/location should be restricted only to the central pillars in Bankinghall / to hide electrical pipes / AC drain pipes / any prime location)</p>				
	PARTITION				
4	<p>Supplying and erecting full height opaque / solid partitions (up to false ceiling height) as per following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: To be finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves in both faces as per instructions. Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits, switches etc. shall be separately paid for)</p>	Sqft.	775		
5	<p>Supplying and erecting full height partly glazed for BM cabin side partition portion respectively as per following specifications: Basic frame work: Framing shall consist of Heavyduty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1200 mm) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply Skin membrane: (Opaque portion up to 900mm from floor level and from 2100mm to ceiling, finished with 6mm thick BWP grade plywood on</p>	Sqft.	250		

	<p>each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves as per instructions. Glazing: 12mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm). (for BM cabin side partitions) Top Border: 150mm high laminate of approved make & shade all as directed. Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits & switches etc. shall be separately paid for).</p>				
6	<p>Supplying and erecting Low height partly glazed upto a height of 5 feet as per following specifications: Basic frame work: Framing shall consist of Heavyduty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1200 mm) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply Skin membrane: (Opaque portion up to 1200mm from floor level, finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves as per instructions. Glazing: 12mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm). (for BM cabin side partitions) Top Border: 150mm high laminate of approved make & shade all as directed. Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits & switches etc. shall be separately paid for).</p>	Sqft	150		
7	<p>COUNTERS/ WORKSTATIONS: - Providing and erecting in position Work Station of approx. Size 1350x750x750mm (4'6"x2'5"x2'5"), Table Top made of 19mm thick block board pasted with 1.00mm laminate on top. The sides shall be made of 19mm thick BWP grade block board finished with 1.00mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished steam beach wood mouldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed.</p>	RFT	36		

	Each workstation shall comprise of the drawer unit, with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S.S. handles of approved quality. Inner face of the workstation shall be finished with 0.8mm white laminate. Skirting: 100mm high laminate of approved make & shade all as directed.				
8	BM Table: - Providing and erecting in position Work Station of approx. Size 1500x750x750mm (5'x2'5"x2'5") with side table of size 900 x 450 x 750mm (3'x1'6"x2'6"), Table Top made of 19mm thick block board pasted with 1.00mm laminate on top. The sides shall be made of 19mm thick BWP grade block board finished with 1.00mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished steam beach wood mouldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed. Each workstation shall comprise of the drawer unit, with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S.S. handles of approved quality. Inner face of the workstation shall be finished with 0.8mm white laminate. Skirting: 100mm high laminate of approved make & shade all as directed.	RFT	5		
9	Supplying and erecting Conference Table of size (2100 x 1050 x 750mm) 7' x 3'6" x 2'6". Table Top made of 19mm thick block board pasted with 1.00mm laminate on top. The sides shall be made of 19mm thick BWP grade block board finished with 1.00mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished steam beach wood mouldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed. Each workstation shall comprise of the drawer unit, with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S.S. handles of approved quality. Inner face of the workstation shall be finished with 0.8mm white laminate. Skirting: 100mm high laminate of approved make & shade all as directed. Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of 'Earl Behari' or equivalent approved make.	RFT	7		
10	Providing fabricating & fixing in position twin -stile door / single door at Main Entrance of				

	Branch made of well-seasoned teak wood of size 100 x 50 mm or anodized/powder coated Aluminium sections of required size on frame, top & bottom rail and 12mm thick glass (Modi/ Saint Gobain make) including fixing the frame to brick wall/RCC/wooden surfaces with necessary fasteners to have proper fixing including all incidentals etc complete. Glass to be fixed in the grooves of the teak wood/al. sections with necessary materials/beading etc. The job also includes cost of providing & fixing heavy duty double action hydraulic floor spring (ISI mark) in the floor, fixing the door on it, including necessary fixing materials on the lintel/bottom, bolts, locks & satin finish stainless steel decorative tubular handles(approx.300mm long) on both faces complete as per drawing and instructions. The exposed teak wood surfaces to be polished in approved shade N.C lacquer in mat satin finish. The rate should also include cost for decorative etching on the glass.				
a)	Openable portion	Sqft.	35		
b)	Fixed portion	Sqft.	40		
	CUPBOARDS / STORAGE CABINETS / TABLE SIDE UNITS :-				
11	Providing and erecting in position low / full height Storage cabinet Made of 19 mm thick BWP grade block board including intermediate shelves as per direction, lockable shutters etc. conforming to following specifications: Shutter faces shall be finished with 1mm thick laminate of same or combination shades as per instructions with polished white or steam beech wood (6mm thick) edge lipping and 100mm high teak wood skirting duly polished / painted as directed. Inner faces of cabinet including shutters shall be painted in approved shade. Shutters will be hung by auto-closing hinges, locks, magnetic door catcher and satin finished S.S. handles etc. of approved make. (Payment will be on the area of cabinet face). Skirting: 100mm high laminate of approved make & shade all as directed. Note:- Quantity to be to be restricted to bare minimum as per actual requirement being costly item & to be provided in open area in Banking hall & not in store room. Store room may be provided with steel racks) (Actual face area will be measured for payment purpose.)				
a)	Maximum 400mm deep x 900 mm high	Sqft.	65		
b)	Maximum 400mm deep x 2700 mm high	Sqft.	150		



INTERIOR FURNISHING IN INDIAN BANK MID CORPORATE BRANCH ERODE, 1ST FLOOR 50A/2, PERUNDURAI ROAD, NEAR ERODE MEDICAL CENTER HOSPITAL, ERODE – 638011.

12	Vertical Blinds - Supplying and fixing Vertical blinds for windows with all necessary fixing accessories, arrangements and etc. Cost include beaded chain, fabric and etc. Make Alta vista and Marvel. Cost include wastages, transports, loading, unloading charges, labours, materials, tools, lead, lift and etc. Complete as per instructions of the Architect.	Sqft	120		
13	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edges. The upper portion of the shutter is to be provided with 6 mm thick clear float glass fixed with white steam beech wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g. mortise lock, hinges, handles, door closer etc. of approved make and quality. (Manager cabin door)	Sqft	63		
14	Total amount (excluding GST)				
15	GST @ %				
16	Gross Total				

Total Amount in words: Rupees _____ only +

applicable GST.

(Amount excluding of GST but including discount, if any will be considered for evaluation of financial bid)

Place:

Date:

INTERIOR FURNISHING IN INDIAN BANK MID CORPORATE BRANCH ERODE, 1ST FLOOR 50A/2, PERUNDURAI ROAD, NEAR ERODE MEDICAL CENTER HOSPITAL, ERODE – 638011.

