

Schedule of Quantities for Interior/Furnishing work of IGSS Lucknow

Sl. No.	Description of Item	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
	FALSE CEILING				
2	Providing and fixing 600 mm x 600 mm mineral fiber tiles false ceiling of Armstrong/Gypboard/equivalent approved make of micro look system including suspension system as per manufacturer's specifications and instructions of Architect/ Engineer complete in all respects including making cutouts where necessary for electrical lighting fittings etc. complete all as directed by the Bank. (As per site requirement)	Sft	1200		
5.	<p>Supplying and erecting full height partly glazed/ partitions for ZM cabin side partition/ cash back side portion respectively as per following specifications:</p> <p>Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity.</p> <p>Exposed frame members in the glazed portions shall have wider spacing (approx. 1200 mm) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply.</p> <p>Skin membrane: (Opaque portion up to 900mm from floor level and from 2100mm to ceiling, finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions.</p> <p>Finishing: 1.0mm thick laminate of same or combination shades with grooves as per instructions.</p> <p>Glazing: 6mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm).</p> <p>Al. grill: Readymade anodized aluminium grill of approved design and quality fixed with continuous teak wood / steam beach beads of approved shape (finished 35 x25mm) duly polished by NC lacquer finish. (for Cash Cabin Side Partitions)</p> <p>Skirting- 100mm high laminate of approved make & shade all as directed.</p> <p>Top Border: 150mm high laminate of approved make & shade all as directed.</p>	Sft.	220		

	Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits & switches etc. shall be separately paid for)				
7.	<p>Supply and erecting low height opaque partitions (up to maximum 1200mm height) conforming to the following specifications :</p> <p><u>Basic frame work:</u> Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity.</p> <p><u>Skin membrane:</u> 6 mm thick BWP grade ply on each face up to 900mm height.</p> <p>Glazing: 10mm glass in remaining portion,</p> <p><u>Finishing:</u> 1.0-mm thick laminate of same or combination shades with grooves as per instructions.</p> <p><u>Edge moulds:</u> All free top/ end surfaces shall have polished teak / steam beech wood moulds of approved shape (from 18 x 50mm sections).</p> <p><u>Skirting-</u> 100mm high laminate of approved make & shade all as directed.</p> <p>Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical / telephone/computer wiring, conduits and switch boxes, etc. (Materials for wiring, conduits and switch boxes shall be separately paid for.)</p>	Sft	120		
	COUNTERS/WORK STATIONS:-				
11.	<p>Supplying and erecting clerical counters (running tables) 600mm deep and 750mm high including drawer-cum-cabinet unit for files, space for computer CPU, wire managers, modesty panel, tea tray etc. made with 19mm thick BWP grade block board on top and supporting sides / front with necessary well seasoned Malaysian Sal/ Kail/ Mirandi wood frame work, finished on top with 1.0 mm thick laminate of approved shade and quality, including providing and fixing 450mm long key board tray of approved shade, hardware and accessories at each of the counter. All exposed edges of block board are to be provided with half round teak wood mouldings, duly polished and 100mm high laminate of approved make & shade all as directed.</p> <p>Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer.</p> <p><u>Skirting:</u> 100mm high laminate of approved make & shade all as directed.</p> <p>Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of 'Earl Behari' or equivalent approved make.</p>	Rft	70		

12.	Providing and fixing 1'-6" high, 12mm thick clear float glass railing on clerical counters with S. S. decorative posts of 50mm dia all as directed by the Bank.	Sft.	65		
	DOORS:-				
14	Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edges. The upper portion of the shutter is to be provided with 6 mm thick clear float glass fixed with white or steam beech wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g. mortise lock, hinges, handles, door closer etc. of approved make and quality	Sft.	25		
	CUPBOARDS / STORAGE CABINETS / TABLE SIDE UNITS:-				
17	Providing and erecting in position side cabinet units with shutters of approx size of 400mm deep x 700mm high made of 19mm thick BWP grade block boards including intermediate shelves as per drawing / instructions. Exposed surfaces shall be finished with 1.00mm laminate of approved shade and make. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Free edges of block board shall be finished with polished white or steam beech wood half round moulds (out of 20 x 20 mm sections). Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. <u>Skirting:</u> 100mm high laminate of approved make & shade all as directed. Quoted rates shall include cost of necessary hardware, viz handles, locks with keys in duplicate, etc. (Actual face area will be measured for payment purpose.)(to be put on table's side)	Sft	8		

TABLES:-					
18.	<p>Providing and erecting in position tables as per drawing and conforming to the following specifications :</p> <p>Structure of 19mm thick block board for sides, top and modesty panel, finished with 1.00 mm thick laminate of approved shade and make including drawer–cum-cabinet unit, CPU Trolley, modesty panel, tea tray ,wire managers, 450mm long key board tray, hardware and accessories etc complete. All exposed edges of block board are to be provided with half round teak wood moldings, duly polished.Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Rate to include charges for brass hardware fittings as well as fixtures like sliding gear for drawers of 'Earl Behari' or equivalent approved make.of size</p> <p>a) 1524 x 750 x 750 mm (5.0'x 2.5'x 2.5')</p> <p>b) 1144 x 750 x 750 mm (3.75'x 2.5'x 2.5')</p> <p>c) 1830x750x750mm (6.0'x 2.5'x 2.5')</p>	Each	1		
		Each	10		
		Each	1		
TOTAL (FURNISHING)					
GST					
GRAND TOTAL (FURNISHING)					
<p>List of approved make:</p> <p>1. Block Board: Century /Kitply/ Green (BWP Grade)</p> <p>2. Ply Board: Century /Kitply /Green (BWP Grade)</p> <p>3. Laminates:</p> <p>a) For Partitions/Tables/Counter Surface:- Century:303- Bodensee Beech, Sunmica : E-224/1224-Steam Beech, Formica-FI-1224(SF)-Steam Beech-I, Greenlam : 685-Swiss Pear</p> <p>b) For Border & Skirting:- Century:191- Radiant Red, Sunmica : G-448/1448-Teracotta, Formica- FI-1517(SF) Sienna, Greenlam: 165- Light Red</p> <p>4. Glass: Modi/Saint Gobin/ Indo Asahi/Triveni</p> <p>5. Gyp Board: India Gypsum or equivalent approved.</p> <p>6. Locks/Handles: Godrej/Harrison/Vijayan or equivalent approved.</p>		<p>7. Drawer Sliding Fittings: Earl Bihari (EBCO)/Godrej/Blum or equivalent approved.</p> <p>8. Floor Spring/Door Closer: Sandhu / Hemco / Hardwin or equivalent approved.</p> <p>9. Other materials: ISI mark & approved by the Bank.</p>			

Schedule of quantity for electrical work in IGSS Lucknow

Sl. no.	Description of Items	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Supplying and drawing circuit line by 2x4sqmm+1 2.5sqmm FRLS PVC insulated copper wire by 19mm pvc pipe fully concealed and mending good all the damages) (for AC)	Rmt	120		
2	Supplying and drawing circuit line by 2x2.5sqmm+1 1.5sqmm FRLS PVC insulated copper wire by 19mm pvc pipe fully concealed and mending good all the damages).(For circuit wiring)	Rmt	250		
3	Making point wiring for fan & light by 2x1.5 Sqmm + 1x1sqmm FRLS PVC insulated single core copper wire by 19mm pvc in concealed manner including modular type switch & socket 6Amp, M.S.box, Top plate and cover plate.				
	a) Single point controlled by single switch.	Each	20		
	b) Double point controlled by single switch.	Each	10		
	c) Plug point 6Amp	Each	20		
	d) Call bell point	Each	2		
4	Supplying and fixing 2Nos 3pin 6Amp Socket and 1No 15Amp controlling switch of modular type and connection including M.S box, cover plate and top plate in one board.	Each	10		
5	Supplying and fixing 3Nos 3pin 6Amp Socket and 3Nos controlling switch of modular type including M.S box box cover plate and top plate in one board.	Each	32		
6	Supply and Installation of following light fixture complete with lamps, tubes, fixing arrangement in false ceiling including making connection etc.				
	a) LED light fixture recessed type 2'x2'	Each	20		
	b) LED Down lighter	Each	10		
	c) Wall Bracket Fan/Ceiling fan	Each	10		
7	a) Supply and drawing LAN-cable CAT-6 (D-link or eqv. make) in the PVC pipe.	Rmt	600		
	b) Termination of LAN-Cable in one end by RJ45 Computer Jack & mounting of modular type including supplying and fixing suitable I.O Box in concealed manner (D-link, Roma, Crabtree, MK or eqv. Make in suitable enclosures)	Each			

8	Supply & Fixing patch chords(Cat-6) D-link or eqv.make a) 3'long	Each			
	b)Termination of LAN-Cable in other end byRJ45 socket.	Each			
	TOTAL AMOUNT(ELECTRCIAL)				
	GST				
	GRAND TOTAL (ELECTRCIAL)				
	<p><u>List of Approved Make:-</u> PVC insulated Copper Wire (FRLS grade) : Finolex/Polycab/Havels/RRKabel Electric Cables : Havels/Gloster ELCB + MCB or RCCB : L&T//Siemens/GE/Havels/MDS/MerlinGerin/Leagrand MCBs/MCCBs/DBs : L&T//Siemens/GE/Havels/MDS/MerlinGerin/Leagrand ModularSwitches/Sockets : AnchorROMA/Crabtree/M.K. PVC Conduit/Pipe : AKG/Precision/Prestoplast/Asian Earthing for Bldg.& UPS : EarthElectrodeasperIS:3043-1978/ChemicalEarthing (Earthingresistanceshouldbelessthan2Ohms) Telephonecable : Delton/ITL/Polycab/Finolex/RRKabel Changeover Switch : KEW Lugs : Dowells/Jainson/Equ. LowTensionSFUwithHRCfuse:L&T/Siemens Metal CladSockets :Siemens/MDS/Equ.</p>				