



PREMISES DEPARTMENT
ZONAL OFFICE JHANSI

TENDER DOCUMENT
INTERIOR FURNISHING WORKS IN NEW PREMISES OF
INDIAN BANK –JALAUN MAIN BRANCH & ATM, DISTRICT – JALAUN

PART II – FINANCIAL BID

Ref:No : ZOJHI:PRM:2024-25:22

Date : 06/01/2025

Issued to:

.....
.....
.....

Last date for submission of Bid	20/01/2025 upto 15:00 HRS at Indian Bank, Zonal Office Jhansi, Premises Department, 92, Civil Lines, Bank Chauraha, Jhansi - 284001
Date of Opening of Technical Bid	20/01/2025 at 16:00 HRS at Indian Bank, Zonal Office Jhansi, Premises Department, 92, Civil Lines, Bank Chauraha, Jhansi - 284001
Date of Opening of Financial Bid	To be intimated separately to the Firms Qualifying in Technical Bids

CONSULTANT:

M/s Bharat and Associates
Architects, Engineers, Interiors &
Landscape Designers,
Shop no-1, First Floor, Jeevan Plaza
Viram Khand-5, Gomti Nagar, Lucknow-226010

Mobile No : .7572003101,6394392325

Email – E-Mail: bharatandassociateslko@gmail.com

SCHEDULE OF QUANTITIES

**TENDER FOR INTERIOR FURNISHING WORK IN NEW PREMISES OF INDIAN BANK – JALAUN MAIN BRANCH PREMISES,
DISTRICT – JALAUN**

B.O.Q OF INTERIOR FURNISHING WORK FOR INDIAN BANK BRANCH AT JALAUN MAIN					
A	SCHEDULE - 'A' (FURNISHING WORK)				
S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMT
1	SUSPENDED FALSE CEILING				
1.1	FALSE CEILING WITH COVE(GYPSUM BAORD)	Sq.Ft.	550.00		
	<p>Providing and fixing Gypsum false ceiling as per drawing including of providing and fixing G.I. Frame work shall comprise of G.I. perimeter channel (MF-6A) of size 0.50mm thick having one flange of 19.6mm and another flange shall be of size 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw fixed to the beam to the required curvature with nylon sleeves and screws at not exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent to the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc.</p> <p>The joints to be properly mended with paper tapes and gypsum compound all complete. The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work to be completed as per specification , approval of the bank. No Drop or design(if any)will be considered as extra measurement it will be considered flat ceiling. (Only plan area to be measured for payment) .No extra payment will be made for the cutting of light points , stain glass,cove lighting etc. The measurement will be taken in one level , rate should include the drops also, no extra amount will be paid for the drops.</p>				
1.2	FALSE CEILING (ARMSTRONG CEILINGS – FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL)	Sq.Ft.	605.00		
	<p>Providing and fixing false ceiling system manufactured by M/s. Armstrong World Industries using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height, having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm, having 0.33 mm gauge at every 600 mm. c/c. and wall angle of size 19 x 19 mm., having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c. in both directions using 2.0 mm. thick pre-straightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID(BLACK REVEAL) ceiling tiles manufactured by M/s. Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55, Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/mOK, Humidity Resistance of 99% , having Fire Performance CLASS O /</p>				

	CLASS 1 (BS 476), surface having 3 coats of white paint with Fine Fissured, back of the tile duly sanded and finished with a coat of protective paint over the formed grid complete.(Branch & ATM) .				
	TOTAL OF SUSPENDED FALSE CEILING				
2	PARTITIONS WORK				
2.1	FULL / LOW HEIGHT SOLID PARTITION				
	<p>CASH CABIN PARTITIONS : Supplying & Erecting full height solid cash cabin partitions (upto false ceiling as per following specifications : Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: To be finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves in both faces as per instructions. Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. It shall have decorative aluminum grill (from 1200mm to 2100mm) fixed with teak wood beading (size – 30mm x 20mm, as per profile) with melamine finish. The job shall also include for provision of laying conduits, switch boxes etc. The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete up to the satisfaction of the Architect. All door opening shall have rebated teak wood framework (size – 75mm x 50mm, as per profile) on vertical (2 Nos.) and horizontal (1 No.) sides, with melamine finish and rebate of 40mm x 12mm, all complete up to the satisfaction of the Architect. Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits, switches etc. shall be separately paid for) Framework shall be rigidly secured to floor, bottom of slab & existing walls at 2'-0" c/c with dash fasteners.</p>	Sq.Ft.	155.00		
2.2	<p>Supplying and erecting full height partly glazed / unglazed partitions as per following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminum Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1200 mm) and be finished with 1.00 mm thick laminate of same or combination shades, over 6mm BWP grade ply. Skin membrane: (Opaque portion up to 900mm from floor level and from 2100mm to ceiling, finished with 6mm thick BWP grade plywood on each face with grooves, as per drawings/ instructions. Finishing: 1.0mm thick laminate of same or combination shades with grooves as per instructions. Glazing: 12mm thick clear float glass fixed with polished teak / steam beech wood glazing beads of approved shape (finished 12 x 25mm). Skirting- 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed.</p>	Sq.ft.	185.00		

	Quoted rates shall include all necessary materials, accessories and labour and also to make provisions for electrical / telephone / computer wiring conduits and switch boxes, etc. (Materials for wiring, conduits & switches etc. shall be separately paid for)				
2.3	Supply and erecting low height opaque partitions (up to maximum 1200mm height)	Sq.Ft.	50.00		
	<p>Conforming to the following specifications: Basic frame work: Framing shall consist of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane: 6 mm thick BWP grade ply on each face up to 900mm height. Glazing: 12mm glass in remaining portion, Finishing: 1.0-mm thick laminate of same or combination shades with grooves as per instructions. Edge moulds: All free top/ end surfaces shall have polished teak / steam beech wood moulds of approved shape (from 18 x 50mm sections). Skirting- 100mm high laminate of approved make & shade all as directed. Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical / telephone/computer wiring, conduits and switch boxes, etc. (Materials for wiring, conduits and switch boxes shall be separately paid for.)</p>				
2.4	WALL PANELLING & COLUMN ENCASING WITH DIFFERENT LEVEL INSTRUCTION AS PER ARCHITECT Supplying, Fabricating , erecting & fixing Wall paneling / Column encasing (up to false ceiling) as per drawing and design and conforming to the following specifications : Basic frame work: Framing shall consist of Heavy duty Aluminum Box Sections 50mm x 50mm @ 600mm c/c both ways Horizontally and Vertically. The vertical alternate frames to be fixed to the ceiling with necessary fixtures. Vertical members shall be suitably anchored at ceiling level to ensure rigidity. Skin membrane : 6 mm thick BWP grade plywood on face Finishing : 1.0mm thick laminate sheet of same or combination shades with grooves as per instructions. Skirting: 100mm high laminate of approved make & shade all as directed. Top Border: 150mm high laminate of approved make & shade all as directed. Note: Quoted rates shall include all necessary materials, accessories and labour and also for making provisions for electrical/telephone/computer wiring, conduits and switch boxes, etc. where ever required. (quantity/location should be restricted only to the central pillars in Banking hall/to hide electrical pipes/AC drain pipes/any prime location) Only visible surface will be taken for measurement only.	Sq.Ft.	295.00		
2.5	Aluminum grill on the ceiling of Cash cabin	Sq.Ft.	35.00		
	TOTAL OF PARTITIONS WORK				
3	COUNTER & WORK STATIONS				
3.1	CASH COUNTERS	R ft.	5.00		
	Providing and erecting in position Cash Work Station of approx. size 1370x900x750mm (4.5'x3.0'x2.5'), made of 19mm thick block board pasted				

	<p>with 1.00mm laminate inclusive of a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed.</p> <p>Each cash workstation shall comprise of the drawer unit, Tea tray at top, Cash drawers with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S. S. handles of approved quality. Inner face of cash counter to be provided with 16G, M.S. sheet, finished with 1.0mm thick laminate of approved shade & make, over a coat of approved steel primer. Inner faces shall be finished with 1.0mm thick laminate of approved shade .Skirting: 100mm high laminate of approved make & shade all as directed.</p> <p>Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0 mm thick laminate complete.</p>				
3.2	<p>GLASS BARRIER ON CASH CABIN / OFFICER COUNTER Providing & fixing 12mm thick clear float glass on Cash Counters at front & sides, with S S clamps/patch fittings, necessary polished beadings etc complete all as directed by the Bank.</p> <p>Note: Front glass to be fixed in slanting position towards inside cash area with required angle as directed. Above glass to be fixed either in two pieces. Lower piece having one semi-circular/rectangle 6" dia/long opening at customer top level & other piece to be fixed at suitable height making 3" slit for conversation with customer. In this case, only glass area to be measured for payment purpose.) In case of single piece, one semi- circular/rectangle 6" dia/long opening at customer top level & one circular hole of required dia at suitable height for conversation at centre of cash counter to be provided.</p>	Sq ft	85.00		
3.3	<p>ALUMINIUM JALI ON CASH CABIN TOP Providing and fixing of aluminum grill with square size 75mm x 75mm – 8mm, on top of the cash cabins etc. The grill shall be tightly stretched and nailed to a wooden frame work, made out of 50mm x 40mm teak/hard wood (with anti-termite) members at 750mm c/c approx. both ways or as per site conditions. The erection of framework shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories.All teak wood surfaces shall be painted with two coats of synthetic enamel over one coat of primer. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Bank.</p>	Sq ft	40.00		
3.4	<p>RUNNING COUNTER /CSA /OFFICERS COUNTER Providing and erecting in position Cash Work Station of approx. size 1370x900x750mm (4.5'x3.0'x2.5'), made of 19mm thick block board pasted with 1.00mm laminate inclusive of a 350mm wide customer top at 1155 mm level,. Writing top & customer top should be finished with mirror polished; 18mm thick granite slab (Jet black) with rounded edges and sides with 1.0mm thick laminate of approved shade/make. Both should have sufficient</p>	R ft.	26.50		

	<p>gap in between to accommodate computer monitor up to full depth. The workstations shall be supported from the partition system made of 19mm thick BWP grade block board finished with 1.00 mm thick laminate of approved shade/make. Free edges shall have 18 mm thick, polished white or steam beach wood moldings of half-round profile as per drawings and instructions and 100mm high laminate of approved make & shade all as directed.</p> <p>Each cash workstation shall comprise of the drawer unit, Tea tray at top, Cash drawers with approved telescopic channels for drawer-slides, automatic locks (keys in duplicate), wire managers, space for computer CPU, modesty panel and other necessary hardware and accessories including satin finish S. S. handles of approved quality. Inner face of cash counter to be provided with 16 G, M.S. sheet, finished with 1.0mm thick laminate of approved shade & make, over a coat of approved steel primer. Inner faces shall be finished with 1.0mm thick laminate of approved shade .Skirting: 100mm high laminate of approved make & shade all as directed.</p>				
	<p>The item includes Chest of drawers (size 1'-4" x 2'-0" x 2'- 5") made of 19mm thick commercial ply wood having One drawers at top and a storage cabinet below having shutters of 19mm thick ply wood finished with 1.0mm thick Laminate on all sides. 1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top for each seat. All beading and exposed wood shall be melamine polished and the Internal surfaces shall be .75 mm thick laminate. Item includes 1'-3" high 12mm thick toughened glass above upper tier and readymade metal powder coated CPU trolley, grommet, foot rest for each seat. All complete as per approval and instructions of the Architect / employer.The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement.</p>				
	<p>The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thk laminate complete.</p>				
	TOTAL OF WORKING COUNTER				
4	DOOR & ACCESSORIES				
4.1	Main Entrance Door & Fixed glazing	Sq.Ft.	85.00		
	<p>(WITH ETCHING, HEIGHT – 8' & GLASS – 12mm THICK) Providing and Fixing in Position toughened glass door with 12 mm thick toughened glass with 3M security film complete in all respects with 2 Ozone patch fittings including top patch(OPF-02),BOTTOM PATCH (OPF-03)angle lock(OPL-01)TOP PIVOT (OFS-ACC-GDP)Floor Spring (FS8400) and SS C shaped handle (OGH-55) 32mm x 457 mm all item included. The item also includes door lock completed to the satisfaction of the architect</p>				
4.2	CASH /STORE/ OTHER DOORS	Sq.Ft.	70.00		
	<p>Supplying and fixing in position overall 32 mm thick solid core hot pressed phenol formaldehyde bonded flush door finished with 1.0 mm thick laminate of approved shade and quality on both sides of the door shutter & beading on edges including cost of hardware fittings e.g. Godrej night latch / mortise lock, hinges, door closure, handles etc. of approved make and quality & making provision of peep hole of suitable size with glass & beading all-round all as directed. . Door stopper SS Grade 304, HESSF-2C hardwyn make (Cash/Store/Other doors) Cash cabin shall be fitted with Godrej Night latch.</p>				
4.3	MANAGER CABIN DOOR	Sq.Ft.	50.00		
	<p>Supplying and fixing in position 32 mm thick solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make</p>				

	<p>finished up to 900 mm from floor level with 1.00 mm thick laminate of approved quality on both sides of the door shutter & beading on edges. The upper portion of the shutter is to be provided with 12 mm thick clear float glass fixed with white or steam beech wood glazing beads of approved design, complete as per drawing.</p> <p>Rate to include cost of hardware fittings e.g. mortise lock hardwyn make HML-480 Lock Body 304 Stainless Steel., hinges, handles, door closer Dorma/GEZE Dline / Hardwyn/Godrej or approved equivalent Door Closer etc. of approved make and quality. Door stopper SS Grade 304, HESSF-2C hardwyn make. (Manager cabin door)</p>				
4.4	<p>FLAP DOOR Providing and fixing Flap Door of min. size: 3'6" (B) X 4' (H) made of block board with approved lamination on both side, of required size with hinges/tower bolts/stopper/handles etc complete.</p>	Sq.Ft.	14.00		
TOTAL OF DOOR & ACCESSORIES					
5	TABLE & FURNITURE				
5.1	<p>MANAGER TABLE (Size:- 6'-0" x 2'-6") ht. 2'-6" WITH SIDE CREDENZA INCLUDE 12mm THICK GLASS:-</p>	Nos	1.00		
	<p>Providing and placing in position tables with top, vertical sides/dividers, skirting and modesty panel made out of 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces. It shall also have 75mm x 40mm teak wood runners below the top and for footrest below. Every table shall be provided with a side unit (size – W-500mm, H-750mm, D-500mm approx.), consisting of 150 mm deep drawer at top and a cabinet with open able/hinged shutter below.</p> <p>The facia of drawer and shutter of cabinet below shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The side unit shall have CAM locks, handles, guides, sliding units, hinges, magnetic catcher's etc. of approved make. Every table shall be provided with a pedestal unit (size – W-550mm, H-720mm, D-450mm approx.) below. The table shall have 100mm deep facia, below the top, in which keyboard drawer unit shall be adjusted. It shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The unit shall have CAM locks, handles, guides, sliding units etc. of approved make.</p> <p>The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be finished with 1.0mm thick laminate all complete to the satisfaction of the Architect. Every table top shall be provided with 12 mm thick float glass (as per profile) with polished and beveled (25mm wide) edges all complete to the satisfaction of the Architect.</p> <p>Approx size of table : 1830 x 915 x 750 mm (6.0'x 3.0'x 2.5')</p>				
5.2	<p>Officer TABLE (Size:- 5'-0" x 2'-6") ht. 2'-6" WITH SIDE CREDENZA INCLUDE 12mm THICK GLASS :-</p>	Nos	1.00		
	<p>Providing and placing in position tables with top, vertical sides/dividers, skirting and modesty panel made out of 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) on all exposed surfaces. It shall also have 75mm x 40mm teak wood runners below the top and for footrest below.</p> <p>The facia of drawer and shutter of cabinet below shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the</p>				

	<p>Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. Every table shall be provided with a pedestal unit (size – W-465mm, H-720mm, D-450mm approx.) below. The table shall have 100mm deep fascia, below the top, in which keyboard drawer unit shall be adjusted. It shall be made out 19mm thick water proof board with 1mm thick laminate (as/shade approved by the Architect) and sides and bottom of drawer shall be made out of 12mm thick water proof ply. The unit shall have CAM locks, handles, guides, sliding units etc. of approved make.</p> <p>The job shall include for 6mm x 6mm grooves in between sides and open able drawers and hinged shutters. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be finished with 1.0mm thick laminate, all complete to the satisfaction of the Architect. Every table top shall be provided with 12 mm thick float glass (as per profile) with polished and beveled (25mm wide) edges all complete to the satisfaction of the Architect.</p> <p>Approx Size : 1524 x 915 x 750 mm (5.0'x 3'x 2.5')</p>				
	TOTAL OF TABLE & FURNITURE				
6	LOW / FULL HIEGHT STORAGE CABINETS & SIDE UNIT				
6.1	Low / FULL HT Storage cabinet	Sq.Ft.	95.00		
	<p>P/F in position 450mm deep storage full ht./low ht. cabinets having sides partitions, shelves & shutters, fabricated out of 19mm BWR & 6mm th.BWR Plywood back, with all exposed surfaces & inside of shutters/internal base of drawers to be finished with 1mm thick laminate of rate not less than Rs.1300/-Per Sheet & P/F decorative metallic laminate skirting(silver paint brush 1001 PB of Century)(100mm)as/arch.drg. i/c 31x31mm rounded steam beech wood molding & 6x19mm steam beech wood edging on edges of comm. board as/arch. drg. complete with shelves, shutter, drawers etc. i/c P/F necessary hardware telescopic channels for drawers of Hettich, S.S. piano hinges as/appvd. sample, Hettich handles(as/appvd. sample)in all drawers & shutters, locking arrangement,75mm brass tower bolts, Hettich locks in all shutters & drawers ,magnet catcher, painting the exposed internal surfaces of finished with 1.0mm thick laminate with melamine finish on wood surface with 6mm comm.ply at rear as per arch.drg.& as per site requirements the rate should include 19mm th. pre-polished Itallian granite stone (Asian Quartz) of rate not Less than Rs.350/-per sq ft. as per appvd. sample with half round beveled edge complete on low ht. storage cabinets. All as per the design and instructions Bank.</p>				
6.2	Main Electrical Panel Boxing Cabinet with BISON Board	Sq.Ft.	42.00		
	<p>Providing and fixing of DB Shuttering formed of 12mm thick plywood on 12mm thick Gypsum board (fire Proof) with finish as per Item no 1 for inside and outside shutters finished with laminate on outer surface with SS (4Nos) louvre perforation and necessary hardware, hinges etc complete as per details. All as per the design and instructions Bank. Only front face taken for measurement only</p>				
	TOTAL OF STORAGE & SIDE UNIT				
7	OTHER MISCELLANEOUS ITEMS				
7.1	PIN UP / NOTICE BOARD	NO.	1.00		
	<p>Providing and fixing in position notice board (as per design) of size – 900mm x 600mm x 150mm. The sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect) on all exposed surfaces.It shall have 12mm thick tack The front shall have 6mm thick float glass sliding shutter in two parts.It shall also have 19mm wide two</p>				

	track aluminum channel for sliding arrangement, all around, along with locking arrangement. Board (Make – Cellotex or equivalent) wrapped with stretched blazer cloth (Make- Raymonds), of Rs. 200.00 per Mt. (approx.) in colour and pattern approved by the Architect. It shall be fixed with help of kail/partal wood (sect. 19mm x 25mm) frame work. It shall be covered with 6mm thick water proof plywood, on the back. All the exposed edges of water proof board and ply shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect.				
7.2	WRITING LEDGE-SLIP CUSTOMER DESK	NO	1.00		
	<p>Providing and fixing in position (with rear wall) slip and customer writing desk (as per design) of overall size – 1200mm x 450mm x 300mm. The fixing shall include for expansion bolts, cleats, clamps, bolts, nuts, screws, rivets and other anodized accessories, all complete up to the satisfaction of the Architect.</p> <p>The writing top and facia/sides shall be made out of 19mm thick water proof board with 1mm thick laminate (as per shade approved by the architect), on all sides and . It shall be laid over the base of 19mm thick water proof board (already considered in various items.) and fixed with araldite. It shall include for beveling and polishing at all the exposed edges. The rate shall include cost of all materials, labour, scaffolding, wastages, polishing and T& P etc. It shall be made out of 12mm thick water proof plywood (two surfaces of 6mm thickness, fixed together, where required) on rear and both sides. The front shall be made out of 12mm thick glass (as per profile). It shall be fixed in the grooves, made in side members, in an inclined manner (as per profile in drawing enclosed) with a gap of 75mm (max.) in between. The space shall be further divided in four equal parts with help of 12mm thick water proof plywood. All edges of the glass shall be polished.All the exposed edges of water proof board and plywood shall be provided with 6mm thick teak wood/hard wood lipping. All teak wood surfaces shall be melamine polished and other internal surfaces shall be painted with two coats of synthetic enamel over one coat of primer, all complete to the satisfaction of the Architect</p>				
7.3	CHEQUE DROP BOX / SUGGESTION BOX	No.	2		
	Supplying and erecting cheque drop box / suggestion box (over all size 400mmx150mmx600mm) made of 19 mm thick BWP grade ply board and curved portion at top made out of 90mmx90mm C.P. teak/steam beach wood section. A slit opening of 10mmx150mm is to be provided at the top of the box. An openable shutter of 259mmx262mm size made of 19 mm thick BWP grade block board is to be provided. The entire exposed timber surface including all free edges is to be finished with 1mm thick laminate sheet of combination shade. Inner faces shall be painted with two coats of synthetic enamel paint of approved shade & quality over a coat of primer. Rate to include cost of necessary hardware fittings e.g. hinges, lock, knob, etc. of approved design and quality.				
7.4	ROLLING/ VERTICAL BLINDS	Sq.Ft.	40.00		
	Providing and fixing Roller blinds of approved design and shade by the Architect,incl all std fittings as per manufacturer's specification. The work to be completed as per specification and approval of the architect. (approved brand Vista, Hunter Dogulus)				
7.5	ETCHING WORK & BANK LOGO FOR BRANCH	JOB	1.00		
	Etching for Toughened glass (Branch and ATM), Etching for Cash Cabin Glass, Etching for Front counters.				

	Etching work on glass with chemicals (as per design and profile) as and where required. The rates shall include cost of all materials, labour, T& P, wastage, transportation etc. required for proper completion of work. It shall be made out of following profile.-Bank's logo (300mm dia. / 300mm x 300mm).All complete to the satisfaction of the Architect. Etching work on glass with chemicals (as per design and profile) as and where required. The rates shall include cost of all materials, labour, T& P, wastage, transportation etc. required for proper completion of work. It shall be made out of following profile.-Bank's logo (300mm dia. / 300mm x 300mm). All complete to the satisfaction of the Architect.				
	TOTAL OF OTHER MISCELLANEOUS ITEMS				
8	PAINTIUNG WORK				
8.1	Painting on Walls and Ceilings with two or more coats of first quality of Acrylic Emulsion (Make & Shade Approved by Bank / Architect). It shall include for preparing the surfaces clean, even and smooth with thoroughly brushing with broom, scratching with patti and sand papering respectively, so that the surfaces are free from oil, grease, dirt, mortar droppings & other foreign and loose matter. It shall also include for preparing the surface and filling of holes with 2 coat of first quality acrylic wall putty (Birla Wall Care / JK / Asian) before priming coat of whiting / approved primer. The rate shall include cost of all materials such as plaster of paris, whiting /primer, glue (Fevicol), indigo / stainer, brushes, sand paper, patti, dhoti, broom stick, clean water with storage and other containers, labour, scaffolding / ladder charges, cleaning of floors and other sundries etc., all complete to the satisfaction of the Architect. Please note that in the Branch Hall, walls are to be painted below false ceiling and ceiling is not be painted.	Sq ft	1560.00		
8.2	Providing & applying 2 coats of first quality synthetic enamel paint over a coat of Zinc Chromate metal primer to steel surfaces (window grill, collapsible gate) all of approve make and shade including surface preparation by complete scrapping the existing paint / rust on grills / shutter by using chemical paint striper or suitable approved method, cleaning, filling holes, smoothening the surface all complete as directed by Bank's Engineer. (Measurement Coefficient for each side = 0.5)	Sq ft	80.00		
8.3	Rolling Shutter as same as above in 12.2 but measurement shall be taken for each side with coefficient 1.10 each side.	Sq ft	300.00		
	TOTAL OF PAINTING WORKS				
A	GRAND TOTAL FOR FURNISHING (A)				
B	DISCOUNT (%)				
C	NET TOTAL AMOUNT				
D	GST AMOUNT (..... %) on C				
E	GROSS AMOUNT INCLUSIVE OF GST (A+B)				

GROSS AMOUNT IN WORDS:

Rupees.....only

Place:
Date:

Signature & Seal of the Tenderer