



INDIAN BANK

Sitapur Zonal Office
Near Raja College Ground
Civil Lines, Sitapur,U.P. 261001

TENDER DOCUMENT

Construction of RCC Road at Sitapur Zonal office

PART-II FINANCIAL BID

Ref.No: CO:EST:Xx -Xx
Date : Xx.XX.2025

Name of the contractor:

.....
.....
.....

Last date of submission of tenders	18.07.2025 upto 15.00Hrs. at Indian Bank, Zonal Office Sitapur, Estate Department, Sitapur,U.P. 261001
Date of opening Tender	19.07.2025 upto 15.30 Hrs. at Indian Bank, Zonal Office Sitapur, Estate Department, Sitapur,U.P. 261001
Cost Of Tender	Free Of Cost.

This part of the tender should be submitted in a separate envelope and financial bid shall be quoted only in this form and no other form will be accepted.

This Tender document contains 07 pages

GENERAL TERMS & CONDITIONS

1	All items of work under this Contract shall be executed strictly to fulfill the requirements laid down under "Basis of Design" in the specifications. Type of equipment, material specification, methods of installation and testing and type of control shall be in accordance with the specifications, approved shop drawings and the relevant Indian Standards, however capacity of each component and their quantities shall be such as to fulfill the above mentioned requirement. The basis of the design to be submitted by contractor for approval by Bank
2	The rate for each item of work included in the Schedule of Quantities shall, unless expressly stated otherwise, include cost of:
	a. All materials, fixing materials, accessories, appliances tools, plants, equipment, transport, labour and incidentals required in preparation for and in the full and entire execution, testing, balancing, commissioning and completion of work called for in the item and as per Specifications and Drawings.
	b. Wastage on materials and labour.
	c. Loading, transporting, unloading, handling/double handling, hoisting to all levels, setting, fitting and fixing in position, protecting, disposal of debris and all other labour necessary in and for the full and entire execution and for the job in accordance with the contract documents, good practice and recognize principles.
	d. Liabilities, obligations and risks arising out of Conditions of Contract.
	e. All requirements of Specifications, whether such requirements are mentioned in the item or not. The Specifications and Drawings where available, are to be read as complimentary to and part of the Schedule of Quantities and any work called for in one shall be taken as required for all.
	B. Wastage on materials and labour.
	g. In the event of conflict between Schedule of Quantities and other documents including the Specifications and approved basis of design, the most stringent shall apply. The interpretation of the Bank shall be final and binding.
3	All equipment's, quantities and technical data indicated in this Schedule are for the Contractor's guidance only, This schedule must be read in conjunction with other documents and site conditions. The Contractor shall be paid for the actual quantity of work executed by him in accordance with the approved Shop Drawings & Basis of Design at the contract rates.
4	This Schedule shall be fully priced and the extensions and totals duly checked. The rates for all items shall be filled in INR including NIL items.
5	No alteration whatsoever is to be made to the text or quantities of this Schedule unless such alteration is authorised in writing by Services Consultant. Any such alterations, notes or additions shall, unless authorized in writing, be disregarded when tender documents are considered.
6	The Contractor shall procure and bring Materials/Equipment to the site only on the basis of drawings approved for construction and shop drawings /Basis of Design and not on the basis of Schedule of Quantities which are approximate only. This also applies to the Contractor's requisition for Owner supplied materials.

7	The unit rate for all local equipment or materials in Indian Rupees shall include cost of equipment and materials including all taxes and duties and also including forwarding, freight, insurance and transport into Contractor's store at site, storage, installation, testing, balancing, commissioning and other works required.
8	The Contractor /vendor free to make site visit to ascertain the existing road working conditions and other relevant site feasibility/feature
9	One year (12 months) defects liability period

Signature & Seal of the Tenderer

QUOTE FOR CONSTRUCTION OF RCC ROAD& ALLIED WORKS AT SITAPUR ZONAL OFFICE –SITAPUR(UP)					
S. N	DESCRIPTION	UNIT	QTY	RATE (Rs.)	AMT (Rs.)
1	Surface Preparation				
	The existing Road surface shall be thoroughly cleaned using vacuum and hand equipment/chisels or suitable mechanical equipment to remove debris and loose materials. The surface shall be cleaned with water and ensured to be in a Saturated Surface Dry (SSD) condition, free of foreign materials and excess moisture to receiving fresh concreting (prior to the concreting) . The rate should be included that all the debris /unservice materials to be disposed to municipal dumping ground & stacking of serviceable material.	Sqm	1600.00		
2					
2	Providing and laying M30 Design mixed concrete with Maximum W/C ratio of 0.45 works using 20 mm and down size graded crushed aggregate with minimum cement content of 360 Kg. OPC for the average thickness of 100mm including providing and fixing necessary scaffolding, formworks, entering and shuttering, machine mixing with proper Slope for water drainage compacting by mechanical vibrators, curing, etc. complete. Concrete shall conform to IS 456-Latest edition rate shall be exclusive of the cost of steel reinforcement, which will be paid under a separate item. The item include preparation of suitable surface for concrete and removing of foreign material etc. It has to be needy with suitable Slopes and provided suitable expansion joints and filled with expansion filler etc. The rate including Ramping of Exiting Soil, Sand filling, Forming work h where ever required etc. The rate including curing, Filler ,Expansion board etc .The concrete should installed should be neat and leveled.	Cum	160		
3	Reinforcement				

	Supply and installation of A142 mesh reinforcement or 6mm /8mm dia equal reinforcement of A 142 conforming to IS 1566 including cutting, bending & supply and binding with 20 SWG annealed binding wire where ever required ,joint to be lapped 200 mm . Payment shall be made as per actual of road for A142). A142 to be laid 25mm from top ,no separate rate will be paid for lapping of reinforcement	Sqm	1500		
4	Brick Work & Plastering				
i	UPSTAND WALL :Providing and constructing 230 mm thk. brick work or 200 mm thick block works using bricks in C.M.1:5 (1cement : 5 Fine aggregate) as per IS in super structure. The items shall include the cost of material, scaffolding, transportation, all labours and curing charges. The rate shall be inclusive of suitable surface preparation for brick works and 3":upvc drain and weep holes .the rate including excavation leveling etc	Cum	28.00		
ii	Providing and constructing 115/100 mmthk. brick work or 100 mm block works using bricks in C.M.1:4 (1cement : 4 Fine aggregate) as per IS in super structure. The rate shall include the cost of material, scaffolding, transportation, all labours and curing charges. The rate shall be inclusive of suitable surface preparation for brick works	Sqm	3.00		
v	Providing 15-20 mm thk. external plastering in C.M.1:5 (1 cement : 5 fine Aggregate) on brick/ concrete works including raking out joints where required,pointing, and curing etc. complete as per instructions. The rate include suitable mixing of suitable integrated waterproofing compound in the mortar forplastering,pointing,finishingetc . The rate including repairing of concrete works.	Sqm	450.00		
6	Painting				
i)	Painting Lines, Dashes, Arrows etc on Roads in Two Coats on New Work (Painting lines, dashes, arrows etc on roads in two coats on new work with ready mixed road marking paint conforming to IS:164 on bituminous surface, including cleaning the surface of all dirt, dust and other foreign matter, demarcation at site and traffic control)				
i)	(i) Over 10 cm in width	Sqm	45.00		

ii)	Up to 10 cm in width	Sqm	40.00		
II)	Providing & applying 2 coat first quality SYNTHETIC ENAMEL paint) over a base coat of primer on wall surface as directed by Bank, all of approved make and shade, scaffolding all complete as directed. Rate to be included the cost of filling the pot holes with plaster of paris, removal of unwanted nails, cleaning and carting away debris out of premises, all complete as directed by Bank's Engineer	Sqm	450.00		
NOTE :- GST TAX WILL BE EXTRA.					

Total Amount in words: Rupees.....only

GST (taxes) will be extra

Place:

Signature & Seal of the Tenderer

Date: