



PROPOSED CIVIL CONSTRUCTION WORK OF INDIA BANK, BALRAMPUR BRANCH - CHAATISGARH

GROUND FLOOR

CARPET AREA = 1109.00 SQ.FT.
(EXCLUDING TOILET BUILT UP
AREA, ALL INSIDE WALL
THICKNESS AREA, 1 NO'S INSIDE
COLUMN AREA)

SPECIFICATIONS OF PROPOSED CONSTRUCTION OF BRANCH PREMISES

V1 - 1'-6"x2'-0" (DOUBLE M.S. GRILL)
D1- 3'-0"x7'-0"
D2- 2'-6"x7'-0"
W1- 4'-0"x4'-0"
M.S. SHUTTER- MAIN ENTRY

NOTE-

- ALL INSIDE FLOORING AT BANKING HALL AND ATM OF VITRIFIED FLOORING (1ST CLASS MAKE) - SOMANY OR JOHNSON (2' X 2').
- THE FLOORING AND DADO TILES OF BOTH TOILETS SHOULD BE OF SOMANY OR JOHNSON MAKE. THE FLOORING OF TOILET SHOULD BE ANTI SKID FLOORING.
- THE UROPIAN W.C., WASH BASINS, URINALS SHOULD BE OF PERRYWARE OR JOHNSON MAKE. THE STEEL SINK SHOULD BE PROVIDED AT COFFEE VENDING MACHINE PLATFORM OF 2' X 2'. THE PLATFORM SHOULD BE 2' WIDE AS PER DRAWINGS AND MAKE OF LOWER BASE CUDAPPA AND GRANITE STONE SHOULD BE OVER THE CUDAPPA STONE WITH CEMENT MORTAR FINISHING IN ALL RESPECT.
- THE KOTAH STONE FLOORING OVER THE RCC FLOORING SHOULD BE CONSTRUCTED INSIDE THE STRONG ROOM AREA.
- STRONG ROOM- ALL THE FOUR SIDE WALLS SHOULD BE 12" THICK RCC AND FLOORING SHOULD BE 12" THICK RCC. (THE DETAILED DRAWING SEPARATELY FURNISH FOR CONSTRUCTION)
- WINDOWS 4'0" X 4'0" SHOULD BE FIXED WITH 16 GAUGE SQUARE BAR MS GRILL. ALL THE VENTILATORS 16" X 1'0" SHOULD BE FIXED 16 GAUGE SQUARE BAR GRILL BOTH SIDE.

ER.SUNIL SHARMA

DATE - 21/05/2025

SIGNATURE -

AR. ASHISH
SHRIVASTAVA
CHARTERED ARCHITECT
CA/92/15120
KUSHI AND ASSOCIATE
11, SWASTIK COMPLEX,
RUSSEL CROSSING, JABALPUR
MOB 9131343384, 9425150793