



FGM Office, Lucknow,
1st Floor, New Building,
Hazaratganj, Lucknow-226001

TENDER DOCUMENT –

SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF 200KVA AUTOMATIC VOLTAGE REGULATOR IN BANK'S BUILDING AT HAZARATGANJ, LUCKNOW

PART –2 FINANCIAL BID

Ref.No: CO:EST:FGMO -06

Date : 25.11.2025

Name of the contractor:

.....
.....
.....

Last date of submission of tenders	09.12.2025 upto 15.00Hrs. at Indian Bank, FGM Office, Lucknow, 1st Floor, New Building, Hazaratganj, Lucknow-226001
Date of opening Tender	09.12.2025 upto 15.30Hrs . at Indian Bank, FGM Office, Lucknow, 1st Floor, New Building, Hazaratganj, Lucknow-226001
Cost Of Tender	Free Of Cost.

Financial bid for SITC of 200KVA oil Cooled Stabilizer

Sl.	SPECIFICATIONS & DESCRIPTION	Unit	QTY	Rate	Amount (Rs.)
1.	Supply Installation Testing and commissioning of 200KVA oil Cooled Stabilizer (adhering to Technical Specifications mentioned in Annxure-1)	No.	1		
2	Supply Installation Testing and commissioning of 200 KVA Service Bypass Changeover with on-load Change over & MCCB (adhering to Technical Specifications mentioned in Annxure-2)	No.	1		
3	Supply & Installation of 40 KA Surge Protection device for the 200KVA oil Cooled Stabilizer	No.	1		
4	Supply and installation of Advanced model with 7# Standard Features and Protections for the safety of Air conditioner units & other 3 phase equipment (adhering to Technical Specifications mentioned in Annxure-2)	No.	1		
5	Termination of incoming & outgoing cable with enclosure for the incomer Entire Cabling minimum with 185mm ² Power cable with all accessories viz. Cable Glands, Dowells,& all electrical miscellaneous hardwares Insulations, tapes, saddles, ties, and fasteners, etc.	Job	1		
6	Chemical Earthing. Lightning Grade Maintenance free Earthing using Copper Electrode of size 3000mm Minimum 70MM Diameter long connected with 50x10 mm Copper internal strip (Copper purity not less than 99.9%)complete with excavation, civil works, cast iron cover with backfill compound	No.	2		
7	Supply and laying of 3.5C x 185sqmm armoured Cable (Cu) for input and out connection of the 200KVA oil Cooled Stabilizer	rmt	40		
8	Providing and fixing of Platform for installation of 200KVA oil Cooled Stabilizer (2000mm x 1400mmx150mm) made of RCC with proper reinforcement	1	No		
	TOTAL				
	GST				
	GRAND TOTAL				

Date:

**Signature of
Contractor**

Place: