

B.O.Q OF INTERIOR WORK FOR INDIAN BANK , BHAWANIPATNA BRANCH.					
SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>A</b>	<b>PARTITION WORK.</b>				
<b>1.0</b>	<b>FULLY HEIGHT Partition ( Semi Glazed)</b>				
	<p>Providing and fixing in position partly glazed full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with <b>6 mm plywood ( conforming IS 710 )</b> on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading and 2"x2" T.W. member for door sides . All exposed T.W / beading surfaces to be finished in melamine polish as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.</p> <p>(Note : In case of false ceiling, the vertical members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)</p>	Sft.	271.00		
<b>2.0</b>	<b>LOW HT. HEIGHT Partition ( Semi Glazed)</b>				
	<p>Providing and fixing in position partly glazed 4'-0" HT. Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with <b>6 mm plywood ( confermin IS 710 )</b> on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 12 mm thick glass as per design and fitted with 3-1/4" thick beach wood beading at glass sides All exposed wood. surfaces to be finished in melamine polish of as directed including all necessary Stainless Steel finish fittings/hardware and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/Bank complete in all respects.</p>	Sft.	116.00		
<b>3.0</b>	<b>Partition ( Cement board partition. )</b>				
	<p>Providing and fixing in position full Partition work as per drawing ,in frame work at 2'x2' grind (horizontally and vertically) comprising of 2"x1 ½" hevy gazed almunium section and/or as per frame work shown in the drawings with 12 mm Bisan board on both sides finished with approved two cote of enamel paint over one coate of primer complete in all respects including all labour and materials.</p>	Sft.	96.00		
<b>4.0</b>	<b>Full glazed Partition</b>				
	<p>Providing , fitting &amp; fixing 12mm thick flot glass partition .The partiton will be supported with S.S patch panel fittings as per drawing and design. The exposed edge of the glass partition should be polished to super quality. The work should be completed as per direction of architect including cost of all labour &amp; material .</p>	Sft.	73.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>B</b>	<b>DOOR WORK.</b>				
<b>1.0</b>	<b>Doors – semi glazed</b>				
	Providing & fabricating fixing door shutter with 28mm x 75mm height & 28mm x 75mm, 28 mmx 60mm, 28mm x80mm rails respectively by using Giringa/ Kasi wood of well seasoned with necessary wood joining, planning, polishing etc., as per drawing matching the aligned partition . The shutter will have part glazed 8mm thk float glass side beveled , high polished with body itching of st globain & part solid one covered with 9 mm BWP ply, both sides covered with 1 mm tk laminate of approved shade with necessary WB wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of necessary hinges, <b>motise lock ( 7-lever- 8" lock of Godrej / Doorset make )</b> , aldrops etc., all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect.	<b>Sft.</b>	<b>122.50</b>		
<b>2.0</b>	<b>Doors – glazed</b>				
	Providing and fixing Entrance Door (glazed) as per drawing in 12 mm thk. Clear toughen glass shall be fixed in.Ozon / Enox make patch fitting door . Item to include all necessary hardware of Stainless Steel finish and chemical eaching with bank's logo as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion ( it include SS finished <b>H type 1'-6" long door handle</b> )	<b>Sft</b>	<b>24.50</b>		
	b) Providing & fixing fixed partition made up of 12 mm thk. Clear toughen glass shall be fixed in.Ozon / Enox make patch fitting	<b>Sft</b>	<b>34.00</b>		
<b>3.0</b>	<b>Flap door</b>				
	Providing, fitting and fixing of flap door with frame work made out of 35mmx35mm thick hard wood and nailed with 6mm. thick ply and finished with 1mm. Thick laminates of approved colour and design on both the surfaces of the frame work as per drawing and design.The edges of the door to be covered with decorative wood moulding with two coat of superior wax polish.The work is to be finished with all material ,labour,nails,screws,hings,locks,handles,door closer and all other hard wares as per detail drawings.	<b>Sft</b>	<b>24.00</b>		
<b>4.0</b>	<b>Door closer</b>				
	Providing and fixing Godrej / Doorset / Dorma make over head door closers in door with necessary fixtures and fittings etc.	<b>Nos</b>	<b>5.00</b>		
<b>5.0</b>	<b>Floor spring</b>				
	Providing and fixing Godrej/ Hardween/ Dorma make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	<b>Nos</b>	<b>1.00</b>		
<b>6.0</b>	<b>Night latch lock</b>				
	Providing and fixing Knightlatch lock of Godrej make to cash counter door with necessary fixture and fittings etc as per direction of architect.	<b>Nos</b>	<b>1.00</b>		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>C</b>	<b>FURNITURE WORK.</b>				
<b>1.0</b>	<b>Cash Counter</b>				
	<p>Providing and fixing of counter table of size 4'-6"x3'-0"x2'-6" with 25mm th. ply table top ( <b>conforming IS 710</b> ) the front facia is raised up to ht of 3'-6" with a horizontal 15" wide counter top and front drawer unit consisting 3 Nos of drawer units,slides on telescopic slider made up of 19mm th.ply ( <b>conforming IS 710</b> ) with locking arrangement. <b>It also include metal Keyboard tray manufactured by M/s Godrej / EBCO.The keyboard is a pullout type, fixed to channels and screwed to below table top</b> The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shade and <b>the inner surface is finished with 0.7 mm th inner laminate .</b></p>	<b>Nos</b>	<b>1.00</b>		
	<p>Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved qualityThe work should be mpleted including all labour and material. It also include 8mm th clear table top glass with all edge mechince polished. The 3" front facia of the table to be made with 19 mm ply and a glazed glass pics of size1'0"x1'-0" with bank logo colour eached edge <b>polished fixed with 1/2" SS stord vertically on the front side of the counter as per instruction .</b> The work should be completed including all labour and material.</p>				

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>2.0</b>	<b>Table</b>				
	Providing and erecting in position, Manager's/Officer's Tables and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider with locking arrangement made up of 19mm th.ply ( <b>conforming IS 303</b> ) with locking arrangement. <b>It also include metal Keyboard tray manufactured by M/s Godrej / EBCO.The keyboard is a pullout type, fixed to channels and screwed to below table top</b> . The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shadea and <b>the inner surface is finished with 0.7 mm th inner laminate</b> . Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in dupli'cate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers etc. of approved qualityThe work should be mpleted including all labour and material.It also <b>include 8mm glass top on table with edge polished</b> . All the work should be done as per drawing and as per direction of architect. It also include a glazed glass pics of size1'0"x1'-0" with bank logo colour eached edge polished fixed with 1/2" SS stord vertically on the front side of the counter as per instruction .				
	a) Approx. size of 6'-0"X2'-9"X2'-6" ( with front drawer unit and 8mm clear glass table top all edge polished )	<b>Nos</b>	<b>1.00</b>		
	b) Approx. size of 4'-6"X2'-6"X2'-6" ( with front drawer unit )	<b>Nos</b>	<b>2.00</b>		
	d) Approx. size of 4'-6"X2'-6"X2'-6" ( without front drawer unit )	<b>Nos</b>	<b>5.00</b>		
	e) Approx. size of 4'-6"X2'-6"X2'-6" (Daftari with drawer unit )	<b>Nos</b>	<b>0.00</b>		
	e) Approx. size of 5'-6"X2'-6"X2'-6" (May I help U with drawer unit as per design )	<b>Nos</b>	<b>0.00</b>		
<b>3.0</b>	<b>Storage Unit</b>				
	Providing and fixing of low/ full height storage cabinate having 450mm. depth of made out of 19mm th. block board having one horizontal intermediate shalves. The storage unit should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shade and <b>the inner surface is finished with 0.7 mm th inner laminate</b> . The work also include intermediate shaves as per design .The work should be completed according to drawing and design including all labour and materials.	<b>Sft</b>	<b>67.00</b>		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>4.0</b>	<b>Side Storage Unit</b>				
	Providing and fixing of table side storage cabinate as per mention size made out of 19mm th. block board having one/ two drawer unit at top and cupboard unit at bottom as per design / instruction by architect . The storage unit and drawer units should have locking arrangement with front shutter .The exposed surface is to finished with 1.0mm th.laminates as per design of approved shade and <b>the inner surface is finished with 0.7 mm th inner laminate</b> . The work also include intermediate shelves as per design .The work should be completed according to drawing and design including all labour and materials.				
	a) Approx. size of 3'-6" x 1'-6"X 2'-6"( manager )	<b>Nos</b>	<b>1.00</b>		
	b) Approx. size of 3'-0" x 1'-6"X 2'-6" ( officer )	<b>Nos</b>	<b>5.00</b>		
<b>D</b>	<b>OTHER WORK</b>				
<b>1.0</b>	<b>Suggestion box &amp; Cheque drop box</b>				
	Supplying and erecting free-standing suggestions box of overall size , 450 mm long x 300 mm deep x450 mm high made of 19 mm thick phenol formaldehyde block board, all as in drawing, complete. with hardware. fittings and fixtures of approved make and quality.Top and all exposed surfaces of block board are to be finished with 1mm thick laminate sheet of approved shade and quality. Inner faces of block board surfaces are to be finished with 0.7 mm th inner laminate of approved shades and quality . The shutter should have a glazed portion of size 6"x6" with 8mm. th. clear glass. The work should be done as per design including all labour , material, hardware etc.	<b>Nos</b>	<b>2.00</b>		
<b>2.0</b>	<b>Writing platform for customers &amp; application form set</b>	<b>Rft</b>	<b>3.00</b>		
	Providing , fitting , fixing writing platform at a height of 4' above floor level fixed to the wall made out of 19 mm BWP block board with lamination 1 mm tk on top & hard wood beading ducco painted . At least 10 nos vertical slip in chalan shelves attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6" height , 6" wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of				
<b>3.0</b>	<b>Notice Board</b>				
	Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. float glass. The work should be done including all labour and material.	<b>Sft</b>	<b>12.00</b>		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>4.0</b>	<b>False ceiling (Gypsum board.)</b>				
	False Ceiling (Gypsum Board) Providing & fixing in position false ceiling in Gypboard 12 mm thick for horizontals & Verticals fixed over G.I. frame work as specified by India Gupsm Co. Ltd. including trap doors for A.C. Unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft.	1,136.00		
<b>5.0</b>	<b>False ceiling ( Gride)</b>				
	Providing & fixing in position false ceiling in Armstrong 600 x 600 mm x 15/16 mm Dune Supreme RH 95 Prima tile with sheihard gride Tegular edge framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A. C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A. C. unit in 18 mm thick M. R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	Sft	0.00		
<b>6.0</b>	<b>Panelling</b>				
	Encasing to columns , banking hall entrance where ever shown in drawings by fixing 6mm ply to the frames made out of 40mm x20mm. 2 <sup>nd</sup> class treated hard wood like Kasi/Giringa by means of nailing or screwing over with 1 mm tk laminate fixed by means of adhesive having grooves & necessary white beach beading as directed by	Sft.	133.00		
<b>7.0</b>	<b>Electrical panel board cover</b>				
	Providing and fixing of electrical panel board cover made up of 19mm ply with two shutter at the front having T.W luvers as per drawing and design, it allso have furnished with locking arrangement. The exposed surface is finished with 1mm. Th. Laminates and inner surface is finished with two cote of plastic emulsion paint over one coate of primer . The work should be completed including all hardware, material and labour.	Sft	28.00		
<b>8.0</b>	<b>Façade of front entrance door.</b>				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.	Sft	80.00		

SL.N o.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
<b>9.0</b>	<b>Glazed display board.</b>				
	Providing and fixing glazed display board as per design and instruction of architect of size 1'6"x2'-6" of 12mm th. Glass of edge polished and 1" edge beveled and fixed on wall with 1" SS stude as per direction . The work include all labour and materials.	<b>Nos.</b>	<b>7.00</b>		
<b>10.0</b>	<b>Vertical blinds</b>				
	Supplying, fitting & fixing in position coloured 0.33mm thickness acrylic coated cleanable/ washable vertical blinds (Marvel or its equivalent, as approved) inclusive of all recommended accessories colour pattern etc., as per Architect's approval. The cost includes all the materials, labour, trasportation taxes etc., complete for the work.	<b>Sft</b>	<b>40.00</b>		
<b>11.0</b>	<b>Aluminium Grill</b>				
	Providing and fixing in position readymade anodized aluminum grill of approved design and quality fixed with continuous steam beech/teak wood beads of approved shape (finished 35 x 25 mm) all round, polished and coated with NC lacquer finish.(In cash cabins.)	<b>Sft.</b>	<b>42.00</b>		
<b>TOTAL</b>					

**B.O.Q OF INTERIOR WORK FOR INDIAN BANK ,ATM AT BHAWANIPATNA .**

<b>SL.No.</b>	<b>DESCRIPTION OF ITEMS</b>	<b>UNIT</b>	<b>QUANTITY</b>	<b>RATE</b>	<b>AMOUNT</b>
1	<b>FRONT ENTRANCE DOOR AND PARTITION</b>				
	Providing and fixing Entrance Door (glazed) as per drawing in black Anodised aluminium door single groove section of size 125mmx25mm (Jindal make) in top and bottom & sides glazed with 12 mm thick glass of approved make with chemical eaching design as per drg. . Item to include all necessary hardware of Stainless Steel finish as approved by the Project Consultant/Bank complete in all respects.				
	a) Open able portion ( it include SS finished H type 1'-6" long door handle )	<b>Sft</b>	<b>24.50</b>		
	b) Fixed portion	<b>Sft</b>	<b>34.00</b>		
2	<b>FLOOR SPRING</b>				
	Providing and fixing Godrej make heavy duty floor spring in entrance door with necessary fixtures and fittings etc.	<b>Nos</b>	<b>1.00</b>		
3	<b>FALSE CEILING</b>				
	Providing & fixing at site plain Gypsum Board false ceiling made out of 12.5 mm thick paper reinforced gypsum board sheets to be fixed with main frame channels of size(80 mm x 26 mm x 0.5 mm) at every 450 mm c/c, intermediate channels of size(15 mm x 45 mm x 0.9 mm) at every 1220 mm c/c with perimeter channel 20 mm x 26 mm x 0.5 mm all along the wall shall be provided . The frame work to be suspended with strap bolts as recommended using rail plugs 12.5 mm dia x 35 mm long with 6 mm dia bolt and soffit cleat. Ceiling surface is to paint with two coats of distemper to get a smooth & even look including the cost of hard ware fittings,all labour & materials.	<b>Sft</b>	<b>66.00</b>		



SL.No.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
4	<b>Façade of front entrance door.</b>				
	Providing and fixing in position Aluminium composite panel boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5 mm – 3 mm – 0.5 mm) including fabrication for the same with aluminium sections, required hardware, silicon sealant (Dow corning 789) masking tape, necessary scaffolding etc. as detailed in drawing complete in all respects.It also contain the shutter and lock system for the collapsable gate to hide at the entrance as per	<b>Sft</b>	<b>77.00</b>		
	<b>TOTAL</b>				

<b>INTERIOR WORK OF BRANCH :-</b>	
<b>INTERIOR WORK OF A.T.M :-</b>	
<b>TOTAL :-</b>	

**Total Amount In Words:-**