

PRICE BID OF INDIAN BANK KARUMKULAM BRANCH & ATM**Schedule of items for Furnishing works**

| Sl.No | Description | QTY | Unit | Rate | Amount |
|--------------|--|------------|-------------|-------------|---------------|
| A | BANKING AREA | | | | |
| 1 | Dismantling existing False ceiling, partitions, counters/tables after stage wise progress of work and stocking of serviceable material and disposal of unserviceable material from the site as directed by the bank official. | 1.00 | LS | | |
| 2 | Making necessary arrangement for the branch to function smoothly during the progress of renovation work that includes rearrangement of existing set up as required by branch from time to time. | 1.00 | LS | | |
| 3 | Glazed door : Providing and fixing entrance door using 12 mm toughned glass including floor springs of 120Kg with all necessary patches and Glass to glass lock round type (w/o cut out) patches for hanging the toughned glass ,etc complete. The door should have SS 'H'-type (45x425mm) door handles on both sides. All Edges of the glass to be polished and Provide Rubber beading/Weather proof ,The emblem and sticker works are as per the detailed drawing. | 4.45 | SQM | | |
| 4 | Frameless glazing:- Providing and fixing frame less glazing using 12 mm toughned glass with all necessary patches for hanging the toughened glass as per detailed drawing. All Edges of the glass to be polished and provide rubber beading/weather proof. The emblem and sticker works are as per the detailed drawing. The rate inclusive of cost and conveyance of all materials to site, lead, lift and labour charges for erection. | 3.92 | SQM | | |
| 5 | Full height Partition both side lamination :- Providing full height partitions with hard wood frames of size 5 x 5 cm vertically and horizontally at 60 CMS spacing, or at closer intervals as per site conditions, 6 mm BWR 303 grade ply and 1 mm laminate (in two colours as per design) of approved make on both sides of partition. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly, necessary cutting to be made in the plywood surface to fix switch boxes of electrical, telephone sockets, computer information outlets etc. Door to be done in same manner. Size: 90cmx210 cm with Cylindrical locks, SS Tower bolt, SS Hinges, door closure & stopper. (Measurement of payment only up | 5.79 | SQM | | |

Indian Bank

Prima Arch

| | | | | | |
|---|--|-------|-----|--|--|
| | to bottom of false ceiling. Main hard-wooden frame section of partition will go up to the bottom of RCC slab) | | | | |
| 6 | Half glazed and half paneled full height partition:- Providing full height partitions with hard wood frames of size 5 x 5 cm vertically and horizontally at 60 CMS spacing, or at closer intervals as per site conditions, 6 mm BWR 303 grade ply and 1 mm laminate (in colours as per design) on both sides upto 100 CMS high, glazing from +100 to 210 CMS level with 12 mm bevelled glass with emblem and sticker works and door. Glazing to be in big panels as per design wherever required. Glass to be fixed with polished decorative 2nd class teak wood beadings. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly, necessary cutting to be made in the plywood surface to fix switch boxes of electrical, telephone sockets, computer information outlets etc. Door to be done in same manner. Size: 75cm x 210 cm with Cylindrical locks, SS Tower bolt, SS Hinges, door closure & stopper. (Measurement for payment only up to bottom of false ceiling. Main section of partition will go up to the bottom of RCC slab) | 22.23 | SQM | | |
| 7 | Full height partition one side mica:- - Providing full height partitions with hard wood frames of size 5 x 5 cm vertically and horizontally at 60 CMS spacing, or at closer intervals as per site conditions, 6 mm BWR 303 grade ply and 1 mm laminate (in colours as per design) on one side and 2 coat enamel painting over one coat primer on other side. Wooden preservative to be applied on the hard-wooden frame before fixing the plywood. Providing provision for access doors wherever required in matching pattern. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly, necessary cutting to be made in the plywood surface to fix switch boxes of electrical, telephone sockets, computer information outlets etc. Door to be done in same manner with vision panel of size 45 X 45. Door Size: 90cm x 210 cm with Cylindrical locks, SS Tower bolt, SS Hinges, door closure & stopper. | 23.14 | SQM | | |
| 8 | Hollow Core Drywall partition:- - Providing & fixing approved make hollow core drywall system using 51mm wall framing systems as core with 9mm thick Fibre cement boards fixed according to company specifications including additional frames for fixing doors. The partition should withstand its weight. The joints shall be finished with putty to appear jointless. | 30.31 | SQM | | |

Indian Bank

Prima Arch

| | | | | | |
|----|---|-------|-----|--|--|
| | The partition shall be finished with good quality a coat of primer 2 coat painting etc. Complete. The partition shall be extended up to true ceiling or bottom of beam. | | | | |
| 9 | Low height partition:- Providing and fixing 120 CMS high partition with hard-wooden frame of size 5 x 5 cm vertically and horizontally at 60 CMS spacing, or at closer intervals as per site conditions. 6 mm BWR 303 grade ply wood and 1 mm laminate (in 3 colours) on both sides up to + 90 CMS level, 12 mm plain glass with slits, etching and edge polishing from + 90 to + 120 CMS level, .Glass to be fixed with polished 2nd class teak wood beadings. Necessary provision for electrical switches may be provided. | 14.28 | SQM | | |
| 10 | Front Glass:- Providing and fixing 12 mm plain glass with edge polishing. Glass to be fixed with polished wood beadings. The emblem and sticker works are as per the detailed drawing. | 4.14 | SQM | | |
| 11 | Single Window Counter partition:- Providing partitions for cash cabins with 5 x 5 CMS size hardwood frames vertically and horizontally at 60 CMS spacing, or at closer intervals as per site conditions, 6 mm BWR 303 grade ply and 1 mm laminate (in 3 colours as per design) on both sides up to 0 to 90cm height, glazing from +90 to +180 CMS level with 12 mm glass with etching and edge polished grooves, access doors wherever required in matching pattern with hardwood frames, Glazing to be in big panels as per design. Necessary holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly, necessary cutting to be made in the plywood surface to fix switch boxes of electrical, telephone sockets, computer information outlets etc. Door to be done in same manner. Size: 75cmx180cm with Night latch locks, all best quality hardware, SS Tower bolt, SS hinges, SS handle, & stopper. etc; complete. Glass to be fixed with polished wood beadings. Voucher tray of size 15 x 25 x 5 cm with 19 mm BWR 303 grad ply, 1 mm laminate, teak wooden lipping etc. to be given for each cash cabin | 9.93 | SQM | | |
| 12 | Semi glazed Flush doors with Both side Mica:- Providing and fixing 30 mm thick single leaf solid core and resin bonded flush door water proof quality with 1 mm thick lamination on both side with 12mm glass and etching including external wooden lipping all round the shutters, all as per drawing and instruction. the doors and lamination of approved make, colour and design including all best quality hardware, brass hinges, mortice lock with cylindrical | 1.59 | SQM | | |

Indian Bank

Prima Arch

| | | | | | |
|----|--|-------|-----|--|--|
| | lock, 7.5x1cm size hard wood skirting etc;. complete. | | | | |
| 13 | Semi glazed Aluminium door : Providing and fixing door using 10 mm glass and Particle board. 100x40x2.4mm (1.867kg/m) aluminium section on 4 side and middle up to 120cm height including all best quality hardware,SS Tower bolt, SS hinges, Mortise lock,Door closer,powder coated Aluminium handle fixed to the frame for All door etc;. complete | 3.18 | SQM | | |
| 14 | Wicket doors with Both side Mica 75 cm Height:- Providing and fixing 30 mm thick single leaf solid core and resin bonded flush door water proof quality with 1 mm thick lamination on both side external teak wooden lipping (2nd class teak wood) all-round the shutters, all as per drawing and instruction. the doors and lamination of approved make, colour and design including all best quality hardware, SS Tower bolt, SS hinges, lock etc; complete | 1.80 | SQM | | |
| 15 | Panelling:- Providing panelling to walls and pillars with 5x3 cm wooden frames at 60 cm c/c horizontally and vertically, 12 mm marine ply and 1 mm laminate, as required etc. complete. Lamination to be in 3 colours as per design | 19.80 | SQM | | |
| 16 | Clerical Counter:- Providing table type clerical counters 75 cms wide, 75 cms height, with table top, ,vertical dividers on both sides of drawer units and between counter seats all in 19 mm BWR 303 Grade plywood. 5x3 cm wooden frame to be given horizontally below inner edge of counter top for the entire length of the counter. Wooden foot rest of 7.5 x 3 cm size and necessary plywood frame work for drawer units to be given. Each seat (about 150 cm to 165 cm wide) to have CPU stand, key board tray and wire manager, three drawers with Godrej make multi latch locks, key board tray and CPU stand with 19 mm BWR 303 Grade ply and 1 mm laminate etc. Drawers to have 'Ebco' brand telescopic drawer slides.Counter top to be finished with 1mm thick laminate of approved colour and 8mm thick glass . All external surfaces 1 mm laminate finish and internal surfaces finished with two coats of enamel paint over two coat of primer & one coats of putty. Front vertical side of counter to be provided with two coloured lamination as per design etc. complete. 10mm thick wooden lipping for all exposed plywood edges. | 10.40 | RM | | |
| 17 | Single window counter:- Providing single window counters 90 cms wide, 113 cms height, ledger top 90 cm width, transaction top 60 cms width, vertical dividers on both side of drawer units and between counter seats all in 19 mm BWR 303 Grade plywood. | 1.62 | RM | | |

Indian Bank

Prima Arch

| | | | | | |
|----|---|-------|------|--|--|
| | 5x3 cm wooden frame to be given horizontally below inner edge of counter top for the entire length of the counter. providing 10mm thick wooden lipping for all plywood edges. Wooden foot rest of 7.5 x 3 cm size and necessary plywood frame work for drawer units to be given. Each seat (about 150 cm to 165 cm wide) to have CPU stand, key board tray and wire manager, key board tray and CPU stand with 19 mm BWR 303 Grade ply and 1 mm laminate etc. Ledger top & Transaction top to be finished with 1 mm laminate and 8mm thick glass. Front vertical side of counter to be provided with two coloured lamination as per design. All internal surfaces painted with two coat of primer, one coat putty & two coats of enamel paint. | | | | |
| 18 | False ceiling:- Providing seamless false ceiling with GI frame work and 12.5 mm thick gypsum board sheets , as per standard specifications of M/s.Gypsum India Limited for horizontal and vertical surfaces including providing cutouts for light fittings, painting with 2 coats of plastic emulsion paint over primer and putty etc. complete | 97.47 | SQM | | |
| b | Grid type false ceiling :- Providing & Fixing of grid type false ceiling with armstrong tile(Classic Lite tiles with Rivel edge frames) and armstrong suspension system as per standard specifications of Armstrong world industries including providing cutouts for light fittings, etc. complete | 92.72 | Sqm | | |
| 19 | Tables:- Providing table with 60 cms wide, 75 cms height, with table top, 5x3 cm wooden frame to be given horizontally below inner edge of counter top for the entire length of the counter. Providing 10mm thick wooden lipping for all plywood edges. Wooden foot rest of 7.5 x 3 cm size and necessary plywood frame work for drawer units to be given. Each seat (about 150 cm to 165 cm wide) to have CPU stand, key board tray and wire manager, three drawers with Godrej make multi latch locks, key board tray and CPU stand with 19 mm BWR 303 grade ply and 1 mm laminate etc. Top of the table should be with 1mm laminate and 8mm glass . Drawers to have 'Ebco' brand telescopic drawer slides.Counter top and all external surfaces finished with 1 mm laminate and internal surfaces finished with two coat of primer & one coats of putty & two coats of enamel paint .Front vertical side of counter to be provided with two coloured lamination as per design etc. complete. | | | | |
| a | Manager's table of size 200x 80 cms with 3 hard wood drawers as detailed above (without side unit) | 1.00 | EACH | | |
| b | Officer's table of size 150 x 75 cms with 1 drawer | 1.00 | EACH | | |

Indian Bank

Prima Arch

| | | | | | |
|----|--|------|------|--|--|
| | and 1 storage space as detailed above (without side unit) | | | | |
| 20 | Side unit for table:- Providing table side unit with 19mm BWR 303 grade ply for top, intermediate shelf, three vertical sides, sliding doors and 9 mm ply wood for rear side. All external surfaces and top including rear side with 1 mm laminate finish, all fixtures, Godrej locks nylon bushes, wooden lippings etc. complete. All internal surfaces finished with two coat of primer & one coats of putty over two coats of enamel paint. | | | | |
| a | Manager Cabin 120x45x75 cm size | 1.00 | EACH | | |
| b | Cash cabin 135x45x75 cm size | 1.00 | EACH | | |
| 21 | Writing ledge / cheque drop box / suggestion box -Supply/ installing wall mounted writing desk, cheque drop box, suggestion box as per detailed drawing. Outer sides shall be laminated and inner sides shall be painted with two coats of enamel paint over a coat of primer & two coats of putty. | 1.00 | EACH | | |
| 22 | | | | | |
| 23 | Counting room table :- Providing table type counters 60 cms wide, 75 cms height, with table top, front apron, vertical dividers 19 mm BWR 303 grade plywood. 5x3 cm wooden frame to be given horizontally below inner edge of counter top for the entire length of the counter. Wooden foot rest of 7.5 x 3 cm size. Counter top to be provided with 1mm laminate . All external surfaces 1 mm laminate finish and internal surfaces with enamel finish. 10mm thick beach wood lipping for all plywood edges. | 3.33 | Rm | | |
| 24 | Pantry Counter, :- Providing table type pantry counters 60 cms wide, 75 cms height, with table top, front apron, vertical dividers 19 mm BWR 303 grade plywood. 5x3 cm wooden frame to be given horizontally below inner edge of counter top for the entire length of the counter. Wooden foot rest of 7.5 x 3 cm size. Counter top to be provided with 20 mm edge bevelled and edge polished granite (jet black). All external surfaces 1 mm laminate finish and internal surfaces with enamel finish. 10mm thick beach wood lipping for all plywood edges. | 4.48 | Rm | | |
| 25 | Full Ht./Low Ht. Laminated Storage - Fabricating and fixing 45cm deep storage unit constructed out of 19mm. Thk BWR.ply sides and 19mm thick shutters-side hung with 1mm laminate, 12mm.thk hHW lipped BWR.ply bottom with MS Hinges. Exposed edges should be provided with wooden lipping. All external surfaces and top including rear side with 1 mm laminate finish, all fixtures, Godrej locks nylon bushes, wooden lippings | 5.04 | Sqm | | |

Indian Bank

Prima Arch

| | | | | | |
|--------------|---|------|-----|--|--|
| | etc. complete. All internal surfaces finished with two coat of primer & one coats of putty over two coats of enamel paint. | | | | |
| 26 | NOTICE BOARD :- | | | | |
| | Providing and fixing pinup boards. It consists ½” soft boards of good density to be mounted over 19 mm thick BWR grade plywood. The soft board will be covered with a plain fabric (approx. Rs.150 /Rmt.) from front and edges. Suitable moulding (as directed by architect) will be fixed on all four sides and will be finished in polish. | 1.00 | No | | |
| | Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately. | | | | |
| | TOTAL | | | | |
| B ATM | | | | | |
| 1 | Glazed door : Providing and fixing entrance door using 12 mm toughned glass including floor springs of 120Kg with all necessary patches and Glass to glass lock round type (w/o cut out) patches for hanging the toughned glass ,etc complete. The door should have SS 'H'-type (45x425mm)door handles on both sides. All Edges of the glass to be polished and Provide Rubber beading/Weather proof ,The emblem and sticker works are as per the detailed drawing. | 1.91 | SQM | | |
| 2 | Frameless glazing:- Providing and fixing frame less glazing using 12 mm toughned glass with all necessary patches for hanging the toughened glass as per detailed drawing. All Edges of the glass to be polished and provide rubber beading/weather proof. The emblem and sticker works are as per the detailed drawing. The rate inclusive of cost and conveyance of all materials to site, lead, lift and labour charges for erection. | 2.46 | SQM | | |
| 3 | Full height partition both side ACP:- Providing full height partitions with hard wood frames of size 5 x 5 cm vertically and horizontally at 60 cms spacing, or at closer intervals as per site conditions, 6 mm marine ply and 1 mm ACP (in colours as per design) on both side.wooden preservative to be applied on the wooden frame before fixing the plywood. (Measurement of payment only up to bottom of false ceiling. Main wooden frame section of partition will go up to the bottom of RCC slab) | 2.62 | SQM | | |

Indian Bank

Prima Arch

| | | | | | |
|---|---|-------|------|--|--|
| 4 | Internal ACP Cladding:- Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. | 14.14 | SQM | | |
| 5 | Hollow Core Drywall partition one side ACP:- Providing & fixing approved make hollow core drywall system using 51mm wall framing systems as core with 10mm thick Fibre cement boards fixed according to company specifications on one side and 6 mm BWR 303 grade ply and 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (in colours as per design) on other side including additional frames for fixing doors. The partition should withstand its weight. The joints shall be finished with putty to appear jointless. The partition shall be finished with good quality a coat of primer 2 coat painting etc.complete.Necessary holes must be made in the frame sections to run the wires ,computer cables wherever necessary. Door to be done in same manner with vision panel of size 45 X 45. Door Size: 75cm x 210 cm with Cylindrical locks,SS Tower bolt, SS Hinges, door closure & stopper. The partition shall be extended upto true ceiling or bottom of beam. | 9.00 | SQM | | |
| 6 | False ceiling:- Providing seamless false ceiling with GI frame(Gypsum India Limited) work and 12.5 mm thick gypsum board sheets , as per standard specifications of M/s.Gypsum India Limited for horizontal and vertical surfaces including providing cutouts for light fittings, painting with 2 coats of plastic emulsion paint over primer and putty etc. complete | 5.17 | SQM | | |
| b | Grid type false ceiling :- Providing & Fixing of grid type false ceiling with Armstrong tile, Model: Classic Late RH99 Armstrong. (Classic Late tiles with Ravel edge black groove grid frames) and Armstrong suspension system as per standard specifications of Armstrong world industries including providing cut-outs for light fittings, etc. complete | 2.18 | Sqm | | |
| 7 | cheque drop box / suggestion box -Supply/ | 0.00 | EACH | | |

Indian Bank

Prima Arch

| | | | | | |
|---|---|------|-----|--|--|
| | installing wall mounted writing desk, cheque drop box, suggestion box as per detailed drawing. Outer sides shall be laminated and inner sides shall be painted with two coats of enamel paint over a coat of primer & two coats of putty. | | | | |
| 8 | NOTICE BOARD :- | | | | |
| | Providing and fixing pinup boards. It consist ½” soft boards of good density to be mounted over 19 mm thick BWR grade plywood. The soft board will be covered with a plain fabric (appox Rs.150 /Rmts.) from front and edges. Suitable moulding (as directed by architect) will be fixed on all four sides and will be finished in polish. | 0.00 | Sqm | | |
| | Note : Only soft bords provided on other than the partitions will be measured and soft board made in the partitions will be the part of the partition measurement (rate) and not consider separately. | | | | |
| | TOTAL | | | | |
| | Grand Total | | | | |
| | ADD GST 18% | | | | |
| | Grand Total | | | | |

(Rupees.....)

.....Only)