

C	AIR- CONDITION WORKS :(For Branch & ATM)				
S.No.	Item	Qty.	Unit	Rate in Rs.	Amount (Rs.P)
1.00	Supply,installation, testing & commissioning of the following Cordless Hi-wall with <u>4 star</u> rated Split Air conditioners fitted Reciprocating / Rotary compressors, including copper pipping / drain pipping etc.				
a	2.0 TR with 5.0 KVA Stabiliser	2.00	Nos		
b	1.5 TR with 5.0 KVA Stabiliser (Branch)	3.00	Nos		
c	1.0 TR with 5.0 KVA Stabiliser (Branch)	1.00	Nos		
d	1.0 TR with 5.0 KVA Stabiliser (ATM)	2.00	Nos		
2.00	Supply, installation, testing & commissioning of the following Soft drawn copper piping with 9 mm thick Nitrile rubber, Wiring between indoor / out door unit, insulation including all necessary fittings between indoor and out door air cooled condensers of the 25 mm in size & Along With Main Pipe.	28.00	Rmt		
3.00	Supply, fixing, testing & commissioning of the Condenser supports .				
	For Split AC Unit	8.00	No.		
4.00	Minor Civil works (chipping for drain pipe, replastering for the same)	8.00	No.		
TOTAL Amount for (Air-conditioning works) C:					
Rupees					