

SECTION - IV
AIR - CONDITIONING WORK

SL. NO.	ITEM DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1.1	Supply, installation, testing and commissioning of 2.00TR Hi-wall split units, R-22 duty with hermetically sealed rotary compressor with indoor and outdoor units, refrigeration pipe, electrical, etc.	Each	3		
1.2	Supply, installation, testing and commissioning of 1.50 TR Hi-wall split units, R-22 duty with hermetically sealed rotary compressor with indoor and outdoor units, refrigeration pipe, electrical, etc.	Each	1		
1.3	Supply, installation, testing and commissioning of 1.00 TR Hi-wall split units, R-22 duty with hermetically sealed rotary compressor with indoor and outdoor units, refrigeration pipe, electrical, etc.	Each	1		
1.4	MS welded platform for maintenance for ODUs including safety cage	Each	5		
1.5	Supplying, installation, testing and commissioning of Drain Water Pipes G.I. with 10 mm thick Kinifoam insulation beyond initial length of 5.00 mtr. for each A.C units. 25 MM NB	Mtr.	45.00		
1.6	Supplying, installation, testing and commissioning of Copper Refrigerent Pipes with necessary insulation beyond initial length of 5.00 mtr. for each A.C units.	Mtr.	40.00		

TOTAL CARRIED TO ELECTRICAL SUMMARY :