

**QUOTATION FOR FOR ELECTRICAL WORK AT "HADAPSAR BRANCH" INDIAN BANK..**

Sr No	Description	Qty	Unit	Supply & Labour	
				Rate Rs.	Amount Rs.
<b>I</b>	<b>Supply, Erection,testing, commissioning of following Light Fittings for Recessed &amp; Surface Type Ceiling</b>				
A-1	SITC of 2 X 36 W CFL Direct-Indirect recessed Mounting light fittings, with 2X36W CFL lamps, hanging arrangement with chain/rod for support form ceiling etc complete. Along with wiring from the Junction Box upto light fittings in Flexible PVC Conduit.	10	Nos		
A-2	SITC of 1X18W CFL Down lighter Fitting with Frosted Glass cover, with 18W CFL lamp, Hanging Arrangement with chain/rod for support form ceiling etc complete. Along with wiring from the Junction Box upto light fittings in Flexible PVC Conduit.	6	Nos		
A-3	SITC of 2X16W CFL Down lighter light fittings, with 2X36W CFL lamps, arrangement for fixing of fitting on ceiling or Gypsum false ceiling etc complete. Along with wiring from the Junction Box upto light fittings in Flexible PVC Conduit.	16	Nos		
A-4	SITC of 1X28W T5 Tube Light Fitting with Acrylic diffuser, brackets for fixing on wall/ceiling, with wiring from ceiling rose upto the tube light fitting etc complete.	10	Nos		
A-5	SITC of 1X11W CFL Light Fittings with lamp to be erected on wall for toilet & passage lighting	3	Nos		
A-6	SITC of 12" Wall Mounted Fan. Make USHA/Crompton	3	Nos		
A-7	SITC of 1200 mm Sweep Ceiling fan. Make USHA/Crompton	6	Nos		
A-8	SITC of 8" Exhaust Fans with Louvers to be erected in the aluminum frame.	3	Nos		
				<b>Total I</b>	
<b>II</b>	<b>Lighting &amp; Point Wiring</b>				
A-8	SITC of Concealed/above false ceiling <b>Primary Light Point</b> with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch in modular box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from SWitch Board)	20	Nos		
A-9	SITC of Concealed/above false ceiling <b>Secondary Light Point</b> with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from Primary Point)	10	Nos		
A-10	SITC of Concealed/above false ceiling <b>Emergency light Point</b> with 2X2.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch & 6A 2in1 Socket erected on modular box with all other required accessories etc. complete.	8	Nos		
A-11	SITC of concealed/above false ceiling <b>Exhaust Fan Point</b> with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch in modular box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from SWitch Board)	0	Nos		
A-12	SITC of concealed/above false ceiling <b>Ceiling Fan Point</b> with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch 7 5 step Fan Speed Regulator in modular box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from Switch Board)	3	Nos		
A-13	SITC of concealed/above false ceiling <b>Independent 6A Point</b> with 2X2.5 sq. mm + 1X1 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch & 6A 2in1 Socket erected on modular box with all other required accessories etc. complete. (Max. Distance of PPoint from DB 5 mtrs)	10	Nos		
A14	SITC of concealed / false Ceiling Looped 6A Point with 2 x 2.5 sq mm + 1x 1 sq mm FRPVC wiring in PVC pipes ( of ISI make ) along with Anchor make Roma / Legrand Mosaic make Modular 6 A switch & A 2 in 1 Socket erected on modular box wil alll other required accessories etc complete. to be looped from Primary Point ( Max dist 3 mtrs )	15	Nos		
A-15	SITC of concealed/above false ceiling/ on partition / wall <b>Power Point 16A Point</b> with 2X4 sq. mm + 1X1 .5 sq. mm FR PVC Wiring in pvc pipe (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 16A Switch & 6/16A 2in1 Socket erected on modular box with all other required accessories etc. complete. (Max. Distance of Point from DB 5 mtrs)	3	Nos		
A-16	SITC of Primary Ligth Point with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch in Surfaec Box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from SWitch Board)	0	Nos		
A-17	SITC of Secondary Ligth Point with 2X1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from Primary Point)	0	Nos		
A-18	SITC of Emergency light Point with 2 X 2.5 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch & 6A 2in1 Socket erected on Surfaec Box with all other required accessories etc. complete.	UR	Nos		

A-19	SITC of Exhaust Fan Point with 2 X 1.5 sq. mm + 1X 1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch in Surface Box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from Switch Board)	UR	Nos		
A-20	SITC of Ceiling Fan Point with 2 X 1.5 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch 7 5 step Fan Speed Regulator in Surface Box with all other required accessories etc. complete. (Max. Point Len. 5 Mtrs from Switch Board)	UR	Nos		
A-21	SITC of Independent 6A Point with 2 X 25 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch & 6A 2in1 Socket erected on Surface Box with all other required accessories etc. complete. (Max. Distance of Point from DB 5 mtrs)	UR	Nos		
A-22	SITC of Looped 6A Point with 2 X 25 sq. mm + 1X1 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 6A Switch & 6A 2in1 Socket erected on Surface Box with all other required accessories etc. complete. To be looped from primary point. (Max. Distance of Point from Primary Point 3 mtrs)	UR	Nos		
A-23	SITC of Power Point 16A Point with 2 X 4 sq. mm + 1X1 .5 sq. mm FR PVC Wiring in Casing Caping (of ISI Make) along with ANCHOR ROMA/LEGRAND MOSAIC make Modular 16A S.Pole & 6/16A Socket erected on Surface Box with all other required accessories etc. complete. (Max. Distance of Point from DB 5 mtrs)	7	Nos		
A-23 a	Providing & fixing 16 A.S. Pole M.C.B. with enclosure for 3 Phase.	7	Nos		
Tender Item	Description	Qty	Unit	Supply	
				Rate Rs.	Amount Rs.
A-25	SITC of 2 X 4 + 1 X 1.5 sq. mm FR PVC Wiring in Concealed/above false ceiling PVC Conduits.	150	Mtrs		
A-26	SITC of 4 X 4 + 1 X 2.5 sq. mm FR PVC Wiring in Concealed/above false ceiling PVC Conduits. (A.C wiring)	125	Mtrs		
A-27	SITC of 2 X 2.5 + 1 X 1 sq. mm FR PVC Wiring in Casing Caping.	UR	Mtrs		
A-28	SITC of 2 X 4 + 1 X 1.5 sq. mm FR PVC Wiring in Casing Caping.	UR	Mtrs		
A-29	SITC of 4 X 4 + 1 X 2.5 sq. mm FR PVC Wiring in Casing Caping.	UR	Mtrs		
A-30	Type 1 Modular Switch & Socket ( U.P.S ) on Counter, Manager Cabin, Server Room,				
	SITC of computer power supply box comprising 3 nos White coloured Anchor Roma modular type 6 A socket & 1 no 16 A modular switch housed in a molded box with front plate & back box. ( Box fixed on wall /partition.	8	Nos		
A-30	SITC of Main DB, Fabricated non compartmentalised, Dual Source Multi function meter for kWh readings (DG & MSEDCL), Indicating Lamps, Cu. Bus Bars with 63A MCCB incomers for MSEDCL & DG with Conectors for logic operation, 63A TPN MCB outgoing feeders .Providing & fixing of 100A 415V Strip type Bus bar,etc complete	1	No.		
A-31	SITC of 4 Way TPN Distribution Board (Lighting DB) with 32Amp, TPN incomer MCB & Twelve nos of 6A SP MCB's. To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Name Plate on DB	1	No.		
A-32	MCB & upto Twelve nos of 10/16/20A SP MCB's. To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Name Plate on DB	1	No.		
A-33	SITC of 4 Way TPN Distribution Board (USP incoming DB) with 32Amp, TPN incomer MCB. To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Brass Name Plate on Distribution Board etc complete	1	No.		
A-34	SITC of 4 Way TPN Distribution Board (USP Outgoing DB) with 32Amp, TPN incomer MCB & about Twelve nos of 6A SP MCB's. To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Name Plate on Distribution Board etc complete	1	No.		
A-35	SITC of 4 Way Distribution Board (Inverter incoming DB) with 32Amp, TPN incomer MCB. To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Name Plate on Distribution Board etc complete	1	No.		
A-36	SITC of 6 Way SPN Distribution Board (Emergency DB) with 32Amp,DP incomer MCB & 4 nos of 6A SP MCB's . To be erected on wall/concealed in wall with necessary hardware, ferruling the wires for identification (phase, neutral & earth wires), tagging the outgoing MCB's for identification of circuits, Name Plate on Distribution Board etc complete	1	No.		
				Total II	

III	<b>Earthing</b>				
A-37	SITC of 600x600x6 Copper Plate type Earthing as per BIS 3043, with specifically prepared earth pit @ 2.5 mtrs deep. With alternate layers of charcoal & salt, 50 X 6 GI. Earth Strip from earth plate up to surface with Plated Nut Bolts. Earth Strip shall have two holes at the top to provide good earthing continuity for the earth strip connected to earth pit. CI Funnel, @ 1' 6" X 1' 6" CI chamber cover etc complete. Earth pits to be marked with paint for earth pit numbering [Earth Pits to be made in Hard Murum Strata]	3	No.		
A-38	SITC of 25 X 6 mm Copper Earth Strip to be laid from Earth Pit earthing points.	25	Mtrs		
A-39	SITC of 1C X 6 sq. mm YY Yellow Green Cable. (for UPS Earthing, All Distribution Boards Earthing)	25	Mtrs		
A-40	SITC of 1C X 10 sq. mm YY Yellow Green Cable. (for UPS Earthing, All Distribution Boards Earthing)	10	Mtrs		
				<b>Total III</b>	
IV	<b>DATA &amp; Telephone Wiring</b>				
A-41	SITC of 2 pair twisted 0.5 sqmm annealed Cu flex cable for Telephone to be laid through PVC Pipes along with all other accessories.	45	Mtrs.		
A-42	SITC of 10 pair armoured jelly filled 0.5 sq mm annealed Cu cable for telephone to be laid from EPBX extension to chrone JB	10	Mtrs.		
A-43	SITC of crone Junction Box suitable for termination of 10 telephone terminals to be mounted on wall or structural member, powder coated with pad lock facility.	1	No		
A-44	SITC of Beetel Phone with display & memory with patch cord & terminal	UR	No.		
A-45	Supply & erection of LAN cable (CAT 6) to be erected through Casing Caping along with all other accessories.	240	Mtrs.		
A-46	Supply & erection of RJ 45 terminal suitable for modular slot & Lucent type terminal arrangement	12	No.		
A-47	Supply & erection of RJ 11 terminal suitable for modular slot & Lucent type terminal arrangement	3	No.		
A-48	SITC of Alumenium ways 50X32mm with good finish complete with necessary accessories for jointing, termination etc, to be erected below flooring with proper clamping arrangement etc complete.	0	Mtrs		
A-49	SITC of Floor boxes 150X150X50 with good finish, entry from all sides with sealable caps, Box must have matt finish SS Plate on top which will have to be fixed after completion of flooring.	0	No.		
A-49A	P & f 6 Watt Philips / Ahuja make ( Concealed in false ceiling )	0	Nos		
A-49 B	P & f Amplifier of " Boss " / Ahuja " make 40 watt with proper termination.	0	No		
A-49C	P & f Speaker wires in conduit at required terminals				
				<b>Total IV</b>	
<b>Tender Item</b>	<b>Description</b>	<b>Qty</b>	<b>Unit</b>	<b>Supply</b>	
				<b>Rate Rs.</b>	<b>Amount Rs.</b>
<b>V</b>	<b>Supply Installation Testing Commissioning of 1.1 KV PVC Insulated PVC Sheathed Armoured/ Unarmoured LT Cables (Polycab/RRKabel) including PVC Pipes, Fittings &amp; Accessories, Mounting of Pipes on Wall/ceiling, Terminaiton of these cables with Lugs (Material of Lug must be same as that of cable material). Ferruils, Cabel Tans etc complete</b>				
A-50	3 1/2C X 25 Sq.mm AYFY. (from Meter Board to Main DB, DG Set to Main DB)	12	Mtrs		
A-51	4 C X 10 Sq.mm YY. (From Main DB to Power DB)	10	Mtrs		
A-52	4 C X 6 Sq.mm YY. (From main DB to UPS Incomer DB, UPS to UPS Outgoing DB)	10	Mtrs		
A-53	4 C X 4 Sq.mm YY. (From main DB to Lighting DB )	15	Mtrs		
A-54	3 C X 2.5 Sq.mm YY. (From UPS Outgoing DB to Power Sockets, Lighting DB to Switch Boards )	250	Mtrs		
				<b>Total V</b>	
<b>VI</b>	<b>9U , 19" 450 mm DX 300mmW, Closed Wall mount MS 18 SWG Powder Coated Rack with Glass Door Opening in front with power panel cabel</b>	1	No		
				<b>Total VI</b>	
				<b>Grand Total</b>	
AMOUNT RS :					

RATES INCLUSIVE OF ALL TAXES & LIABILITIES.

**Conditions :**

Quoted rates has to be inclusive of all taxes duties labour material , scaffolding , Cleaning of site premises etc.  
As tender to be item tender, final bill will be as per quantity executed on site as per instructions.

**SPECIFICATION OF MATERIAL TO BE USED FOR EXECUTION OF ELETRICAL WORK.**

Sr No	Specification	Make
1	Cable (Fire Retardant)	Finolex/ Polycab / R.R equivalent
2	Wires ( Fire Retardant)	Finolex/Equivalent
3	Casing Caping	Modi
4	Luminaries ( Lamp)	Philips/Wipro/Bajaj/Osram
5	Electrical fittings ( Light fittings)	Philips/Wipro/Bajaj
6	MCB DB etc	Legrand/L&T/Switchgear/ Sceneder
7	Speaker	Philips/ Equivalent
8	P.V.C pipes	Precision/modi
9	Fan ( Ceiling/ Wall mounted/ Pedestal)	Bajaj/Crompton/Equivalent
10	Modular Switches	legrand (Mosaic )/ Equivalent
11	Covered Switches	Legrand/ Anchor Roma.

**Note**

- 1 Samples of all items will be approved by the consaltant & Bank Authority only.
- 2 Consultant & Bank Authority holds the Right to install any of above fittings etc mentioned, without change in rates
- 3 Workmanship has tobe of Good Quality only.
- 4 All Concealed wiring , unless suggested, cost inclusive of chistling, laying, finishing etc inclusive.
- 5 Rates Shall be Inclusive of All Taxes Duties, Octroi Transport , Labour etc , without extra cost .
- 6 Litght fittings rates shall be quoted inclusive of lamp cost labour , & hardware etc inclusive .

Seal Of Contractor

**QUOTATION FOR INTERIOR WORKS FOR INDIAN BANK , "HADAPSAR (Sasane nagar)" Branch PUNE .**

FIX FURNITURE & ALLIED WORKS						
Sr No	No	Specification	Qty	Unit	Rate	Amount
I		<b>ENTRANCE :</b>				
	a	<b>Entrance Glazed Door : ( 12 mm thk Toughned Glass )</b>	28	Sft		
		Providing & fixing Entrance Door @ 4'0" X 7'0" along with all necessary hardware, Door Closer/ Floor machine , Door Stoper, 25 mm dia 2'0" " H / D type S.S Handle etc complete.				
	b	<b>Side Panelling : ( to cover side wall &amp; Rolling shutter channel )</b>	80	Sft		
		Providing & fixing side panelling made in 19 mm htk ply finished with Aluminum composite sheet ( Out door quality ) etc complete.				
	c	<b>External Partition. 4" Width.</b>	75	Sft		
		Partition :P & f Partition min 4" wide made in Composite panel (Sheet @1.5mm thk ) Aluminu section@ 1.5" x 4" , 2'0" c/c ( standard format ) upto 3'0" ht.Composite Sheet on both sides. ( Silver/ as approved .				
	d	<b>Aluminum Sliding Window. ( 3Track ) ( Jindal / Heavy equivalent )</b>	51	Sft		
		P & fixing Powder coated Aluminum sliding window, 3 track. Clear glass along with frosted flim, as per the direction .etc complete.				
	e	<b>Toughned Glass partition.</b>	35	Sft		
		P & Fixing Toughned Glass partition ( 12 mm thk ) in Aluminum Anodised , profile , press fit method, along with frosted film as per direction.				
II		<b>AT MANAGER CABIN.</b>				
	a	<b>Partition: As per Detail</b>	160	Sft		
		P & F Partly Glazed Partition made in @ 2 1/2" x 2" Salwood frame 2'0" c/c, 6mm ply fixed on both side sides,1mm thk laminate from both sides,6m thk glass with frosted/ clear film, matching Zinc polish Beading , Provision for Data & Power conduit running , Fixing of Switch Boards, including Gazed Shutter with "D" Type handle, Ball Bearing Hinges, Door Closer etc complete.				
	b	<b>Manager,s Table: @ 6'6" x 2'6", Side Ledge: 3'6" x 1'9" ( As per Detail)</b>	1	No		
		Providing & fixing Table & Side Storage made in 25mm PLB, 19 mm PLB , Drawers with Telescopic Channels, 3" S.Steel Handles, Locks, Post formed Top, As per Detail Dwg,6 mm thk polished Glass top. etc complete.				
	c	<b>Chairs:</b>				
		Providing Cushioned Chairs with P.U Back, Gas lift technology, Revolving Chair, with Standard Co Warranty for min 1 Year. ( Revolving )				
		Mgr Chair (High Back Chair) ( As per Approved )				
	d	<b>Customer Chair</b>				
		(Chairs with 1 Year written Warranty from manufacturer.)( "S" Profile )				
	e	<b>Low Height Storage @ 7'0" x 3'0" )</b>	21	Sft		
		Providing & fixing Low Height Storage made in P.L.B , Brass, S.S Hinges, @ 4" S.S handles, Etc complete.Painted/ Polished internally. A sper detail etc complete.				
IV		<b>BANKING HALL / CUSTOMER LOBBY</b>				
	A	<b>At Low Height Counter with Storages etc complete.</b>				
	a	<b>Cash Counter &amp; Clerk Counter @3'9" Ht( As per Detail )</b>	10.5	Rft		
		P & fixing Counter made in PLB, 12mm thk toughned Glass, necessary Hardware, 10 mmthk Glass for service platform, 6 mmthk glass at working top as per detail Dwg , with lockkable Storages , 2 lockable drawers with slauts to keep cash, metal Key board drawer with mouse pad & storage.platform to keep C.P.U ,etc complete.partition/ race way for Electrical wires, Lan Cabling etc.				

	b	<b>Officer Counter table / Clerk table @2'6" Ht ( As per Detail )</b>	9.5	Rft		
		P & fixing Counter made in PLB, 12mm thk toughned Glass, necessary Hardware, 10 mmthk Glass for service platform, 6 mmthk glass at working top as per detail Dwg , with lockkable Storages , 2 lockable drawers Key board drawer with mouse pad & storage,platform to keep C.P.U, etc complete,partition with provision for Electrical wires, Lan Cabling etc. table top with 6 mm thk edge polished glass top .				
	c	<b>Medium High back Chair ( Officer )</b>				
	d	<b>Visitors Chair ( medium back with " S " profile )</b>				
	e	<b>Low back Chair 1( Clerk Cashier ( 2 )</b>				
	f	<b>Cushioned Chair ( Daftari )</b>				
<b>Sr No</b>	<b>No</b>	<b>Specification</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
		<b>Partition</b>				
	a	<b>Full Height side Partition for Cash Counters ( As per Detail) 5'0" ( along with Shutter )</b>	132	Sft		
		P & F Partly Glazed Partition made in @ 2 1/2" x 2" Salwood frame 2'0" c/c, 6mm ply fixed on both side sides,1mm thk laminate from both sides, 6 mm thk toughned glass/ Aluminum Grill as per site requirement. Provision for Electrical & Power conduit running , Fixing of Switch Boards, Cutout in side glass/ Aluminum Grill with tray, for trasaction. provision Fixing of Switch Boards, including 3" thk Grilled/ Glazed Shutters with "D" Type handle, Ball Bearing Hinges,Dead lock, as per requirement etc complete. as per requirement etc complete.				
	b	<b>Fascia Glazed Partition above 3'9"at cash Counter, (2'0" ht )( As per Detail)</b>	20	Sft		
		Fascia Glazed Partition @ 2'0" ht made in Crystal edge polish 12mm thk toughned Glasswith @ 9"dia semicircle cutout & @ 4" dia cutout , fixed in " D " Brackets on side partition.				
	c	<b>WICKET DOOR ( 2 Leaf )</b>	20	Sft		
		P & F 2 Leaf 3"thk Wicket Wicket Door,with locking arrangement, latch, laminated from both side , etc complete.				
	d	<b>DAFTARI Table ( As per Detail) @ 2'6"" x 2'3"</b>				
		Providing & making of Daftari table made in PLB with 1.5" Thk top, foot rest, @ 2 Drawers, Side Storage as per requirement,with top Skirting etc complete.				
	f	<b>SEATING ( In Lobby &amp; Banking Hall )</b>				
		<b>3 Seater</b>	2	Nos		
		Providing 3 Seater Sofa made in silver Powder coated mesh, & crome plated legs. With comfortable seating ( As per Approval )				
	g	<b>Slip Writing Counter . @ 1' 0" wide Polished Edge Granite top</b>	5	Rft		
		Providing & fixing table made in Ply with storage arrangement & Edge polish Granite Top ( Granite : Lakha Red/ equi )with 3" laminated Skirting above.				
	i	<b>Rear Full Height Storage Unit ( Below Staircase )</b>	32	Sft		
		Providing & fixing Full Height Storage made in P.L.B , Brass, S.S Hinges, @ 4" S.S handles, Etc complete.Painted/ Polished internally.				
<b>VII</b>	j	<b>Partition inside Strong Room for Safe.</b>				
		P & F partition made in T.W 2" x2" frame structure 2'0' C/C with pre laminated sheet inserted in frame, Melamined polished frame. Etc complete.	45	Sft		

		<b>MEZZANINE FLOOR</b>				
<b>VIII</b>		<b>SERVER ROOM</b>				
	a	<b>Partition between Loan Section Server Room ,</b>	77	Sft		
		Providing & fixing Partition made in Ply, T.W Sections, 6 mm ply fixed on both sides 6 mm thk glass ,laminate, finish on both sides upto 7'0" ht .Partly Glazed door with Lock, handle, Door closer etc complete.				
	b	<b>Computer Table ( For Server ) 10'3" x 2' 3"</b>	10	Rft		
		Providing & making table made in PLB with laminated , Side Storages, Key Board Drawers, Power & data Race way above table top. etc complete.				
	c	<b>Partition for Mezzanine Floor &amp; Lower Banking hall. ( To enclose Mezzanine Floor )</b>	232	Sft		
		Providing & fixing Partition made in Ply, T.W Sections, 6 mm ply fixed on both sides 6 mm thk glass ,laminate, finish on both sides upto 7'0" ht .Partly Glazed door with Lock, handle, Door closer etc complete.				
	d	<b>Partition between Server Room U.P.S Room &amp; Staitionary Room ,</b>	145	Sft		
		Providing & fixing Partition made in Ply, Aluminum Sections 50 mm x 25 mm , 6 mm ply fixed on both sides, 5 mmthk wired glass fixed above 3' upto 7' 0", laminate, finish on both sides upto ceiling ,Partly Glazed Door,with Door closer, Lock etc complete .				
	e	<b>Staff Chair</b> ( Specs as per clerk chair )				
<b>XII</b>		<b>OTHER WORKS</b>				
	a	<b>Race Way</b>	85	Rft		
		Power Race Way: Providing & fixing Raceway 6" wide made in ply, finished in laminate & fixed to wall with S.S coated cap screws, & making provision for Switch boards & data peripherals , etc complete.				
	b	<b>Panelling: ( For Enclosing A.C Copper Pipes , Drain Pipes &amp; Data &amp; Power cables )</b> P & f panelling made in Ply/ B.B / M.D.F , & finished with laminate / Paint as per site conditions.(or as directed ) in A.T.M Room ( incl Rolling shutter side Jam)	265	Sft		
	c	<b>Vertical Blinds :</b> <b>Providing &amp; Fixing Vertical Blinds of "Vista Levolor" Make / equi</b> Vista " Dust Guard Vibrant " Series. Along with Powder coated track system.	125	Sft		
	d	<b>Suggestion Box &amp; Cheque Drop Box</b> Providing & fixing powder coated M.S Suggestion Box & Cheque drop box ( With Top Flap & Glass for view ).	2	No		
		<b>Total Expenditure for Furniture</b>				
		<b>FALSE CEILING</b>				
<b>3</b>	a	<b>False Ceiling along with Plastic emulsion paint for gypsum band :</b> P & f Combination of ArmStrong Ceiling tiles with Gypsum ceiling @ ( 70 : 30 ratio ), with necessary light cut out, with 3 " flat cornice/ cove in gypsum ( 6" vertical drop of gypsum ) etc complete. ( Armstrong Tagular/ Equivalent tiles )	725	Sft		
		<b>FOR FALSE CEILING</b>				

Note:

- 1 All Storages to have Standard Lock & Key for shutters.
- 2 All Storages to have Painted / Polished internally
- 3 All Tables with key board Drawer, shall be with cushioned pam rest.
- 4 All table top to have Wire manager, & 6 mm thk edge polished glass top.
- 5 All Tables to have Foot Rest, & C.P.U shelf .
- 6 False ceiling to be installed in standard way , ( With Fastners for every vertical support )
- 7 All quoted rates has to be included with All taxes, Octroi, Material & labour, & Transport etc , without extra cost.
- 8 All table tops & Low ht Storage top to be Post formed laminated/ PL .
- 9 Partition Glass to have frost film of ht @3'6" in strips as per suggestios.
- 10 Chairs with Hydraulic locking system, coushioned ,P.V.C Armrest, & 1 Year written Company Warranty
- 11 Partition only with only supports ,& not with specs , above false ceiling will not be considered in measurement.
- 12 Air Condition Machines " Blue Star/ Daikin/ Carrier/ Hitachi along with Co Warranty Certificate.
- 13 Rates to be quoted along with chistling, fixing & re doing , levelling & finishing etc.

Sign & Stamp of Contractor.

MATERIAL SPECIFICATION FOR "INDIAN BANK" " Hadapsar Branch.			
	Description	Brand Name .	Code
	S.S Fittings	Dorma/ Ozone / Godrej/As approval	
	Plywood ( 303 Grade Alternate Core )	Green ply/ Century (Sharon )/ Samrat	303 Grade
	Laminates	Donear/ Archid / Equivalent	
		Decolam /Formica /Green / Samrat	
	Formica Code : 1283 Schliersce Beech (wood Grain), 1457 : Spectrum ( Blue)		
	Hardware	Neetlefort/ equivalent/As per approval .	
	Adhesive	Fevicol/ Falcofix/ Carpenter	
	Vetrified Flooring Tiles	As per Approval	
	Dado Tiles ( Toilet )	As per Approval	
	Wood for partition	Salwood.	
	Wood for Beeding	matching as per laminate/ As per approval	
	Paints	Asian/ Dulux/ Berger.	
	Customer Waiting Chairs		
	Perforated powder coated Crome plated finished legs, ( as approved )		
Note			
Material to be procured only after approval of Sample by concerned Authorities & Consultant			
Consultant & Bank Authories hold the Right to Install any of Above Items mentioned.			
Workmanship has to be of Good Quality			
Contractor to co ordinate with other Agencies involved in project timely, to complete the project in stipulated time.			
Equivalent material has to be approved by Architect/ Designer.			

Seal of Contractor.



Quotation for INDIAN BANK "HADAPSAR BRANCH "PUNE.		
ANNEXURE		
Sr No	SPECIFIC WORKS	AMOUNT IN Rs
0	CIVIL WORK ( Flooring & Skirting )	
1	FIX FURNITURE & ALLIED WORKS	
2	PAINTING WORK	
3	FALSE CEILING WORK	
4	AIR CONDITIONING WORKS	
5	ELECTRICAL WIRING & FITTINGS with data cabling	
Total Quoted Amount in Rs		
Quoted Amount :Rs		
<p>Rates are Including Taxes &amp; Duties etc. Sign &amp; Stamp Of Contractor.</p>		