

Bill of Quantity for Furnishing works for Indian Bank
at Etah Branch
Branch Only

Note: The Contractors should quote the rates without G.S.T. No Tender shall be accepted which claims the rates including G.S.T.

1. No offsite prefabrication shall be allowed in any case. All fabrication shall be done at the site after getting the materials inspected by the architect
2. No payment shall be made for any incomplete or unsatisfactory work.
3. The Contractor should strictly follow the Booklet requirements of the Bank including the detailed drawings in the booklet. Any discrepancy between the booklet and the Specifications below should be brought to the notice of the Architect.
4. List of material to be strictly as per the booklet.
5. Cable Managers to be provided in the tables and Counters wherever required.
6. All underframe should be properly treated with antitermite and waterproofing material
7. All Locks in the drawers and doors etc. should be of Godrej
8. All keyboard Trays and Drawers to be on Channel Sliding Mechanism.
9. Rates of Items having glass is including of Etching works and Etching to be provided as per Bank's Design and Specification.

S.No.	Item	Units	Qty.	Rate	Amount
	In case of full height partitions measurement of height shall be taken from the finished floor level upto the level of the false either side of the partition ceiling, in case of varying heights on average height shall be considered.				
	The rate to include provision of extra framework as necessary for skirting & making provision for laying conduit as/drg & directions of site engr./architect. All underframing to be treated with antitermite solution chlorpyrifos based in recommended dilution.				
1	Full ht. Partitions (partly glazed / Unglazed and Doors). P1 & P2	Sq. ft.	490.00		
	Providing and fixing of wooden partitions made out of 50mm x 40mm kail /wood (with anti- termite -Trishul/Pentaphene(STP)) under framing for horizontal (at 0mm, 75mm, 750mm, 900mm, 1500mm, 2100mm, 2550mm and ceiling levels) & vertical (at 600mm c/c approx.) divisions or as per site conditions. It shall be covered with 6mm thick water proof ply (Archid/Century) with 1mm thick laminate, (from 0mm to 750mm and 2100mm to 2550 mm/ceiling levels) on both sides. The design shall have 6mm x 4mm grooves (horizontal or vertical) at various levels, as suggested by the Architect.				
	It shall have 8mm thick etched glass (from 900mm to 2100mm) fixed with teak wood beading (size - 30mm x 20mm, as per profile) with melamine finish. The job shall also include for provision of laying conduits, switch boxes etc. The erection of partition shall include for expansion bolts cleats, clamps bolts, nuts, screws, rivets and other accessories, all complete up to the satisfaction of the Architect.				
	All door opening shall have rebated teak wood framework (size - 75mm x 50mm, as per profile) on vertical (2 Nos.) and horizontal (1 No.) sides, with melamine finish and rebate of 40mm x 12mm, all complete up to the satisfaction of the Architect.				

	It shall also include for door shutters, as per required width and 2100mm high. It shall be made out of 75mm x 25mm kail/chir wood (with anti-termite) under framing for styles, top, middle and 100mm x 25mm for bottom rail. It shall be covered with 6mm thick water proof ply with 1mm thick laminate, (from 0mm to 900mm and other under frames) in shade and pattern approved by the Architect, on both sides. The design shall have 6mm x 4mm grooves (horizontal or vertical) at various levels, as suggested by the Architect.				
	the partition and doors shall have hinges floor springs/sliding arrangement/hydraulic door closer, mortise locks (Godrej make all), etc. The rate shall include cost of all materials, labour, T&P, wastages, etc. required for proper completion of work, all complete to the satisfaction of the Architect. For unglazed partition upto the false ceiling with the same specs. as above without glass for partition.				
2	Low Height Partition P3	Sq. ft.	41.00		
	Same specification as in 1 but P/F half height partition of height 4'-6" with wooden laminate till 3'-0" and 1'-6" height 12 mm thick glass secured with D brackets including all hardware necessary with the same specs. as above.				
3	P4-(Full Ht. 7'-0" for Cash Cabin)	Sq. Ft.	167.00		
	(Cash Cabin)				
	Solid till 4'-0" then GLASS height till 7'-0" then again solid				
	Decorative Grill (12mm thk)-hexagonal opening as per instruction of Bank's Engineer/Architect.) All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak Lipping.				
	Other Specification as per partition P1				
4	C1: FRONT COUNTER	Rft	21.50		
	Counter shall be made up to 19mm plywood finished with 1.00mm thick off- white laminate.				
	The apron shall be up of 19mm ply finished with laminate of approved colour . The counter shall have 1 1/2"x1" wood edge beading with melamine polish.				
	Running counter shall have Drawer unit comprising of two sliding drawers on telescopic channels & bottom openable shutter with all hardware as per schedule of interior, furniture & finishes.				
	The inside of counter & drawer unit will be finished with two coats of synthetic enamel paint & two coats of primer.				
	The counter shall have 1'-0"x3'-0"x1 1/2" thick projected panel at every 4'-6" length & shall be finished with 1mm thick silver metallic color laminate on all sides . These panels above the counter will be provided with digital name plates as per specification enclosed in the branding section of this manual . The panel will be finished with 8mm float glass with SS button refer drwing.				
	The counter shall have CPU trolley , foot rest & cable manager . Refer schedule .				
	Side Credenza /printer table shall be made of 19mm thick plywood & finished with 1mm thick off- white & wenge laminate				
	It shall be two top drawers 4" deep with telescopic channels & two bottom openable shutters with all hardware. Refer schedule of interiors , furniture & finishes.				
	The inside of counter & credenza will be finished with two coats of synthetic enamel paint & two coats of primer				
	The apron shall be made as slant at an angle & made of 19mm ply finished with 4mm thick wenge veneer & 1.0mm thk Silver metallic color laminate . The Apron shall have 4mm thk grooves & should be hand polished. Refer drwg. The veneer will be finished with two coats of melmine polish.				

5	C2: Cash Counter	Rft	5.25		
	Do as above item no. C1 (No side table) cash counter shall have two tops i.e. one at 2'-6" for writing top & other 4'-0" for customer top. upto 7'-0" height (Full front portion and writing top made of 12.0mm ply(as per list of materials) and 3", 12.0mm plain glass slit on customer top) on and above writing top 12 mm plain Glass till 7'-0" should have necessary wooden support and opening edge with proper polish finish for cash and voice transaction.				
6	C3: Server Counter	Rft	5.00		
	Providing and placing in position server counter 2'-6" wide made of phenol bonded 19mm thick commercial board with top front and sides finished in 1.0 mm thick laminate on top, front and sides. The counter to have teak wood moulding as per design. The counter shall be provided with a key board tray, drawer, and a cabinet with a shutter below W-375, H-750mm, Depth- 500mm. .The Keyboard tray to be made in such a way to house both the Keyboard and the Mouse and also to be made of 19 mm thick commercial board completed as per Detailed Drawing and Specification Drawers and a cabinet with a shutter below W-375mm, H-750mm, Depth- 500mm. shall consist of 12 mm thick commercial board for bottom , sides and back of 19 mm thick phenol bonded commercial board with laminate in front and shall slide on tray system provision (sliding mechanism).				
	All the units shall be provided with all the necessary hardware as approved by the Architect such as knobs, handles, Godrej cabinet locks, sliding mechanism as approved by the Architect, Magnetic Catchers Piano brass hinges etc. All unexposed surfaces to have synthetic enamel paint with primer, all complete as per detailed drawing, specifications and directions of the engineer in charge. Footrest in teak wood as per drawing. All exposed edges to be finished in teak wood moulding in clear melamine polish. Locks of drawers other than cash should be of Premium multipurpose lock no.5131. Locks for cuboards doors - for left handed doors: door no. 5011 & for right handed 5012				
7	12 MM THICK ETCHED GLASS FOR CASH CABIN'S AND FRONT COUNTER	Sq. ft.	47.00		
	Providing & fixing 12 m.m. glass in front of cash cabin and front counters with brass clamps including cut out for passing currency as/details. The edges of the glass to be machine polished.				
8	Wicket Gate Solid	No.	1.00		
	(Banking Hall) SS finish Hinges				
	Size-3'-0" X 4'-6"				
	Board-19mm thick (MR Grade IS303)				
	(Incl Door Closer/Stopper/mortice lock)				
9	S1: Storage (Low Height) with locks	Sq.Ft.	22.00		
	Size-2'-6" highX 1'-6"deep, 8'-6" highX 1'-6"deep				
	Ply Wood-19.0mm thick board for side top and door & back 6.0mm IS 303 with shutters, shelf 19.0mm ply				
	Shelf-19.0mm thick ply				
	Handle-Brush finish stainless steel				
	Lock-Vijayan/Godrej				
	Internal surface zinc oxide polish and other required accessories instructed by Bank's Engineer/Architect.				
10	T1: Manager Table with Side Table	No.	1.00		
	Same as above complete work including 12 mm thick glass on top				

	Side Table-3'-0" X 2'-6" X 1'-4"				
	Ply Wood-19.0mm thick for frame work				
	Supports-2" X 2" & 2" X 1.5" CP Teak Wood and beading Patti				
	Drawer-1'-6" wide two drawers and one shutter below the drawers at left side of the table and two drawers at side table and below two shutters				
	Laminate-1.0mm thick approved colour				
	Key Board Tray-Metal INNOFIT make				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	Foot Rest-12.0mm thick Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches 12.0 thick plain glass with edge polish at top of the table (Other Exposed Edge of Ply with half round beading with approved colour polish)				
11	T2 Clerk Table without Side credenza	No.	1.00		
	Size: 4'-0"x2'-6"				
	Other specifications as above				
12	Writing Table & Brochure Holder , Cheque Drop Box ,Suggestion Box with Notice Board .(The work shall be executed as per design and Elevation.)Branch	No.	1.00		
	Providing and fixing in position a writing counter with open storage made of 12mm and 19mm thick ply/ commercial board finished with 1.0mm laminate and teak wood moulding/ lipping with a 6mm glass top with polished edges as per drawing and design. The glass to be of size to fit internally and the 19mm border and 6mm lipping to be flushed with the glass. The storage unit shall consist of vertical space dividers of 12 mm board with 1.0 mm laminate till the glass top for the provision of holding withdrawl/ deposit slips stationery etc. The counters to be held in position around the columns by dash fastners at a height of 3.5/ 4 ft. Notice board with cellotex base & cloth bound in corporate coloured binded with teak wood lipping of 35 by 12 mm.size 1500X1200.All wooden surfaces to be finished in clear melamine polish and all unexposed sides to be finished in enamel paint of approved colour to be approved by the designer all complete as per detailed drawing, specification and direction of the Engineer in Charge.				
13	Column Pannelling & Wall paneling	Sq.Ft.	246.00		
	Providing & fixing in position 2"x2" kailwood frame and finished with 6 mm thk.ply(as per list of Materials) on both sides with 1.0 mm thk. Laminate on top as per instruction of the Architect				
14	Meter Boxing with proper locking system (Only front face to be Measured for payment purpose)	Sq.Ft.	34.00		
	Manufacturing, supplying and fixing box type metre storage with overall depth of 1'6" and height as per the size of the metre. comprising of the following.				
	19mm block board hinged double shutter, height as size of the panel with alround beadings 3/4" x 1/2", powder coated handles, piano hinges, magnetic ball catches, lock, locking arrangement, tower bolts etc., all as per directions.				
	All visible surfaces to be fixed with 1.0mm thick lamination sheet with matching grains & grooves as per instructions				
	All internal & rear surfaces to be painted with two coats of enamel paint over a coat of primer / putty as directed to get a smooth finish.				
15	Shutter boxing with trap door and External cladding	Sq.Ft.	92.00		

	Providing & fixing in position 19 mm. commercial board finished with 1 mm. thick laminates (as per list of Materials and approved colour/shades) on external sides and internal sides to be finished with 2 coats of enamel paint. All works to be done as per the instruction of the Architect.				
16	MAIN ENTRANCE DOOR WITH FIXED ALUMINIUM GLAZING	Sq.Ft.	94.00		
	Door Size-4'-0" X 7'-0"				
	Frame- 6"X2" Aluminium powder coated frame (18 gauge) (All four sides) with approved colour by Bank's Engineer/Architect				
	Glass 5.0/ 6.0mm thick Plane glass with mat film as approved by architect/bank engineer)				
	Floor Spring -Heavy Duty appropriate size (Hyper/Everite make)				
	Handle -'D' Type stainless steel finish both sides with push/pull indication)				
17	False Ceiling Armstrong Tiles	Sq. ft.	492.00		
	Providing & Fixing Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections) false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations. Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc. (Note - : Only the plan area will be measured for the purpose of contractor 's payment , no extra payment shall be given for design)				
18	False Ceiling Gypsum	Sq. ft.	402.00		
	Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop upto 1'6" etc. (Note - : Only the plan area will be measured for the purpose of contractor 's payment , no extra payment shall be given for design)				
19	Acrylic Emulsion with POP Base.(FOR HALL AREA)	Sq.Ft.	1000.00		
	Painting on undecorated / decorated wall and ceiling surfaces with two or more coats of acrylic emulsion(Asian/ Berger make) (as / shade approved by the Architect) of approved brand. It shall include for preparing the surfaces clean, even and smooth with thoroughly brushing with broom, scratching with patti and sand papering respectively, so that the surfaces are free from oil, grease, dirt, mortar droppings & other foreign and loose matter. It shall also include for preparing the surface and filling of holes with plaster of paris before priming coat of whiting / approved primer.				
	The rate shall include cost of all materials such as plaster of paris, whiting /primer, glue (Fevicol), indigo / stainer, brushes, sand paper, patti, dhoti, broom stick, clean water with storage and other containers, labour, scaffolding / ladder charges, cleaning of floors and other sundries etc., all complete to the satisfaction of the Architect.				
20	Vertical Blinds	Sq.ft.	35.00		
	Providing & fixing Sun/Vista make as approved by Bank's Engineer/Architect with runner, thread and other accessories				
	TOTAL				