

INDIAN BANK, ZONAL OFFICE, PUNE – PREMISES DEPARTMENT					
Progress House, 3rd Floor, Pune – Mumbai Road, Shivaji Nagar, PUNE – 411005,					
INTERIOR FURNISHING WORKS OF INDIAN BANK BRANCH AT KOLHAPUR					
Name of the Contractor :					
<b>INTERIORS &amp; CIVIL WORK AT BRANCH</b>					
A	FALSE CEILING	Unit	Qty	Rate	Amount
A1	GYPSUM CEILING	sq.m	35		
	Providing and fixing falseceiling of India Gypsum Company 12.5MM THK HILUX MAKE make which includes fixing of GI perimeter channel of 0.55mm thk having one flange of 20mm and the other flange of 30mm and web of 27mm along the perimeter of ceiling screws fixed to wall/partition with the help of necessary screws and sleeves of 610mm c/c and suspended GI intermediate channel of size 45mmx0.9mm thk with flange of 15mm each from soffit at 1220mm centre with ceiling angle width25x10x0.55mm thick fixed to soffit of GI cleat with steel expansion fastener. Ceiling section of 0.55mm thick having knurled web of 51.5mm and 2 flanges of 26mm each with lip of 10.5mm and then fixed to intermediate channel with the help of connecting at 457mm centre using 12.5mm tapered edge Gyp board is then screw to the ceiling sections either screw 230mm center, all joints to be finished with necessary paper tapes and jointing compounds the finished as directed with 3 coats of luster paint. the rate is inclusive of making openings for light fittings and AC grilles Complete				
	verticlas	rm	100		
A2	TILED CEILING	sq.m	75		
	Providing 600x600 tiles15mm thk armstrong make on T24 grid fixed as per manufacturer specification. Complete.				
	<b>TOTAL: PART A: FALSE CEILING</b>				
<b>B</b>	<b>FURNITURE WORK</b>				
B1	Partitions ( with laminate finish)	sq.m	99		
	Providing and fixing on site in required position Full/half height partition of height as shown on drawing made out Hard wood sections of full size 50mmx50mm treated with anti termite treatment space at maximum 600 mm horizontally and vertically.c/c with proper half notch joint between the horizontal and vertical members and lap joint between two straight members with proper fixing, to be covered with 6mm ply of approved make on either side so as to make a composite partition thickness of 62mm. All exposed periphery of the partition to have 12x75mm agrowood moulding with half round on both sides fixed to the partition finished in natural polish. Partition shall be finished on both sides with 1.0mm laminate of approved shade make and design fixed with Fevicol (SH) and mild steel nails and supports as required for adequate strength. Including all recommended Hardware,Doors,12/6mm thk glass etc.as shown in drawing. Complete.				

SIGNATURE OF CONTRACTOR WITH SEAL

INDIAN BANK, ZONAL OFFICE, PUNE – PREMISES DEPARTMENT				
Progress House, 3rd Floor, Pune – Mumbai Road, Shivaji Nagar, PUNE – 411005,				
INTERIOR FURNISHING WORKS OF INDIAN BANK BRANCH AT KOLHAPUR				
Name of the Contractor :				
B2	Counter	R.M	9.1	
	Providing & fixing at site <b>Counter</b> made out of 18mm thick of size & design as shown in drawing and as per Architect's instructions. The counter shall include one no cash drawer wher CTO is going to sit while other drawers and EBCO Make ready made computer drawer on slides per clerk space. All external finishing to be done in 1.0mm laminate all internal surfaces to be french polished only. All edges shall have 25x 8mm TW/agrowood lipping. The top & front surface of vistors side to in 1.0mm thk laminate . As shown on drawing and directed. . Refer drawing complete.			
B3	Counter front partition	sq.m	3	
	Providing and fixing counter front partition in 10mm thk glass with white film at botton, with opening for cash transcation Complete as shown in drawing.			
B4	TABLES	sq.m	5.5	
	Providing & fixing onsite <b>tables</b> made in 18mm ply for top vertical & front finished in 1.mm thick laminate vertical and 1.5mm laminate on horizontal surface externally, all internal surface in, french polish, item to include all hardware, lipping etc. as shown in drawing and as instructions issued by the Architect. The table shall have computer keyboard drawer with lock and cable ring on top surface. The drawer unit shall consist of drawers as shown in drawing with 12mm ply for front and ebco make drawer sides on slides and back. One footrest in salwood section of 70mmx35mm, Providing multipurpose lock and recessed handles of approved make for each of drawer and shelf. Rubber wood beading for all expose surface finished in natural polish Complete(for payment table top is to be measured)			
B5	Panelling	sq.m	23	
	Providing & fixing on site wall panelling in 6mm ply finished with 1mm laminate. As per design shown and directed by Architect with edge8mm thk agrowoob. lipping finished in polish etc. The panelling shall have gap of 35mm from wall to be provided by 35mmx35mm thk hardwood laminate treated with anti termite for levelling surface and fixed at 600mmx600mm horizotal and vertical ( for concealing conduits pipe) complete.			
B6	Entrance door -	sq.m	8	
	Providing & fixing on site <b>Entrance door</b> Jindal Make Heavy Sections. Aluminum powder coated be inclusive of boxing for the doorfinished in 3.0mmAluminum Composite Panel. The glass shall be12mm clear green tinted glass with Bank Logo in acid etching. Inclusive of all hardware, pivot , floor spring top lock etc. Complete.			

<b>INDIAN BANK, ZONAL OFFICE, PUNE – PREMISES DEPARTMENT</b>				
Progress House, 3rd Floor, Pune – Mumbai Road, Shivaji Nagar, PUNE – 411005,				
<b>INTERIOR FURNISHING WORKS OF INDIAN BANK BRANCH AT KOLHAPUR</b>				
Name of the Contractor :				
B7	Writing Desk	sq.m	1	
	Providing and fixing on site writing desk made in 18mm ply finished with 1.0mm laminate and 12mm clear glass with edge crystal polish supported on s.s studs and caps for holding slips/challans. including dust box shown below. As shown on drawing and directed by Architect. Complete.			
B8	Storages	sq.m	14	
	Providing & fixing <b>Storage units</b> made in 18mm ply front sides horizontal and vertical and back in 6mm ply with front shutter finished in 1.0mm laminate of approved shade and colour agrowod lipping finished in french polish all internal surface shall be finished in french polish only including all necessary hardware such as Handles ( s.s finish) hinges ( brass anodised) Locks (Ebco make) Magnetic catch etc with 18mm plywood shelves at 400mm approx c/c etc . The depth of storage units shall be 450mm.complete.			
B9	Notice board	no	1	
	Providing & fixing on site soft board covered with blazer cloth on 12mm ply as base and 50x25 mm T.W. frame finished in polish.			
B10	Column Panelling	sq.m	23	
	Providing supplying and designing on column panelling on 12mm ply fixed to coloumn with spacers finished with 3.0mm thk ACP panelling. Complete.			
B11	Vertical Blinds	sq.m	10	
	Providing & fixing on site <b>Vertical Blinds</b> of 100mm of vista/mac make of approved shade as drieved and channels fixed as per site conditionsfor measurement window opening shall be considered only.			
	<b>TOTAL: PART B:</b>			
	<b>T O T A L : FURNITURE WORK (A+B)</b>			

<b>INDIAN BANK, ZONAL OFFICE, PUNE – PREMISES DEPARTMENT</b>					
Progress House, 3rd Floor, Pune – Mumbai Road, Shivaji Nagar, PUNE – 411005,					
<b>INTERIOR FURNISHING WORKS OF INDIAN BANK BRANCH AT KOLHAPUR</b>					
Name of the Contractor :					
<b>FURNISHING OF ATM</b>					
no	Item of work	unit	qty	rate	amount
1	False ceiling in gypsum	sq.m	9		
	Providing and fixing suspended false ceiling of India gypsum make which includes fixing of GI perimeter channel of 0.55mm thk having one flange of 20mm and the other flange of 30mm and web of 27mm along the perimeter of ceiling screws fixed to wall/partition with the help of necessary screws and sleeves of 610mm c/c and suspended GI intermediate channel of size 45mmx0.9mm thk with flange of 15mm each from soffit at 1220mm centre with ceiling angle width 25x10x0.55mm thick fixed to soffit of GI cleat with steel expansion fastener. Ceiling section of 0.55mm thick having knurled web of 51.5mm and 2 flanges of 26mm each with lip of 10.5mm and then fixed to intermediate channel with the help of connecting at 457mm centre using 12.5mm tapered edge Gyp board is then screw to the ceiling sections either screw 230mm center, all joints to be finished with necessary paper tapes and jointing compounds the finished with three coats of lustre paint as directed. the rate is inclusive of making openings for light fittings and AC grilles.Complete				
2	Entrance Partitions	sq.m	8		
	Entrance partition wooden specification same as above but with in 12mm glass and door with bank's acid etch logo. Along with 32mm thk flush door with 8mm thk glass ss finish handles, door loser, pivot all hardware. Complete				
3	blank				
4	Panelling	sq.m	18		
	Panelling on 35mmx35mm hardwood frame work 600x600mmc/c grid finished with 6mm thk play and 2.0mm thkACP complete				
5	Notice Board	no	1		
	Providing softboard in framework and 12 mm ply backingfinished in maroon colour blazer cloth				
6	Display Panels	no	1		
	Acrylic display panel in double 8mm thk arcylic sheets on s.s studs ( size 600x750mm)				
7	Shutter boxing	sq.m	10		
	in 19mm thk marine ply finished in 1.0mm thk laminate with conceled aldrops and aeces door for shutter maintainence.				
<b>T O T A L ( interior) of ATM</b>					
<b>T O T A L ( interior) of Branch</b>					
<b>Grand TOTAL FURNISHING WORKS (BRANCH +ATM)</b>					
<b>Less Discount if any - % Rs.</b>					
<b>Total Interior Furnishing Works Rs.</b>					
<b>Total amount in words Rupees</b>					

SIGNATURE OF CONTRACTOR WITH SEAL